




XFEL cavity production tests and comparison before/after module assembly

TTC Meeting KEK
Dec 2-5, 2014



**Detlef Reschke, Denis Kostin, Laura Monaco, Nick Walker, Mateusz Wiencek,
Kirk Yamamoto**
for the Cavity- and Module Team




- Vertical Acceptance Test
- Module Test
- Changes in Cavity Performance from Vertical Test to Module Test

- More in the “Module Test WG” by Mateusz and Nick

Vertical tests at AMTF




Number of vertical tests (history)



- ALL vertical acceptance tests counted (incl. hall3 + cavities with limited acceptance + return from Saclay + ...)


Vertical Tests per Month



Average:
> 9.5 tests per week
 since Oct 2013


■ EZ
 ■ RI

Reminder: Cavity Surface Preparation



Two schemes for the final surface treatment:

- E. Zanon: **Final 10µm BCP** (“BCP Flash”)
- Research Instr.: **Final 40µm EP**




At both companies all surface preparation infrastructure in full and standard operation!

Close **supervision** of infrastructure, processes, procedures and handling by DESY + INFN Milano

- No performance guarantee** results in:
- the risk of unexpected low gradient or field emission is with DESY
 - **responsibility for re-treatment at DESY**

Vertical acceptance tests




- Analysis of vertical acceptance tests includes
 - Series Cavities
 - “HiGrade”-Cavities
 - NO infrastructure commissioning tests

- So far delivered: 512 cavities (Nov 30)
- Total RF tested: ~500 cavities (Nov 30)

- Data analysis group:
S. Aderhold, L. Monaco, D. Reschke, (D. Sertore), J. Schaffran,
L. Steder, N. Walker, K. Yamamoto
+ XFEL cavity data base team: V. Gubarev, D. Gall, S. Yaser
- Analysis fully based on XFEL cavity data base

- Status of vertical tests analysis: **Nov 10, 2014** (~470 cavities)

RF test conditions



- **Cavity “full equipped” refers to**
 - Dressed with He-tank (except of “HiGrade” cavities)
 - Equipped with fixed High Q-antenna, Pick-up and two HOM-antennas

- Only Q(E)-measurement at 2K + fundamental mode frequencies
 - Remark:
 - no $Q_0(T)$,
 - no $Q_0(E_{acc})$ in fundamental modes,
 - no $Q_0(E_{acc})$ at various bath temperatures
 - All cavities checked for Q-disease by parking at 100K

- Measurement with fix coupling
 - => over-coupled at low and medium gradients
 - => error impacted by $\beta > 1$ coupling

- “Long pulse” operation (few seconds RF on); not full cw
(in order to protect HOM feed-throughs)

- Up to now no administrative radiation limit

Acceptance Criteria for Vertical Test

■ Acceptance criteria:


“Usable gradient”

- INITIAL: >26 MV/m (10% margin to required average design operating gradient)
- NEW (after analysis of retreatment results in May 2014):
 > 20 MV/m (for optimized number of retreatments and retests)


■ Definition of usable gradient:

- Gradient of Quench or
- Gradient at Unloaded $Q_0 < 1 \times 10^{10}$ or
- Gradient at X-ray level:
upper detector $> 1 \times 10^{-2}$ mGy/min; lower detector > 0.12 mGy/min
(different location/distance of detectors)

Results: Maximum Gradient “As received”



- Analysis: No selection done, no cut




	RI	EZ	Total
Tests	182	234	416
G_{AVG} (MV/m)	32.9	29.1	30.8
G_{RMS} (MV/m)	7.6	7.	7.5
yield @ 20MV/m	91%	88%	89%
yield @ 26MV/m	87%	76%	81%
yield @ 28MV/m	84%	69%	75%

- Reminder: RI applies “Final EP” => higher gradients expected
- Comment: “Missing” cavities with status “as received”?
=> About 50 cavities sent back to vendor (new status “retreatment at vendor”)

Results: Usable Gradient “As received”

Usable Gradient:

Usable Gradient





	RI	EZ	Total
Tests	182	231	413
G_{AVG} (MV/m)	28.6	25.5	26.9
G_{RMS} (MV/m)	7.9	6.9	7.5
yield @ 20MV/m	87%	79%	83%
yield @ 26MV/m	71%	53%	61%
yield @ 28MV/m	63%	41%	51%

“not passed”:

- re-treatment at DESY; partly still to be done
- “special” handling e.g. retreatment by vendor accepted

Results: Trend of Usable Gradient "As received"






Improvement of usable gradient?

Impact of Re-Treatment

- Analysis of ~80 cavities after **first** re-treatment => **typically HPR**
- Pairs of vertical tests of same cavity taken => before vs. after RT
- Reasons for re-treatment:
 - **mostly field emission** (61 cavities)
 - quench at “low” gradient (7 cavities)
 - low Q-value at low gradient (6 cavities)
 - leak (2 cavities)
 - other (6 cavities)
- **Remark:**
 - Higher priority on curing “field emission”, “low Q”, ...
 - Quench gradient > 20 MV/m (often) accepted also for initial acceptance criteria
- Improved performance in the last months => to be confirmed

Re-Treatment: Gradients






Usable gradient (before) [MV/m]

Usable gradient (MV/m)

	Before	After
Tests	81	82
G_{AVG} (MV/m)	18.5	26.6
G_{RMS} (MV/m)	6.3	6.8
yield @ 20MV/m	40%	83%
yield @ 26MV/m	10%	56%
yield @ 28MV/m	7%	50%


Re-Treatment: Q-Value at 4 MV/m



	avg	rms	SE
before	2.02	0.36	0.04
after	2.4	0.38	0.04

Remark: Trend of Q-values stable over production time

Other cavity related “challenges”




15

- **He-Tanks:** One critical dimension NOT well-defined in DESY drawings
=> not all positions in module possible
=> **solved:** cavities shortened by 1mm + “sorting” wrt. position in module
- **2-phase line (longitudinal weld)** does not fulfill PED-requirement
=> **solved, but significant effort;** 2-phase lines on affected cavities + He-tanks exchanged
- **Q-values of critical HOM** out of expected range (several cavities):
=> reason still under investigation
- **Scratches by wrong tooling + EP electrode** at iris (several cavities)
=> **solved:** identified with high resolution optical inspection + fixed for future cavities (affected cavities require rework procedure!)
- **Splatters (+holes) during equator welding** (several cavities)
=> instable parameters of EB-machine; rework procedures in application/preparation
- **3D- Transfer measurement** (reference for string alignment) incorrect
=> **solved?:** improper measurement procedure identified

Other cavity related “challenges” II

- “Special” (physically challenged) cavities at both vendors (several cavities)
=> individual time consuming rework procedures
- Suspicious of cold leaks
=> still open; very often not confirmed at 300K + in re-test after reconnection
- Post-Documentation batch of first series cavities + “special” non-conform cavities
=> work will be finished end of 2014/beginning of 2015

Vertical test => string assembly




17

- **Sorting of cavities for string assembly** according to
 - gradient
 - mechanical constraints**=> string proposal**
- routine weekly transport in boxes to Saclay => very reliable, but **shock log data still not fully understood**
- **Cavities up to XM31 at Saclay**



Module Test at AMTF



- 22 modules arrived with 13 modules tested (XM-3 excluded)
- 3 horizontal test stands in full operation



Module Test Procedure


- **Detailed test procedures** described in detail at last TTC Meeting + by Mateusz Wiencek in WG
- Relevant for cavity performance:
 - **Flat-top** measurements of **individual** cavities
=> **gradient** + x-ray values
 - **Heat load** measurement at 15 MV/m + 23.6 MV/m of **all** cavities
=> **average Q-value** + x-ray values
- **In-situ Processing** done in 1. Flat-top measurement (followed by 2. FT-measurement for confirmation)
if necessary: add. **processing with short pulses** (750 μ s + 100 μ s)
- **Diagnostics** at Module Test Stand
 - Quench detection system
 - **Two x-ray detectors** at each end of the module
(- dark current monitors => still under commissioning)

Figure of Merits of Module Test

- **Maximum Gradient** given by:
 - quench limit
 - rf power limit at ~ 31 MV/m
 - (- x-rays)


- **Operational Gradient** defined by:
 - quench limit – 0.5 MV/m
 - rf power limit at ~ 31 MV/m
 - x-ray limit of 10^{-2} mGy/min (at one detector)

- **No Q-value measured for individual cavities!**




Module Test Results

Comparison of Max. and Operational Gradient for CM test at AMTF




Preliminary data; results are not published

Module Test Results II




- Average Operational gradients of modules with individual rf distribution
- All modules can be operated above 23.6 MV/m !!



Successful technology transfer to CEA Saclay + Alsyom


Module Test Results III

- Averaged Q-values at 23.6 MV/m of modules from heat load measurement (in case of cavities with lower gradients => reduced average gradient)
- All modules above close to or above 10^{10} .




Module Test Results: Limitations

- No hard Multipacting barriers => fast processing (if any; <1h per cavity)
- Limitations of Maximum + Operational gradient (XM-2 to XM13: 13 modules, 104 cavities):




Changes in Cavity Performance from Vertical Test to Module Test



- Hans: “too often we are disappointed by a decreased gradient of single cavities”
- Difference of **maximum gradient** from module test and vertical test

$\Delta E_{acc}(\text{Mod-Vert})$ vs. Module



Remark:
If Module Test is limited by available RF power (~ 31 MV/m)
=> **Ignore the decrease of maximum gradient** (set $\Delta E_{acc} = 0$)

Changes in Cavity Performance from Vertical Test to Module Test


- Decreased performance has been observed after module assembly at DESY (FLASH modules), Fermilab (CM-1), KEK (S1-global), Saclay (XFEL modules)
 - => not site dependent
 - => typically 0 – 3 cavities affected
 - => more **quench**, than field emission limited (see below)
 - (- enhanced field emission => typically explained by particle contamination during handling or improper venting condition
 - **reduced Quench gradient =>???)**

- Discussions and presentations at TTC Meetings (e.g. Beijing 2011 + Saclay Nov 2014), SRF 11, ...

- Intensive analysis was done for (at least) FLASH modules (presented at TTC Dec 2011)
 - => see below

Comparison of field calibration constant k_t

- Crucial is correct calibration of field calibration constant: k_t
 $\Rightarrow E_{\text{acc}} = k_t \cdot \sqrt{P_{\text{trans}}}$
- Error of ~10% possible \Rightarrow not sufficient to explain decrease of gradient

Comparison of K_t between V.T. and C.T.

Comparison of gradients: vert vs. hor

■ What gradient to compare?

- different **rf power limits**
- different **x-ray measurement arrangement** (see D. Kostin, SRF 2011)
- pulsed vs. “nearly cw” operation
- **Q-value** cannot be measured for individual cavities in module test

=> Given “usable gradient” of vertical test and “operational gradient” of module test **cannot** be compared simply 1:1

■ **Quench** is clear cavity limitation => **ok**


(but pulse operation may lead to little higher quench gradient by shifting the thermal limit)

■ **X-ray** limitation is less exact



e.g. XM13, C7+8 with a x-ray limitation of “usable gradient” in vertical test at ~25 MV/m do **not** show significant x-rays in module test up to 31 MV/m

=> **nevertheless significantly decreased performance is detectable**


■ **Q-value** important for heat load of accelerator, but not to measure for individual cavities in module test => ??




- Cavities with decreased gradient performance in XFEL-modules
- No dependence on k_t
- Critical decrease to operational gradient in a module less than 25 MV/m happened to 17 cavities, or 19% (out of 88 cavities)




Observations: Gradient distribution




- Decreased maximum gradient:
 - nearly all cavities limited by quench
 - distribution of gradients: not always limited around 20 MV/m!



Observations: Position in module



- Dependence on position in module + kind of limitation:



- **Operational gradient:**
About 2/3 limited by quench!
- **Maximum gradient:**
Nearly all limited by quench!


Additional information:
No correlation between position and amount of degradation

- Comparison to **FLASH-modules** (with leak check after pos. 4):

Position of Cavity in modules	P 1	P 2	P 3	P 4	P 5	P 6	P 7	P 8
No of cavities degraded @ position	2	2	5	1	2	4	2	1

- Middle positions affected stronger ???

Possible explanations: TTC 2011



- From **TTC 2011** for 3 analyzed cavities:
 - “**No differences to other cavities** in line found in assembly log book in respect of
 - particulates loading
 - assembly times
 - leakage found
 - RGA”
 - No hint for defect of any hardware for cleaning, pumping, etc.

- => “**NO provable explanation for degradation w/o FE**”

- After removal of He-tank: vertical test with SeSo + T-Map followed by Optical Inspection:
 - **Z88 recovered w/o any treatment !!!???**
 - **AC127 with dark spot at equator 2**
 - **Z133 nothing special found at (unsafe?) quench location**

- => **reinvestigation under discussion**

Possible explanations

- TTF special topic meeting at Saclay (Nov 2014)
- **Transportation** (DESY => Saclay => DESY)
 - transportation tests with individual cavities => no indication
 - transportation of individual cavities from vendors to DESY in identical boxes => no degradation (?)
 - ongoing: Retest of 9 cavities after transport to Saclay and back to DESY
- **Critical cleanroom processes** from vertical test to module test:
 - cleanroom assembly of power coupler (procedure + “dirty” coupler)
 - cleanroom connection of string incl. “flushing” with ultrapure gas
 - several pumping and venting cycles
- **Other possible explanations:**
 - improper cooling of HOM's => unlikely (no “recovery effect“ observed)
 - “hard” Multipacting => no indication (see above)
 - strong processing event in first run causing material displacement => no indication, but difficult to distinguish to “normal” processing

Verifying / excluding explanations

- **Transportation**: Retest of 9 cavities after transport to Saclay and back to DESY
=> Result??
- **Reproduce cleanroom procedures** several times with individual cavities (w/o tank) and check performance in vertical test (incl. diagnostics)
=> for XFEL difficult due to man power + infrastructure limitation
- Restart **individual horizontal tests**
=> for XFEL NOT possible due to man power (+ infrastructure) limitation
- **Disassembly of modules** and analysis of individual cavities
=> done for TTC 2011 => some reinvestigation necessary?
=> for XFEL **NOT possible** due to schedule
- More ideas???


- Vertical cavity testing, module testing and all work flows at AMTF are well established + in full operation
- Vertical acceptance test performance is well above specification
- Re-treatment gives significant improvement => worthwhile effort!
- String and module assembly procedures successfully transferred to CEA Saclay + Alsyom resulting in good module results above specification with room for improvement
- No explanation for cavities with decreased performance

Thanks to all colleagues of

- E. Zanon
- Research Instruments
- CEA Saclay /Alsyom
- INFN Milano
- IFJ-PAN
- DESY

for their material, information and support






Additional slides



Vertical test => string assembly II



38

- **Mechanical constraints:**


- **He-Tanks**

One critical dimension NOT well-defined in DESY drawings

=> assembly not possible at all positions in module

Solution:

- cavities shortened by 1mm
- “sorting” wrt. position in module



- **Q-values of critical HOM** out of expected range (few cavities):

- reason with RI under investigation
- sorting in dedicated module

2-Phase Line (Service Pipe) Welding done in Routine Operation

