


# ***Cryogenic performance in STF2 cryomodule tests***

KOJIMA Yuuji and NAKAI Hirotaka  
High Energy Accelerator Research Organization (KEK)

in collaboration with

HARA Kazufumi, HAYANO Hitoshi, HONMA Takuya,  
HOSOYAMA Kenji, KAKO Eiji, KIMURA Nobuhiro, KONDO Yoshinari,  
NAKANISHI Kota, YAMAGUCHI Seiya and YAMAMOTO Akira (KEK)

# STF2 CM-1 + CM-2a Cryomodules




- Head unit : connection to cryogenic system
- STF2 CM-1 : 8 cavities + 1 sc quad magnet fabricated at FNAL
- STF2 CM-2a : 4 cavities
- End unit : liquid helium level detection

# Concept of STF2 Cryomodules

- Design of STF2 CM-2a modified to check CW operation feasibility
  - Larger 2K 2-phase supply line ( $\phi 76.3 \rightarrow \phi 89.1$ )
- Electric heaters attached to cavity tanks to simulate dynamic heat load from superconducting cavities
- Usage of liquid nitrogen for 80K thermal shield instead of 40K thermal shield cooled with helium gas
- Conduction cooling of sc quad magnet
  - Aluminum strips from 2K 2-phase pipe

# Cool-down Curve



# Measured Static Heat Loads

- Total heat load at 2 K :  $\sim 29.5$  W
  - 2K cold box (2K pot) :  $\sim 1$  W (measured in previous test)
  - Cavities + 2K cold box :  $\sim 19.9$  W
  - Cavities :  $\sim 18.9$  W (total of 12 cavities)  
 $\sim 1.6$  W/cavity (average value)
  - SC quad magnet + pipes :  $\sim 9.5$  W

# Summary

- First cool-down of STF2 CM-1+CM-2a completed
- Cryogenic system did work in cool down of STF2 CM-1 and CM-2a cryomodules
- Dynamic heat load from cavities could be simulated with electric heaters up to 30 W
  - Helium pumping system cannot sustain temperature of 2K with simulated heat loads above ~ 20 W
- No difference in cryogenic conditions with simulated dynamic heat loads in STF2 CM-1 and CM-2a in this measurement
- Flooding of superfluid helium into GRP observed occasionally

# ***Extra Slides for Q&A***






# STF2 CM-1 + 2a



20141202/TTC2014/STF2Cryomodules/KOJIMA & NAKAI




# STF Cryogenic System Configuration




# *Equipments Installed*

- Two wire position monitors to measure vertical displacement of cavities and gas return pipe (CM-1)
- Eight optical windows for Laser displacement sensors to measure vertical displacement of gas return pipe (CM-1)
- One beam position monitor (CM-1)
- Two potentiometers to measure axial displacement of gas return pipe (CM-1)
- One superconducting liquid helium level sensor in end unit

# STF Cryomodules



Optical Windows



STF CM-1

STF CM-2a

## **Vacuum vessel of STF CM-1 consists of 3 parts**

- Established technique and machine tools
- Manufactured in limited period
- Limitation of delivery opening of the tunnel

# Current Schedule

- Assembly of STF CM-1 complete in January, 2014
- Assembly of STF CM-2a complete in May, 2014
- Connection to cryogenic system complete in June, 2014
- Completion inspection by the prefectural government in July, 2014 → Passed already
- First cool down of STF CM-1 and CM-2a in October and November, 2014 (capture cryomodule excluded)
- First excitation of sc quad magnet with Fermilab colleagues in November, 2014