

DESY-II Testbeam Facility



Marcel Stanitzki


for the

DESY Testbeam Coordinators



The DESY Testbeam Facility

- Facility fed by DESY-II synchrotron
- Bremsstrahlungs / conversion beam with E_e up to 6 GeV
- Beam momentum steered by magnet current by test beam user.
- Rates depending on beam line, energy, target material, collimator setting and operation.







Beam availability

- DESY-II synchrotron
 - $\sim 99\%$ uptime during schedules runs
 - Main purpose: Injector for PETRA-III
 - Test Beam is parasitic user
- Beam structure
 - 1 MHz clock
 - Basic magnet cycle 12.5 Hz (accelerating from 450 MeV to 6.3 GeV)
 - 1 bunch per fill (30 ps)
- Interruption during Extraction for Petra (sec-min)
 - Otherwise almost DC beam (no spill structure)



Unique Infrastructure at DESY

- TB21 & 22 both provide a pixel telescope
 - Complete Package (Hardware, Trigger, Reconstruction software)
- Dipole Magnet in TB 21
 - For tracking studies
- 1 T Solenoid for putting detectors in a magnetic fields
 - Internal diameter 85 cm
 - Moveable
 - Possible to install pixel telescope



Current Status


- Shutdown 2014
 - March-December 2014
- End of Shutdown was driven by PETRA-III extension schedule
 - PETRA-III will start commissioning in February 2015
- Beam in DESY-II since last week
 - Smooth Start-up after 9 month
- First users:
 - CMS Pixels starting this week
- Call for Users
 - In November 2014 for the Jan-Jun 2015 period



DESY-II Test Beam Facility 2015

- Call for beam time
 - Jan-Jun 2015
- 22 Groups responded
 - 30 weeks of beam time
 - LHC community : 55 % of the groups
- EU-funded infrastructure a big success
 - 68 % of groups request EUDET/AIDA Telescope
 - 28 % request the EUDET-PCMAG solenoid


Projects






More details

Weeks



Infrastructure requests





Shutdown Projects 2014

- The shutdown gave us the opportunity to do some improvements (and some cleaning up)
 - New flooring in the areas
 - DACHS
 - Laser Alignment System
 - Upgraded Vacuum pumps
 - Beam Monitors
 - New Carbon Fiber Targets
 - New Beam Magnet controllers and PC's
 - Cameras in the areas (already in 24/1 now everywhere)
 - And by popular request : new phones



Changes for the Users - DACHS

- Several changes mandated by Safety Dep.
 - Interlock handling
 - Enforcing of training checks
- Most important
 - DACHS cards are now mandatory for all Users
- DACHS controls
 - Access to the huts
 - Part of the Interlock
- As DACHS cards will have information on safety training (a.k.a. No Training → No Access)



DACHS Con't

- First time only
 - Users need to register in DESY Database (PIP)
 - Needs to happen before coming to DESY
- DACHS card
 - Valid ~ 10 years
 - Personal ID
- Safety course
 - Annually
 - Training Status is stored in DACHS System





Registration


- Registration will be handled by our Indico system
- If you don't have a DACHS card
 - System will generate the form for you
 - Sign it and send it (best a week before)
 - Indico system does have all info
- Upon arriving at DESY
 - Go to V1 (Geb 6, Zi 111) and get your picture taken and a DACHS Card issued
- Attend Safety lecture
 - Coordinators will give you access to the areas



The end of Controlled Access (ZZ)

- As per Directive from D3 and the DESY directorate
 - Controlled Access/ZZ is no longer permitted at the DESY Test Beam
- This means
 - Every access requires breaking and re-enabling the interlock
 - Setting the interlock is 2 min operation, no major operational impact
- For TB24/1 a separate set of rules applies
 - Due to PCMAG magnet interlock

Laser Alignment system



- Now provided in each area
 - Should simplify aligning your setup with the beam

Test Beam Monitors



- Test Beam Monitor
 - Simple: Two Scintillators in Coincidence
 - Used by the control room to monitor beam in the area
 - Users have also access to signals
 - Currently being commissioned



Other changes

- New flooring in the area
 - Major improvement
- Radiation Safety department will now insist on proper documentation (English/German)
 - They'll not accept shipments without this information
- Update to the infrastructure
 - Improved power outlets
 - More Ethernet ports



Scientific Accounting

- Acknowledging the use of the facility:
 - The research leading to these results has been carried out at the Testbeam Facility at DESY, a member of the Helmholtz Association (HGF)
 - Adding parts of should be fine ;-)
- Scientific Accounting
 - We now have to keep track of conference talks, proceedings, papers that have used the DESY Test Beam
 - HGF likes to see the “impact” of the facilities it funds
 - Please provide the necessary information



AIDA 2020

- AIDA2020 has just been approved
 - Successor of AIDA
- DESY-II Test Beam Facility
 - Increased Funding for Transnational Access
 - Support for Telescopes
 - Modest improvements to the infrastructure
- Grant preparation phase
 - AIDA2020 will be up and running in spring



Outlook 2015

- The plan is to run till ~November 2015
 - Again driven by PETRA-III
- Once this is finalized
 - Call for Users for the second half of 2015
- Stay tuned



How to apply for beamtime

- Send an email to
 - testbeam-coor@desy.de
- Testbeam coordinators will try to accommodate everybody
- There is an annual call for testbeam time
 - Subscribe to
<https://lists.desy.de/sympa/subscribe/testbeam-info>
- Lots of information at
 - <http://testbeams.desy.de>
 - Latest Schedule
 - Updates, Instructions



Summary

- DESY-II Testbeam facility offers
 - 3 beamlines with 1-6 GeV electrons
 - Unique Infrastructures
- 2014 Shutdown is finished
 - Many improvements to the Infrastructure
- Starting up in January 2015
 - Run start tied to PETRA-III Schedule
 - Some operational changes compared to 2014
- Foresee to end the run in November 2015
 - Details and Call to follow !