BCM1-F Status

Wolfgang Lange


Words and their meanings


- Background Radiation Monitoring consists of
 - BCM1-F/L (Beam Conditions Monitor, *Fast/Long term*)
 - 1-L polycrystalline diamond sensors with 1cm²
 - 1-F singlecrystalline diamond sensors with 0.25 cm²
 - BSC (Beam Scintillator Counters)
 - more subdetectors (active and passive devices, here not mentioned)
- Contributions from DESY:
 - Comissioning of BCM1-F (4 detectors on either side of pixels)
 - Measurement (characterization)
 of (pCVD) diamond sensors for BCM1-L
 - Support for installation of BCM1-F/L, running in
 - Software to read out BCM1-F and to publish data
 - Tools for running and diagnosis (soft- and hardware)

Performance of BCM1-F Module

- all modules measured (10 preamp+sensor + 10 opto-hybrids)
 - readout CMS-like with fibres
 - measurement with pulses and ⁹⁰Sr source
 - measurement of current consumption and leakage currents


M10_3_400V_t_hiStat






BCM1-F/L Module (L-shape)


- all L-shapes with modules are mounted (currently 8+1)
 - BCM1-F with diamond, preamp, cable and screening hoods
 - analog optohybrid (AOH) with mono mode fibre
 - encapsulated diamond sensor of BCM1-L



Mounting and Testing


- Assembled modules mounted onto carriages and tested again
- CMS like environment (power supplies, cables, distributions)






Mounting in CMS

• Carriage -> Installation Cassette -> final position in CMS



Patch panel 0

- Patch Panels assembled and tested: each has 2 BCM1-F/L channels
 - generation of test puls ok (both polarities visible)
 - power distribution ok (HV, LV)
 - HV and LV filters ok



Status of readout

- use of Optobahn receiver module
- signal distribution electrically
 - either use of charge sensitive (integrating) ADC -> spectra
 - or use of sampling ADC (2ns period -> 500 Ms/s) -> CMS
- sampling method with signal processing gives comparable results
- sampling ADC read out via optical link (PCI card inside PC)
- dump as binary data to the local disk, see also "software"
 - -> interface to CMS "under construction", publish & subscribe
- investigation of TDC planned, integration into readout planned

Summary and outlook

- BCM1-F frontends needed a very careful mounting (~3h each)
- no general problems known currently
- cross check BCM1-F with BCM1-L done -> ok
- ready to install into CMS (end of June ???)