




Laser-based Synchronization System Installation

Cezary Sydlo
on behalf of the LbSync Team



24th April 2015
DESY



Optical Synchronization Team within MSK

2

Bunch Arrival Monitor
Hardware & Electronics
RF to laser locking
Laser to laser locking
Coordination
Fiber Link Stabilization

Marie Kristin Czwalinna
Matthias Felber
(Thorsten Lamb)
Jost Müller
Cezary Sydlo
Falco Zummack

Now @
FLASH + FLASH2
 & XFEL

3	=>	18
a lot	=>	even more
0	=>	14
3	=>	16
10	=>	42


5-6 times increased!

Laser to RF (REGAE/ANGUS)
CW Fiber Link Stabilization
Control Theory
Dedicated electronics
Software


Mikheil Titberidze (PhD student)
Szymon Jablonski (PhD student)
Michael Heuer (PhD student)
Ewa Janas (PhD student)
Pawel Predki (PhD student)
Tomasz Kozak (PhD student)

Dependent on strong interaction with LLRF


LbSync at the European XFEL



European X-Ray Free-Electron Laser


Courtesy:
M.K. Czwalińska

- XTIN: up to 24 link stabilization units at injector site
 - 2 links for experimental hall (continuous out-of-loop check)
- XHEXP: 2nd synchronization room in the experimental hall
 - Slave laser oscillators
 - 8 link stabilization units (space for up to 20)



- **Huge development effort for the European XFEL**
 - Learn from FLASH
 - Exploit gathered experience for European XFEL developments
 - Test new developments at FLASH
 - Allow reflow of improvements to FLASH, keep systems identical
- **The number of installations and its locations is significantly increasing, but personnel is limited**
 - Simplify commissioning and maintenance
 - Unify and standardize systems
 - Stay modular

Developments for LbSync (1/2)




- **Link Stabilization Unit: Tested and in production**

- LSU V3.2 (SMF only) => V4.0 (PMF)
- Long Delay-stage
- Balanced photodetector: Improved performance
- Link electronics: Integrated and improved




LSU V4.0



4ns Delay stage

- **Bunch Arrival Monitor: In progress**

- 40GHz Pickups: Improved performance
- Frontend



40GHz pickup

- **RF-to-laser lock (REFM-OPT): More testing**


- New development

- **Laser-to-laser (L2L): In testing phase**

- New set-up for all laser system




REFM-OPT: 3HE 19"



L2L setup



Developments for LbSync (2/2)



6


- **MTCA cards**

- AD84, FMC25, FMC20, PZT4, MD22, AD16 (for link locking): Testing
- LASY, LASIO (dedicated laser locking cards): In progress





- **Electronics**

- Laser diode driver: Tested and in production
- Laser to RF lock modules: Tested and available
 - (with Laurin AG)
- Specialized electronics: Tested and in production
 - FRED (with LLRF/WP02)
 - TMCB (with LLRF/WP02)
 - ...




Link Stabilization results



- **Prototype tested in lab 26a with 3.6km PM fiber installed in hall1**
 - **Realistic, uncontrolled ambient conditions for meaningful results**

C. Sydlo et. al. "Femtosecond timing distribution for the European XFEL", Proceedings of the 36th International Free Electron Laser Conference FEL 2014, August 25-29, 2014, Basel, Switzerland

Critical points




DONE!

- Most developments finished successful
- Received 21km PMF cable for XFEL
- Synchronization room “Laserraum1” mostly finished
- Optics installation on superinvar optical table started




- Progress on L2RF & BAM is limited by personnel
 - Relocate workforce from finished developments
- Software (it works, but is far from final state)
- PMF cable installation: “blowing in fibers” must work!
- Operation and maintenance of synchronization in the future.
A lot of additional systems with FLASH II and XFEL!

Next steps



- **ASAP**
 - Install 4.2km PMF loop over Osdorfer Born (reused later for XHEXP)
 - Commission and check Synchronization system
- **Till end of 2015**
 - Finish all tunnel installations (REFM-OPT and BAM Frontend)
 - Install all stabilized links in XTIN “Laserraum1”
 - Collision with FLASH II work?
 - Ready for installations and comissioning in Subsync-Hutch/XHEXP
- **From April 2016**
 - Build up Subsync-Hutch
 - Use gathered experience for commission of links in HEXP
 - Use laser-to-laser locking as soon as experimental laser operate

About 30 mirrors set, more than 200 still to come



Thank you



XTIN UG5 “Laserraum1” (17. April 2015)