


# Status of the LHC and commissioning plans

by Helmut Burkhardt / CERN for the LHC team

- **Short introduction - main challenges**
- **LHC status, 1st experience with beams and status following the incident**
- **Commissioning steps and expected beam parameters**

**Acknowledgements :** LHC team, mentioning in particular Lyn Evans, the former LHC and current sLHC project leader, and Steve Myers director for accelerators K-H.Mess and R. Schmidt for advice, in particular on the issue of magnet interconnects and quench protection, O. Brüning & M. Giovannozzi on optics and commis, M. Ferro-Luzzi on physics program, R. Bailey on commis.




## High design Centre-of-mass energy of 14 TeV in given (ex LEP) tunnel

- Magnetic field of 8.33 T with superconducting magnets
- Helium cooling at 1.9 K
- Large amount of energy stored in magnets
- “Two accelerators” in one tunnel with opposite magnetic dipole field and ambitious beam parameters pushed for very high of **luminosity of  $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$**
- **Many bunches with large amount of energy stored in beams**


## Complexity and Reliability

- Unprecedented complexity with 10000 magnets powered in 1700 electrical circuits, complex active and passive protection systems, ....
- 
- **Emittance conservation**  $\varepsilon_N = \beta \gamma \varepsilon$ , related to phase space density conservation, Liouville constant “intrinsic” normalized emittance  $\varepsilon_N$ , real space emittance  $\varepsilon$  decreases with energy
  - in absence of major energy exchange in synchrotron radiation / rf damping
  - clean, perfectly matched injection, ramp, squeeze, minimize any blow up from: rf,
  - kicking beam, frequent orbit changes, vibration, feedback, noise,..
  - dynamic effects - persistent current decay and snapback
  - non-linear fields (resonances, diffusion, dynamic aperture, non-linear dynamics )


# The total stored energy of the LHC beams



Nominal LHC design:  $3.2 \times 10^{14}$  protons accelerated to 7 TeV circulating at 11 kHz in a SC ring





**LHC: > 100 × higher stored energy and small beam size: ~ 3 orders of magnitude in energy density and damage potential. Active protection (beam loss monitors, interlocks) and collimation for machine and experiments essential. Only the specially designed beam dump can safely absorb this energy.**



controlled experiment with beam extracted from SPS at 450 GeV in a single turn, with perpendicular impact on Cu + stainless steel target

450 GeV protons →

r.m.s. beam sizes  $\sigma_{x/y} \approx 1$  mm



**SPS results confirmed :**

**$8 \times 10^{12}$  clear damage**

**$2 \times 10^{12}$  below damage limit**


for details see V. Kain et al., PAC 2005 [RPPE018](#)

**For comparison, the LHC nominal at 7 TeV :**

**$2808 \times 1.15 \times 10^{11} = 3.2 \times 10^{14}$  p/beam**

**at  $\langle \sigma_{x/y} \rangle \approx 0.2$  mm**

**over 3 orders of magnitude above damage level for perpendicular impact**





	LHC	LEP2
Momentum at collision, TeV/c	7	0.1
Nominal design Luminosity, $\text{cm}^{-2}\text{s}^{-1}$	1.0E+34	1.0E+32
Dipole field at top energy, T	8.33	0.11
Number of bunches, each beam	2808	4
Particles / bunch	1.15E+11	4.20E+11
Typical beam size in ring, $\mu\text{m}$	200 – 300	1800/140 (H/V)
Beam size at IP, $\mu\text{m}$	16	200/3 (H/V)

- **Energy stored in the magnet system:** **10 GJoule** Airbus A380, 560 t
- **Energy stored in one (of 8) dipole circuits:** **1.1 GJ (sector)** at 700 km/h
- **Energy stored in one beam:** **362 MJ** 20 t plane
- **Energy to heat and melt one kg of copper:** **0.7 MJ**

the LEP2 total stored beam energy was about 0.03 MJ




# The CERN accelerator complex : injectors and transfer



Beam size of protons decreases with energy : area  $\sigma^2 \propto 1 / E$   
 Beam size largest at injection, using the full aperture


simple rational fractions for **synchronization**  
 based on a single frequency generator at injection







**1st Injection**  
**clockwise - beam 1**  
**sector 2 - 3**  
**8-10 Aug. 2008**

**2nd Injection**  
**anti-clockwise beam 2**  
**sector 8 - 7**  
**22-24 Aug. 2008**






Local mini-quench  
*“quenchino”*


verification of quench limit in magnets  $\sim 2 \times 10^9$  protons  
 @ 450 GeV and calibration of  $B_{\text{eamLossMon}}$  system





**10:30 beam 1 3 turns**  
**15:00 beam 2 3 turns**  
**22:00 beam 2 several 100 turns**







- First & Second Turn on screen
- First Turn on BPM system


Jörg Wenninger

Courtesy of Roger Bailey & O. Brüning




longitudinal position around the ring,  $s$  [m], here by monitor number





**H and V successfully scanned in the range  $\pm 12 - 18$  mm**


[LHC Perf. Note 1](#) Sep.2008




## $\beta$ -measurements and analysis

[LHC Perf. Note 8](#) Jan 2009


ABP and OP group



**A lot was learned from the cold-checkout, injection tests and the few days with beams in the LHC in 2008. Instrumentation and software and analysis worked very well and allowed many measurements, detailed analysis and adjustments. This also allowed to diagnose and later correct noisy channels and cabling error etc.**




one trace every 10 turns






# Simulation of injection with 170° injection phase offset





pt

turn 0


longitudinal phase space









real LHC




projection of previous plot : longitudinal charge density distribution

# LHC beam 2 with well adjusted RF capture



**important : observation of good beam lifetime at injection energy**








## Past

- QRL cryo-line (He supply)
- DFB power connections, warm to cold transition
- Triplet quadrupoles - differential pressure

## More recent


- **PIM** plug in module with bellow, systematically checked / repaired after warm up using “ping-pong” ball with RF-emitter : polycarbonate shell,  $\varnothing$  34 mm, 15 g, 2h battery powered, 40 MHz emitter, signals recorded by LHC BPM
- Vacuum leaks, condensation - humidity sector 3/4
- Magnet powering check / correct : min/max, cabling - polarity
- Single event upset, radiation to electronics, shielding etc
- Magnet re-training magnets quenching below what was reached in SM18
- Magnet interconnects, splices →





Commissioning with beam interrupted by a series of hardware failures - **not related to beams**

- two large transformers ; 13 - 18 September 2008 '08
- 19 Sept. '08 at 11:18:36, incident during hardware commissioning of sector 3/4 towards 5.5 TeV/ 9.3 kA, at 8.7 kA or  $\sim 5.2$  TeV, of the 600 MJ stored energy about 2/3 dissipated into the cold-mass      1 MJ melts 2.4 kg Cu



bad splice 220 n $\Omega$  at electrical connection between dipole and quad Q23,  $\sim 6$  t He or 1/2 of arc lost; pressure built up in adjacent each 107 m long, vacuum sub-sectors causing significant collateral damage.

details : LHC-PROJECT-REPORT-1168 March '09



some typical numbers and back of envelope estimates :

good splice  $\sim 0.3$  n $\Omega$ ,  $I = 12$  kA,  $U = R I = 3.6$   $\mu$ V (now) possible to check

$P = R I^2 = 0.043$  W    quench would need locally  $> 10$  W - depending on position - less critical in magnet

new QPS triggers at 0.3 mV for  $> 10$  ms

LHC dipole  $L = 100$  mH    stored energy in single dipole  $I^2 L / 2 = 7.2$  MJ     $\times 154 = 1.1$  GJ / sector




**BUS**  
 Cross-section Cu: 282 mm<sup>2</sup>  
 Cross section NbTi: 6.5 mm<sup>2</sup>  
 Kapton+isopreg insulation  
 RRR specification: >120  
 RRR experimental (D. Richter)  
 - RB bus: 223-276 (4 data)  
 - RQ bus: 237-299 (4 data)



**JOINT**  
 Joint length: 120 mm  
 Cu U-profile: 155 mm x 20 mm x 16 mm  
 Cu wedge: 120 mm x 15 mm x 6 mm  
 Insulation:  
 - 2 U-shaped layers of kapton  
 (240 mm x 0.125 mm thick)  
 - 2 U-shaped layers of G10  
 (190 mm x 1 mm)




# Busbar Splice



**normal conducting, soldered electrical connection between SC cables**  
1684 units  $\times$  6  $\approx$  10 000 splices at magnet interconnects; 1/3 dipole, 2/3 quads



Courtesy:  
Christian Scheuerlein



possible problems in soldering :

- overheating - SnAg loss
- too cold - SnAg unmelted, poor connection


A. Siemko et al. LMC 5/08/09

Now possible to diagnose : X-ray, ultrasound, resistance measurement.

Most reliable : resistance measured at room temperature

good : 10  $\mu\Omega$  dipole (RB) , 17  $\mu\Omega$  quadrupole (RQ).

Measured in 5 sectors which were warmed up. Fixed all above  $\sim$  40  $\mu\Omega$ . Other sectors measured at 80 K




## damage repair

- **39 dipoles and 14 quadrupoles removed - and re-installed. Last magnet back in tunnel on 30/04/2009, electrical connections finished 2nd June**

## avoid reoccurrence


- **Improved diagnostics, measurements of magnet interconnects - splice resistance**
- **> 50 % of machine ( sectors, 1-2, 3-4, 5-6, 6-7, all standalone magnets) with fast pressure release valves**
- **Improved anchoring on vacuum barriers around the ring**
  - aperture symmetric quenches and joints in magnets
  - 2 × faster discharge
- **Enhanced Quench Protection System**
- **Remaining risks minimized by keeping maximum beam energy limited to 3.5 - 5 TeV for the first run**



**Major amount of work - much of the hardware work is finished**

**Time also used to further improve crucial systems like BLM, complete collimator installation ..**

**Restart LHC with beam by mid-November 2009**



**Main strategy in commissioning :**

**establish circulating beams and good lifetime at the injection energy. ✓ Sept. 2008**

Chamonix 2/2009 baseline

1 month commissioning

10 month proton physics

1 month lead ions

**August '09 : Detailed discussion of the knowledge from the 5 sectors measured at warm and the 3 sectors measured at 80 K**

**All put together and discussed in special LMC meeting on 5 Aug. 2009.**

**Decision by management - 6 Aug. 2009.**


**Go in three steps**

**1. collisions at injection energy  $2 \times 0.45 \text{ TeV} = 0.9 \text{ TeV}$**


**2. physics run at  $2 \times 3.5 \text{ TeV} = 7 \text{ TeV}$**

**3. physics run at increased energy, max.  $2 \times 5 \text{ TeV} = 10 \text{ TeV}$**

**Towards the end of 2010 before the winter shutdown : 1st run with heavy ions, lead - lead.**



- **complete the BPM checks ( 70% H, 30% V done)**
- **adjust and capture beam 1**
- **beam 1 & beam 2 timing**
- **experiments magnets : turn on solenoids and toroids**
- **possible to allow for first collisions at  $2 \times 450$  GeV**
- **turn on IP2 / 8 spectrometers - verify perfect bump closure**
- **start to use collimators, increase intensity**
- **check out the beginning of the ramp,  $\sim 450$  GeV to 1 TeV**
- **QPS commissioning**
- **beam dump commissioning**
- **full ramp commissioning to initial physics energy of 3.5 TeV**
- **first collisions at physics energy of  $2 \times 3.5$  TeV**
- **increase intensity and partial squeeze**



design LHC intensity :  $3.23 \times 10^{14}$  protons / beam


1st years, limited by magnet quench / collimation

maximum beam loss rate  $\sim 10^{-3}$  /s fraction or  $\sim 4 \times 10^{11}$  p/s

**Examples for 0.001/s Loss Rate**

- It is really the **loss rate that matters** above a few ms. So what counts is the ratio of loss amount over loss duration (**short loss spikes are very dangerous**). We get the peak loss rate 0.001/s from:
  - 1% of beam lost in 10 s.
  - 0.1% of beam lost in 1 s.
  - 0.01% of beam lost in 100 ms.
  - 0.001% of beam lost in 10 ms.
- Stick with the **official loss rate 0.001/s** from now on, adding some evolution.
- Assume 0.002/s is achieved in the first year of LHC operation at 5 TeV, as shown in following slides.

Ralph Assmann 21



# bunches : nominal is 2808 bunches, 25 ns spacing


**LHC year 1 :** Important to go in small steps - minimize beam losses. Max. total intensity at 5 TeV roughly  $\sim 1/10$  nominal.

start of physics run :  $I < 2 \times 10^{13}$  p with intermediate coll. settings

later :  $I < 5 \times 10^{13}$  p with tight coll. settings.

3.5 TeV intensities could be a bit higher - details remain to be worked out





Baseline beam parameters for  $E_b = 5$  TeV have been worked out, discussed and agreed, LPC 7/5/09  
 Details for 3.5 TeV still need to be defined.

		scale factor 3.5 to 5 TeV
intensity	more critical at high E	take 1 ; conservative
emittance	$E^{-1}$	1.43
$\beta^*$	$\sim E^{-1}$ triplet aperture	1.43
<b>Luminosity</b>	$\sim E^{-2}$	<b>2</b>
beam-beam tune shift	constant	1

Luminosity estimates : **roughly 2x less at 3.5 TeV compared to 5 TeV**  
 this should be conservative and does not take into account that lower energies are less critical for protection, shorter ramp time and faster turnaround.



Beam-beam tune shift parameter  $\xi$   
 for head-on collisions depends  
 only on intensity ( not energy,  $\beta^*$  )

$$\xi = \frac{r_c N}{4\pi \epsilon_N}$$

N	$\xi$
$5 \times 10^9$	0.000163
$4 \times 10^{10}$	0.00130
$1.15 \times 10^{11}$	0.00374


nominal LHC : round beams and const  $\epsilon_N$   $\sigma_{x,y} = \sqrt{\beta_{x,y} \epsilon_N / \gamma}$

at the design emittance





# Parameter space



		No crossing angle						Crossing angle				
Energy	TeV	0.45	0.45	3.50	3.50	3.50	3.50	3.50	3.50	4.00	5.00	7.00
Bunch intensity	1.E+10	1	4	4	4	4	9	9	9	9	9	11.5
Bunches		4	43	43	43	156	156	702	1404	2808	156	2808
Emittance	$\mu\text{m}$	3.75	3.75	3.75	3.75	3.75	3.75	3.75	3.75	3.75	3.75	3.75
$\beta^*$	m	11	11	11	2	2	2	3	3	3	2	1
Luminosity	$\text{cm}^{-2} \text{s}^{-1}$	4.2E+26	7.2E+28	5.6E+29	3.1E+30	1.1E+31	5.6E+31	1.7E+32	3.3E+32	7.7E+32	8.0E+31	1.0E+34
Protons		4.0E+10	1.7E+12	1.7E+12	1.7E+12	6.2E+12	1.4E+13	6.3E+13	1.3E+14	2.5E+14	1.4E+13	3.2E+14
% nominal		0.0	0.5	0.5	0.5	1.9	4.3	19.6	39.1	78.3	4.3	100.0
Stored energy	MJ	0.0	0.1	1.0	1.0	3.5	7.9	35.4	70.8	161.7	11.2	361.7
Monthly (0.2)	$\text{pb}^{-1}$	0.00	0.04	0.29	1.59	5.76	29.16	85.84	171.67	399.85	41.65	5231.88
Physics month				1	2	3	4	?	?	?	?	


Pile-up,  $\sigma_{\text{in}} = 75 \text{ mb}$

0.09    0.5    0.5    2.4


**( $10^6$  seconds @  $\langle L \rangle$  of  $10^{33} \text{ cm}^{-2} \text{ s}^{-1} \rightarrow 1 \text{ fb}^{-1}$ )**

courtesy : Roger Bailey, 7 Aug. 2009

# Get LHC beams colliding : BPM resolution



adjust orbits such, that the beam 1 and 2 difference left/right of the IP is the same  
 beams must then collide. This is **independent of mechanical offsets and crossing angles**



nominal beam sizes at the IP			
	450 GeV	3.5 TeV	5 TeV
$\beta^*$ [m]	$\sigma^*$ [ $\mu\text{m}$ ]	$\sigma^*$ [ $\mu\text{m}$ ]	$\sigma^*$ [ $\mu\text{m}$ ]
11	293	105	88.0
3	153	54.9	45.9
2	125	44.8	37.5
1	88.4	31.7	26.5

$\delta x$	$\delta y$	$\mathcal{L}/\mathcal{L}_0$
$\sigma_x$	$\sigma_y$	
0	0	1.0000
0.1	0	0.9975
0.2	0	0.9901
0.3	0	0.9778
0.4	0	0.9608
0.5	0	0.9394
0.5	0.5	0.8825
1	0	0.7788
1	1	0.6065
2	0	0.3679
2	2	0.1353

measured with special (beam-) directional strip-line couplers BPMSW, at about  $L = 21$  m left and right of the IP in front of Q1 in each IR. Resolution each plane  $\delta_{IP} = \sigma_{BPM}$


**Expected resolution for small separation and 0 crossing angle ; in each plane.**

~ **50  $\mu\text{m}$**  using selected, paired electronics ; otherwise ~ 100 - 200  $\mu\text{m}$   
 beam 1 and beam 2 have separate electronics

~ **10  $\mu\text{m}$**  with extra BPMWF button pick-ups. Installed in 1&5, for large bunch spacing, [EDMS doc 976179](#)



# Luminosity scans and absolute luminosity




(pioneered by Van der Meer @ ISR)

**Orthogonal x, y scans  
to determine  $\sigma_{x,y}^*$**

$$\mathcal{L} = \frac{N_1 N_2 f}{4\pi \sigma_x \sigma_y}$$

$$\frac{\mathcal{L}}{\mathcal{L}_0} = \exp \left[ - \left( \frac{\delta x}{2\sigma_x} \right)^2 - \left( \frac{\delta y}{2\sigma_y} \right)^2 \right] \text{ gaussian beams}$$




Accuracy : better than **1%** at ISR

Aim for **early LHC ~ 10 %** ( done @ RHIC )


Contributions :

- Intensity  $N_{1,2}$  BCT ~1%
- Length scale - from BPM, bumps optics, few %
- Particles in tails
- Exact shape

extreme cases :




LEP example, V-plane, 3 bunches



studied by Simon White - as PhD thesis.

principle : H.B. and Per Grafstrom; LHC Report 1019 from 23 May 2007 <http://cdsweb.cern.ch/record/1056691>

and H.B., R. Schmidt, *Intensity and Luminosity after Beam Scraping*, [CERN-AB-2004-032](http://cdsweb.cern.ch/record/1056691)



**LBS : LHC Background Study Group.**

**Chaired by me, deputy D. Macina, scientific secretary A. Macpherson**

**In addition to background simulation, studies and optimization covering more generally experimental conditions including luminosity optimization and calibration and signal exchange between experiments and machine.**

**Core members include the physics coordinator & LPC chairman Massimiliano Ferro-Luzzi and contact persons from the experiments**

**ALICE** Antonello Di Mauro, Andreas Morsch + Werner Riegler

**ATLAS** Witold Kozanecki, Christophe Clement, Mika Huhtinen + Siegfried Wenig

**CMS** Richard Hall-Wilton, Tiziano Camporesi, + Nicola Bacchetta

**LHCb** Gloria Corti, Richard Jacobsson + Magnus Lieng

**TOTEM** Mario Deile; **LHCf** Daniela Macina

**Currently meeting once per month on Thu. afternoon at the CCC**


**Open to all interested and help most welcome.**

**Next meeting is on 27 August, see [indico](#)**





## Concluding remark



**The LHC is the worlds largest and most energetic machine. We also all know that it is not an easy machine and already faced and solved many difficulties.**


**Interventions which require warmup / cool down of sectors imply month's without circulating beams.**

**We had an excellent start of the LHC with beams in 2008 getting quickly both beams around the ring and good lifetime in only 3 days !**

**The current repair and shutdown is also used to further improve the preparations for beams for physics.**

**The LHC is scheduled to restart in mid November'09. First collisions will be at injection energy and the first high energy physics run at 3.5 TeV beam energy. During 2010 the energy will be increased towards 5 TeV. A run with lead-ions is scheduled towards the end of the run later in 2010.**

# Backup Slides



$$f_{RF} = 400.7896 \text{ MHz}$$

$$\lambda_{RF} = 0.748 \text{ m or } 2.4951 \text{ ns}$$

35 640 RF buckets

Bunches spaced by **25 ns** or  
10 buckets

Inject batches of

2, 3 or 4 x 72 bunches


1 batch = 72 bunches

total  $39 \times 72 = 2808$  bunches

**Leave a 119 bunch**

**abort gap free  $\sim 3 \mu\text{s}$**

A full LHC turn is  $88.9244 \mu\text{s}$




Crossing angle needed for  $> 156$  bunches


to avoid encounters closer than  $\sim 6 \sigma$

Angle scales with  $\sigma$  or  $1/\sqrt{\beta^*}$  and  $1/\sqrt{E_b}$

Nominal angle at  $0.55 \text{ m}$ ,  $7 \text{ TeV}$  is  $\pm 142.5 \mu\text{rad}$

$2 \times 15$  parasitic crossings  $\pm 58\text{m}$  from IP at  $7.5 - 13 \sigma$






two types of magnetic separation bumps :

parallel separation to avoid collisions in beam preparation, off in physics

crossing angle to avoid parasitic collisions, always required for > 156 bunches

IR1 : horizontal separation and vertical crossing angle

IR5 : vertical separation and horizontal crossing angle



orbit corrector magnets used in the IP bumps

MCBX in triplet - important for crossing angle and aperture at injection


collapse bump by combination of MCBC, MCBY and MCBX or ramp down MCBX first

Separation scans, optimization with MCBC, MCBY on one beam

courtesy Simon White

Distance from the IP (m)





**The LHC will run for the first part of the 2009-2010 run at 3.5 TeV per beam, with the energy rising later in the run. That's the conclusion that we've just arrived at in a meeting involving the experiments, the machine people and the CERN management. We've selected 3.5 TeV because it allows the LHC operators to gain experience of running the machine safely while opening up a new discovery region for the experiments.**



**The developments that have allowed us to get to this point are good progress in repairing the damage in sector 3-4 and the related consolidation work, and the conclusion of testing on the 10000 high-current electrical connections last week. With that milestone, every one of the connections has been tested and we now know exactly where we stand.**


**The latest tests looked at the resistance of the copper stabilizer that surrounds the superconducting cable and carries current away in case of a quench. Many copper splices showing anomalously high resistance have been repaired already, and the tests on the final two sectors revealed no more outliers. That means that no more repairs are necessary for safe running this year and next.**

**The procedure for the 2009 start-up will be to inject and capture beams in each direction, take collision data for a few shifts at the injection energy, and then commission the ramp to higher energy. The first high-energy data should be collected a few weeks after the first beam of 2009 is injected. The LHC will run at 3.5 TeV per beam until a significant data sample has been collected and the operations team has gained experience in running the machine. Thereafter, with the benefit of that experience, we'll take the energy up towards 5 TeV per beam. At the end of 2010, we'll run the LHC with lead-ions for the first time. After that, the LHC will shut down and we'll get to work on moving the machine towards 7 TeV per beam.**




# Schedule July 22 (LMC23)





Can be completely avoided up to 156 bunches  
 Then gradually becoming an issue  
 would be good to gain first experience on this  
 in the 2009 / 2010 run  
 Nominal, IP1/5 : each 30 parasitic collisions  $\sim 9\sigma$   
 Parasitic b.b. effects reduce with fewer bunches  
 or increased crossing angle



Simulation : IP5 colliding. IP1 going into collision  
 by ramping down the horizontal separation




Some ref.

W. Herr, M. Zorzano LHC Project Report 462 ; Tatiana Pieloni thesis

Figures above from S. M. White, H. Burkhardt, S. Fartoukh, T. Pieloni, *Optimization of the LHC Separation Bumps Including Beam-Beam Effects WE6PFP018, PAC'09*





close to head on beam-beam :  
 peaks in blow up at  $0.5$  and  $1.5 \sigma$




Horizontal Tune

Vertical Tune







Steps for luminosity increase during the 2009-2010 LHC <i>pp</i> run											
	900 GeV	first high-energy coll.		Pilot physics run							units
				no external crossing angle			with external crossing angle				
step	1	2	3	4	5	6	7	8	9	...	
fill scheme	2x2	=	=	43x43	156x156	156x156	50ns@144	50ns@288	50ns@432	...	
$E$	<b>0.45</b>	<b>5</b>	=	=	=	=	=	=	=	TeV	
$k_b$	2	=	=	<b>43</b>	<b>156</b>	=	<b>144+12</b>	<b>288+12</b>	<b>432+12</b>	bunches	
$N$	5	=	=	=	=	<b>9</b>	=	=	=	$10^{10}$ p/bunch	
$N_{\text{Alice}}$	5	=	=	=	=	=	1	=	=	$10^{10}$ p/bunch	
$\beta^*$ (IP1,5)	11	=	<b>2</b>	=	=	<b>1</b>	3	=	=	m	
$\beta^*$ (IP2)	10	=	=	=	=	=	3	=	=	m	
$\beta^*$ (IP8)	10	=	<b>2</b>	=	=	<b>3</b>	4	=	=	m	
$I/I_{\text{nom}}$	0.031	=	=	0.67	2.42	4.3	4.05	8.1	12.1	%	
$E_{\text{stored}}$	0.0072	0.08	=	1.72	6.24	11.1	10.5	20.8	31.2	MJ	
$\alpha_{\text{net}}$ (IP1,5)	0	0	=	=	=	=	300	=	=	$\mu\text{rad}$	
$\alpha_{\text{net}}$ (IP2)	0	200	=	=	=	=	300	=	=	$\mu\text{rad}$	
$\alpha_{\text{net}}$ (IP8)	0	380	=	=	=	=	620	=	=	$\mu\text{rad}$	
$n_{bb}$ (IP1,5)	1	=	=	43	156	156	144	288	432	colliding pairs	
$n_{bb}$ (IP2)	1	=	=	4	=	=	12	=	=	colliding pairs	
$n_{bb}$ (IP8)	1	=	=	19	72	=	138	276	414	colliding pairs	
$L$ (IP1,5)	0.0026	0.029	0.16	6.9	24.9	161.5	48.3	96.5	145	$10^{30}$ cm <sup>-2</sup> s <sup>-1</sup>	
$L$ (IP2)	0.0029	0.032	=	0.13	=	=	0.05	=	=	$10^{30}$ cm <sup>-2</sup> s <sup>-1</sup>	
$L$ (IP8)	0.0029	0.032	0.15	2.8	10.8	23.7	32.7	65.4	98.1	$10^{30}$ cm <sup>-2</sup> s <sup>-1</sup>	
$\mu$ (IP1,5)	0.012	0.19	1.07	=	=	6.9	2.24	=	=		
$\mu$ (IP2)	0.013	0.21	=	=	=	=	0.028	=	=		
$\mu$ (IP8)	0.013	0.21	1.0	=	=	2.3	1.58	=	=		
Time for physics	~shifts	~days		~weeks		~months					

Definitions:  $\mu$  = average number of inelastic interactions per crossing

$n_{bb}$  = number of colliding pairs at given IP

$\alpha_{\text{net}}$  = net crossing angle

Assumptions: Longitudinal emittance  $\epsilon = 0.5 \text{ nm} \cdot 7 \text{ TeV}/E$

Inelastic cross section:  $\sigma_{\text{inel}} = 52$  and  $75 \text{ mb}$  for  $\sqrt{s} = 0.9$  and  $10 \text{ TeV}$

Estimates: Beam commissioning time\* for reaching step 6  $\approx$  six weeks


Beam commissioning time\* to go from step 6 to step 7  $\approx$  two weeks

Total expected physics running time: of the order of  $5 \cdot 10^6 \text{ s}$

\* with machine available


# Main dipoles in arc cryostat


- Time for the energy **ramp** is about **20-30 min** (Energy from the grid)
- Time for regular discharge is about **the same** (Energy back to the grid)





# Main dipoles: magnet protection

- **Quench detected:** energy stored in magnet dissipated inside the magnet (time constant of 200 ms)
- **Diode in parallel becomes conducting:** current of other magnets through diode
- **Resistance is switched into the circuit:** energy of 153 magnets is dissipated into the resistance (time constant of 100 s for main dipole magnets)












## Electrical connection at interconnects:












Many machine modes

Here concentrating on **STABLE BEAMS**. How to get the most for physics

Optimize conditions - based on direct feedback from experiment



Beam sizes and initial separation at the IP @ 5 TeV

$\beta^*$ [m]	$\sigma^*$ [ $\mu\text{m}$ ]	$n_\sigma$
<b>11</b>	<b>88.0</b>	<b>11.4</b>
<b>3</b>	<b>45.9</b>	<b>21.8</b>
<b>1</b>	<b>26.5</b>	<b>37.7</b>

For a separation of  $d = \pm 0.5$  mm  
 $n_\sigma = 2 d / \sigma^*$  full separation in units of  $\sigma$

5 TeV. Lumi reduction by  $\pm 142.5 \mu\text{rad}$  crossing angle

$\beta^*$ [m]	$L_0 / L$
<b>11</b>	<b>1.0075</b>
<b>3</b>	<b>1.027</b>
<b>1</b>	<b>1.079</b>

$L / L_0$  by the Hourglass effect  
 $H(r), r = \beta^* / \sigma_z$   
 for nominal  $\sigma_z = 7.55$  cm

$\beta^*$	$r$	$H(r)$
10.	132.	0.999972
2.	26.5	0.999289
1.	13.2	0.997174
0.55	7.28	0.990833