



The DESY II Test Beam Facility – Status and Future

Ralf Diener
Norbert Meyners
Marcel Stanitzki



- Facility parasitic fed by DESY II synchrotron (PETRA III injector)
 - 1 bunch per fill, 30 ps, 1 MHz
- 3 carbon fiber targets generate bremsstrahlung photons
- Conversion at target to e^+/e^- with energies up to 6 GeV
- Single electrons, rates depend on: beam line, energy, target, collimation
- Very high availability (~ 99 % uptime)
- Three individual beam lines, controlled by the user
 - Shutter, area interlock, momentum + collimation



- All the useful things:
 - 30 kg and 1 ton stages, 25 t crane
 - Patch panels: Ethernet, optical fiber, BNC, S-HV
 - IP cameras
 - Dry nitrogen, cooling water, gas setup (2 areas)
 - Beam monitor
 - Two EUDET-type beam telescopes
- Dipole magnet in TB 21 (~1.5 T)




- Superconducting 1 T solenoid
 - Usable diameter ~ 75 cm
 - Mounted on movable stage




- Infrastructure projects
 - Common slow control system ✓
 - Large area strip telescope *in progress*
 - More Ethernet ports + all at 1 Gb *started*
 - New interlock system *started*
 - ...

- Running from February 23rd till December 22nd with 4 weeks summer shutdown
- 114 weeks available, 71 allocated (62 %)
 - Beam lines with telescope: 86 % allocated
- 58 % from LHC groups
- User statistics: 230 user, 106 first time at DESY
- Education
 - “HEP for teachers”, summer students: 1 week each


Projects 2017





DESY-II Test Beam Facility
Usage 2017



Infrastructure requests 2017



- Start February 12th, end December 21st
4 weeks summer shutdown
- 103 weeks available, 50 allocated
- 12% all lines booked



Week			TB21		TB22		TB24/1		TB24
				DATA		DATA	PC/MAG	Telescope in PC/MAG	none
1-Jan-18	1								
8-Jan-18	2								
15-Jan-18	3								
22-Jan-18	4								
29-Jan-18	5								
5-Feb-18	6		Startup		Startup		Startup		Startup
12-Feb-18	7		CMS-Pixel-Phase-2	X	XD-TBMST	X	Strip Telescope Installation		CAUCE-AHCAL
19-Feb-18	8		CMS-Pixel-Phase-2	X	ATLAS-OMF-HMCMOS	X			Mu3e-Tile
26-Feb-18	9		ATLAS-Strip-Stress	X	ATLAS-OMF-HMCMOS	X			
5-Mar-18	10		CMS-Pixel-Phase-2	X	Mu3e	X			
12-Mar-18	11		CMS-Pixel-Phase-2	X	ATLAS-ITk-Pixel	X			CAUCE-AHCAL
19-Mar-18	12				ATLAS-ITk-Pixel	X			
26-Mar-18	13		CMS-HGCAL	X	ATLAS-ITk-Pixel	X			
2-Apr-18	14								
9-Apr-18	15		CMS-OT-MaPSA	X	BLAD	X			
16-Apr-18	16		CMS-OT-MaPSA	X					
23-Apr-18	17								
30-Apr-18	18		CMS-Pixel-Phase-2	X	ATLAS-Strip-Embed	X			
7-May-18	19								
14-May-18	20								
21-May-18	21								
28-May-18	22		BLAD	X					
4-Jun-18	23				Setup				
11-Jun-18	24		CMS-Pixel-Phase-2	X	ATLAS-ITk-Strips	X			
18-Jun-18	25		CMS-Pixel-Phase-2	X	ATLAS-ITk-Strips	X			NICA-MPD
25-Jun-18	26		CMS-Pixel-Phase-2	X	Mu3e	X			NICA-MPD
2-Jul-18	27		CAUCE-SW-ECAL	X	ATLAS-Strip-Stress	X			
9-Jul-18	28		X-Ray-Crystal-Rad		ATLAS-Strip-Embed	X	CAUCE-SW-ECAL		
16-Jul-18	29		Summer Shutdown						
23-Jul-18	30								
30-Jul-18	31								
6-Aug-18	32								
13-Aug-18	33		Summer Students	X					
20-Aug-18	34		Summer Students	X					
27-Aug-18	35		CMS-OT-MaPSA	X					
3-Sep-18	36		CMS-OT-MaPSA	X					
10-Sep-18	37								
17-Sep-18	38								
24-Sep-18	39								
1-Oct-18	40		X-Ray-Crystal-Rad	X					
8-Oct-18	41				Setup				HEP for Teachers
15-Oct-18	42				ATLAS-ITk-Strips	X			
22-Oct-18	43				ATLAS-ITk-Strips	X			
29-Oct-18	44				Mu3e	X			
5-Nov-18	45								
12-Nov-18	46								
19-Nov-18	47						LCTPC-Micromegas		
26-Nov-18	48				ATLAS-ITk-Pixel	X	LCTPC-Micromegas		
3-Dec-18	49				ATLAS-ITk-Pixel	X	Interlock Installation		
10-Dec-18	50		OSQAR		ATLAS-ITk-Pixel	X			
17-Dec-18	51	Reactor 25/12 0900	Interlock Installation						
24-Dec-18	52								
Shutdown									



➤ 2-day DESY test beam workshop, October 2017


➤ Main motivation and objectives

- PETRA IV plans
- Ideas for possible upgrades of the facility and the infrastructure
- Long shutdown 2 in 2019/20 at CERN
 - Need to prepare science case for the DESY II Test Beam Facility

➤ Outline

- Presentation of the status and possible future developments
- All user communities invited to present their requirements and wishes + discussion
- Written report handed in January to the directorate to feed into DESY planning

FUTURE OPPORTUNITIES FOR TEST BEAMS AT DESY - 2017



Workshop and discussion on:

- Status and future developments of the DESY test beam
- User requirements and science case
- Near and long term beam time planning



DESY Hamburg, October 5. - 6. 2017

<https://indico.desy.de/event/TestbeamFuture2017>




Local organizing committee:
Cecile Deterre, Ralf Diener, Jan Dreyling-Eschweiler,
Heiko Ehrlichmann, Hendrik Jansen, Norbert Meyners,
Natalia Potylitsina-Kube, Marcel Stanitzki



- LHC
 - Atlas (ITk strips+pixel), CMS (tracking+HGCAL), Alice (ITS), LHCb (SciFi)
- Linear Collider(s)
 - Calice, LCTPC, CLIC (vertex/tracker)
- Belle II (VXD: SVD+PXD)
- Mu3e (recurl pixel layers)
- Dune (LAr TPC, ECAL, 3D scintillator target)
- GSI/FAIR (heavy ion)
 - CBM (Compressed Baryonic Matter) / HADES
 - Panda (EDD: endcap disc DIRC)

FUTURE OPPORTUNITIES FOR TEST BEAMS AT DESY - 2017



Workshop and discussion on:

- Status and future developments of the DESY test beam
- User requirements and science case
- Near and long term beam time planning



DESY Hamburg, October 5. - 6. 2017
<https://indico.desy.de/event/TestbeamFuture2017>




Local organizing committee:
Cecile Deterre, Ralf Diener, Jan Dreyling-Eschweiler,
Heiko Ehrlichmann, Hendrik Jansen, Norbert Meyners,
Natalia Potylitsina-Kube, Marcel Stanitzki



- Quote: “Don't fix it, it's working”
- Beam reliability and availability important and highly appreciated
- Support (incl. telescopes) rated very good
- Run time from Feb-Dec okay
- Availability of DESY test beams extremely important during LS2 at CERN
 - Summer shutdowns should be limited during LS2
 - Install a third beam telescope from CERN
- Needs after 2025 hard to predict, but consensus was that it will be needed

FUTURE OPPORTUNITIES FOR TEST BEAMS AT DESY - 2017



Workshop and discussion on:

- Status and future developments of the DESY test beam
- User requirements and science case
- Near and long term beam time planning



DESY Hamburg, October 5. - 6. 2017
<https://indico.desy.de/event/TestbeamFuture2017>



Local organizing committee:
Cecile Deterre, Ralf Diener, Jan Dreyling-Eschweiler,
Heiko Ehrlichmann, Hendrik Jansen, Norbert Meyners,
Natalia Potylitsina-Kube, Marcel Stanitzki



> Beam wish-list

- Lower energies $< 1\text{GeV}$
(e.g. DUNE detector down to a few 10 MeV)
- Higher energies (tracking \rightarrow less scattering)
- Higher rate
 - Repetition rate of single electrons (25 ns / 40 MHz)
 - Multiplicity per event (pixel sensors)
- Bunch train mode (e.g. ILC like)
- Secondaries (pions, muons)


> Service wish-list

- X_0 scanning using beam telescopes


> Telescope future \rightarrow See other talks at this WS

> Infrastructure wish-list

- Tagged photon beam



- Precise timing system ($< 20\text{ ps}$)
- Energy calibration per event
 - Precise calorimeter (BGO)
 - Fiber "tracker" - two layers: one before beam energy dipole, one in the area





- Common, low mass cold box for irradiated sensors inside the telescope

Disclaimer:
Projects on the following slides are
neither finished planning,
nor funded or decided

- Thicker Bremsstrahlung target → destroys beam too fast ✗
- Higher current → not much more possible ✗
- Higher energy → not possible in normal operations ✗
- Multiple bunches (✓)?

- Currently only one bunch possible, though
 - Linac II could deliver more
 - PIA could be used as a simple roundabout
 - DESY II could in principle handle more buckets
- But: Kicker from Linac II / PIA → DESY II too slow



- Fast kicker
 - R&D would be a great project to keep up with current developments outside DESY ... planning started, not finally decided
 - Kicker speed: one has to see what's achievable
 - Maybe 10-40 bunches in DESY?
 - Could possibly be installed in parallel to current e^- kicker
 - How long do the target fibers survive higher rate?
→ New system (anyway under discussion) with more fiber spares?

- Current beam lines well used, seldom overbooked
→ current three beam lines enough
- Under study:
4th beam line using DESY beam directly
 - Use the R-Weg (former transfer line to DORIS)
 - Extraction line already installed
 - Only dumped beam would be used
→ Repetition rate up to 12.5Hz
 - Intensity: $>1 \times 10^8$ to 3×10^{10} particles/bunch
 - Extraction energy 456 MeV - 6.3 GeV (7 GeV)






Fig.: DESY II energy cycle




- Current beam lines well used, seldom overbooked
→ current three beam lines enough
- Under study:
4th beam line using DESY beam directly
 - Use the R-Weg (former transfer line to DORIS)
 - Extraction line already installed
 - Only dumped beam would be used
→ Repetition rate up to 12.5Hz
 - Intensity: $>1 \times 10^8$ to 3×10^{10} particles/bunch
 - Extraction energy 456 MeV - 6.3 GeV (7 GeV)
- To be done
 - Small hall ($\sim 10 \times 15$ m)
 - Interlock system and shielding
 - Targets, collimators, instrumentation
 - Upgrade of DESY II instrumentation
 - In a first step: no hall just using the existing tunnel?




- > Extraction of DESYII bunches
- > “Full” bunches
 - Rate 12.5 Hz, energy 6.3 GeV
 - Fanning and collimating of the bunch: 10^{10} down to 100 electrons / cm^2



- > Extraction of DESYII bunches
- > “Full” bunches
 - Rate 12.5 Hz, energy 6.3 GeV
 - Fanning and collimating of the bunch: 10^{10} down to 100 electrons / cm^2
- > Secondary particles:
 - Dump on Be target → pions and muons (and neutrons, protons)
 - Energies up to 4 GeV / O(10) pions per bunch
 - In Europe currently only at CERN



- > Extraction of DESYII bunches
- > “Full” bunches
 - Rate 12.5 Hz, energy 6.3 GeV
 - Fanning and collimating of the bunch: 10^{10} down to 100 electrons / cm^2
- > Secondary particles:
 - Dump on Be target → pions and muons (and neutrons, protons)
 - Energies up to 4 GeV / O(10) pions per bunch
 - In Europe currently only at CERN
- > Irradiation
 - Tungsten Target ($\sim 10 X_0$) → intense electromagnetic shower
 - Irradiation chamber at the End
 - Operated parasitically, radiation damage studies



- PETRA IV: “Ultimate” light source
 - Driven by photon science community
 - Timescale ~ mid-twenties
 - Project evolving → Conceptual Design Report 2018

- Initial approach:
Use DESY II as-is as PETRA IV injector

- DESY II well over 30 years old:
Refurbishment of nearly all components
→ Effort probably nearly as high as
for a new injector

- Options

- 6 GeV Linac
- Booster ring in PETRA IV tunnel
- DESY IV in existing tunnel + new LINAC IV:
 - Low emittance 6 GeV booster, ramped at 3 Hz
 - ~ 320 m circumference
 - Injection energy ~ 300 MeV

> PETRA IV: “Ultimate” light source

- Driven by photon science community
- Timescale ~ mid-twenties
- Project evolving → Conceptual Design Report 2018

> Initial approach: Use DESY II as-is as PETRA IV injector

- DESY II well over 30 years old:
Refurbishment of nearly all components
→ Effort probably nearly as high as
for a new injector


> Options

- 6 GeV Linac
- Booster ring in PETRA IV tunnel
- DESY IV in existing tunnel + new LINAC IV:
 - Low emittance 6 GeV booster, ramped at 3 Hz
 - ~ 320 m circumference
 - Injection energy ~ 300 MeV



> DESY IV impact

- Dismantling of DESY II and current test beam setup
- Current beam generation would still work
- Interesting opportunities for the test beam facility

- Flat-top mode,
multi-bunch mode
→ higher rates



- Resonant extraction
of primary beam
→ “High Rates III”
(energy independent)
+ structured beam



> Status and near future

- Currently maintenance and clean-up ongoing before start on February 12th
- 2018: ~50% booked until now
- DESY test beam essential during LS2@CERN in 2019/2020 → maximize available beam time
- Beam line for schools in 2019/2020 @ DESY?

> DESY Testbeam Facility Workshop

- Input from community and science case for test beam facility essential

Outcome:

- Confirmed necessity till at least 2025
- A lot of interesting input on infrastructure needs and upgrade possibilities
 - Manpower limited
- Future possibilities for beam improvements
 - Multi-bunch mode
 - possible in ~1-2 yrs?
 - 4th beam line (high rate, secondaries, irradiation)
 - possible in ~2-4 yrs?
 - DESY IV (flat-top, resonant extraction)
 - mid 2020s?