



# Commissioning Report and Status Update of the PMT Mass Testing Container System



DFG Forschergruppenmeeting, DESY Hamburg,  
18.09.2017

Gefördert durch  
**DFG** Deutsche  
Forschungsgemeinschaft

presented by

**Alexander Tietzsch**

together with

Tobias Lachenmaier<sup>1</sup>, Björn Wonsak<sup>2</sup>, David Meyhöfer<sup>2</sup>, Henning Rebber<sup>2</sup> and Tobias Sterr<sup>1</sup>

(<sup>1</sup>Physikalisches Institut, Universität Tübingen; <sup>2</sup>Institut für Experimentalphysik, Universität Hamburg)



## Abstract

- ❖ Very short reminder about the system and milestones from the last few months
- ❖ Commissioning report (June 1<sup>st</sup> – July 14<sup>th</sup>, 2017)
- ❖ Status of the container system now and some first preliminary results
- ❖ Status update of the 2<sup>nd</sup>/other container system(s)



**Short Reminder about the System and  
Milestones from the last Months**

## Parameters of 20"-PMT to test


- ✓ Detection efficiency @ 420nm (av. 27%, > 24%)
- ✓ TTS of Single Photon Events (< 12 ns)
- ✓ Rise time / fall time (< 8 ns / < 16 ns)
- ✓ HV applied to reach gain of  $10^7$
- ✓ Dark Rate (< 50 kHz)
- ✓ P/V ratio (> 2.5)
- ✓ Pre- and after-pulse ratio (< 5% / < 10%)

- ❖ Reliable measurement of ~20000 20" PMTs within comparable and stable conditions
- ❖ Acceptance tests for crucial parameters with naked PMTs right after delivery
- ❖ Later maybe again full test of all PMTs after potting (depending on electronics scheme...)







## Design of the Mass Testing Container System



## Design of the Mass Testing Container System II



## Design of the Mass Testing Container System III





## Milestones

- ❖ Sent by ship on **March 24<sup>th</sup>** (delay of ca. 2 months w.r.t. original schedule)
  - no climate control during shipment, but enough drying agent inside
  - humidity max. 70% during shipment, max. acceleration of  $\sim 15G$  (!) recorded
- ❖ Container arrived Huangpu Port in China on **May 19<sup>th</sup>**
- ❖ Started commissioning on **June 1<sup>st</sup>**
- ❖ Had two on-site workshops in June
- ❖ Finished mechanical commissioning on **June 27<sup>th</sup>**
- ❖ Data taking in “expert mode” (selected measurements) started on **July 1<sup>st</sup>**
- ❖ In-depth testing and calibration phase of electronics and DAQ from mid July to now





# Commissioning Report

## Overview of commissioning

- ❖ On-site commissioning started on June 1<sup>st</sup>, first simple functionality tests of electronics all successful, only some minor damages found and quickly repaired





## Overview of commissioning II (mechanics)

- ❖ Removed all drawers and light slides from inside for ongoing work, realigned light shaping tubes (disturbed by transportation)
- ❖ Planned re-routing of the LED cabling finished after 1.5 weeks due to some noise problems
  - invested ~ 1 week of very hard work in reducing the noise level
  - successfully controlled all 36 LEDs in parallel for the first time





## Overview of commissioning III (mechanics)



- ❖ Installed fiber splitter system into container in 3<sup>rd</sup> week of commissioning (last missing part)
- ❖ Checked container system a lot for light tightness and tried to remove sources of residual light inside the container
- ❖ Re-installed all mechanical parts, fixation of all cables, closed cable feed through

*Mechanical installation fully completed since June 27<sup>th</sup>!*



## Overview of commissioning IV (electronics)

- ❖ Start commissioning of electronics and DAQ on **June, 18<sup>th</sup>**
- ❖ Climate remote control unit and temperature monitoring system running properly
- ❖ Connection to server farm established
- ❖ Removed several different sources of noise (removed some ground loops, using clean ground for all read-out electronics now, external “quiet” power supply for LED controller, ...)





## Overview of commissioning IV (electronics)

- ❖ Start commissioning of electronics and DAQ on **June, 18<sup>th</sup>**
- ❖ Climate remote control unit and temperature monitoring system running properly
- ❖ Connection to server farm established
- ❖ Removed several different sources of noise (removed some ground loops, using clean ground for all read-out electronics now, external “quiet” power supply for LED controller, ...)
- ❖ Successful test of all channels (HV, data cables, LEDs, fibers)
- ❖ Only a few MCX cables left for trigger recording (small change in plan)

***Electrical installation fully completed since July 14<sup>th</sup>!***

## Overview of commissioning V (DAQ)

- ❖ Some sub-parts of DAQ showed up to still have some bugs (some minor, but also some larger ones: after-pulse, dark noise and TTS measurement)
- ❖ Also found some unexpected problems, like larger ADC jitter than needed for good TTS measurement (invisible in our lab tests, because of comparable LED jitter → missed problems with ADC in our tests...)
- ❖ Full measurement sequence was never conclusively tested before
  - it took a lot of time for debugging with real system
  - data taking is buggy but was possible in principle (in **EXPERT MODE** at the moment)
  - important to make everything convenient for shifters!
- ❖ Started with calibration phase in expert mode, while working on DAQ from remote (fixing all open issues, improve flexibility for calibration, add some new ideas...)

*Final DAQ version was not ready on July 14<sup>th</sup>,  
but now in final testing and maintenance phase!*



## Problems during commissioning

- ❖ Tried to reduce **residual light inside the container** as much as possible, but still observed a slightly increased dark count ( $\sim 10$  kHz w.r.t. values given by vendor, depending on illumination)
  - light leaks in the container are excluded as source by several tests
  - found, that glue to fix Tyvek inside of the light shaping tubes is the source
  - **not removable source of a weak and homogeneous background light source**
  - **try to measure excess with reference PMT in each box as offset (“residual light field calibration”)**
  - avoid same problem for 2<sup>nd</sup> container by using staples instead of glue for Tyvek fixation



## Problems during commissioning II

- ❖ Magnetic field measurement inside showed a field strength of  $\sim 10\%$  of EMF (some few boxes exceed the 10% level, up to 12 % of EMF).
  - **Measurement from Hamburg showed an average of  $\sim 6\%$ !**  
Container is slightly magnetized, most likely from stress during transportation
  - Plan to demagnetize container (at least hot spots) to reduce residual magnetic field inside **(not done/finished yet)**
- ❖ **Delay in schedule** due to some unexpected problems (custom troubles, problems with light tightness, increased noise level,...)
  - Main impact was on automated DAQ, couldn't finish this before we had to leave
  - Try to fix all these things remotely, accompanied by some additional lab tests in Tübingen
  - **Major problem: Very bad remote connection from Germany to China (very time consuming, almost unfeasible)**
  - **A lot of hard work here, but now almost finished**



The image is a photograph of an oscilloscope screen. The screen displays a signal trace on a grid. The trace is a blue line that starts at a low level, then rises sharply to a higher level, and then settles into a noisy plateau. A vertical dashed line is drawn at the point where the signal begins to rise. The oscilloscope's control panel is visible on the right side, showing various settings. At the bottom of the screen, there is a text overlay with a black background and white text.

## Current Status and First Preliminary Results

CH1 50.0mV

M 25.0ns

CH1 / -26.0mV

13-Jun-17 10:41

145.913kHz





## Current Status and Tasks

- ❖ Since working in expert mode is possible, **calibration** of the whole container system started
- ❖ **Test all DAQ parts in depth** to better understand interplay between electronics and DAQ, and look for errors and unknown bugs
- ❖ **Work on** the last sub-parts of **DAQ** are on the way to get finished (including some demands and ideas from onsite)
- ❖ **Data taking with new PMTs** to learn more about the PMT behavior, compare results from container with scanning station results
- ❖ Some maintenance on software left for **shifter convenience** (improve user interface, file naming convention, adjust LOG summary outputs...)
- ❖ Re-adjustment of some cables on the electronics due to changes in DAQ sequence
- ❖ Prepare **shifter manual** (for both regular and expert shifters)



## Current Status and Tasks

- ❖ Since working in expert mode is possible, calibration of the whole container system started **ongoing work**
- ❖ Test all DAQ parts in depth to better understand interplay between electronics and DAQ, and look for errors and unknown bugs **ongoing work**
- ❖ Work on the last sub-parts of DAQ are on the way to get finished (including some demands and ideas from onsite) **ongoing work**
- ❖ Data taking with new PMTs to learn more about the PMT behavior, compare results from container with scanning station results **ongoing work**
- ❖ Some maintenance on software left for shifter convenience (improved interface, file naming convention, adjust LOG summary outputs), **very soon**
- ❖ Re-adjustment of some cables on the electronics due to changed sequence **very soon**
- ❖ Prepare shifter manual (for both regular and expert shifters) **very soon**



## Container Calibration

### ❖ Calibration Plan (minimum):

- ✓ LED-calibration: adjust all LED setpoints with reference PMT to produce different light intensities (0.1/0.2/0.5/0.7/1.0 p.e.)
- ✓ Laser-calibration: adjust Laser tuning to produce an average  $\sim 0.1$  p.e. intensity at all fibers
- ✓ Residual light field calibration: subtract contribution of light shaping shaping tube to “dark” noise rate







### ❖ $\sim 2/3$ of calibration measurements done

### ❖ Some more measurements could also be helpful to better understand the system (additional electronics test / “statistical calibration”)

→ *ongoing discussions*

## PMT Delivery Status



- ❖ Totally received PMTs at Pan-Asia warehouse (last week):  
**3440 tubes** (1760 Hamamatsu tubes, 1680 NNVT MCP tubes)
- ❖ Vendor data:



All plots from *Haiqiong Zhang* and *Zhimin Wang* (see talks from weekly PMT Instrumentation Phone Meetings  
→ corresponding DocDB conferences)

## Some *PRELIMINARY* Results: S/N



- ❖ Signal-to-Noise ratio of container system *better than 10*



$$S/N = \frac{\sigma_{\text{pedestal}}}{\text{mean}_{\text{signal}}} (HV @ 1 * 10^7)$$

S/N




S/N from Charge Spectrum







All plots from *Haiqiong Zhang* and *Zhimin Wang* (see talks from weekly PMT Instrumentation Phone Meetings  
→ corresponding DocDB conferences)

## Some *PRELIMINARY* Results II: PDE

- ❖ Conversion factor (CF): factor between PDE of measured PMT to reference PMT (mostly Hamamatsu EA1578)
- ❖ P/V and PDE CF values from ~ 170 PMTs measured
- ❖ Statistical errors of PDE measurement acceptable for all channels ( $< 5\%$ )





- ❖ Stability over time checked for some PMTs




All plots from *Haiqiong Zhang* and *Zhimin Wang* (see talks from weekly PMT Instrumentation Phone Meetings  
→ corresponding DocDB conferences)

## Some *PRELIMINARY* Results III: PMT types

- ❖ Observed differences in charge spectra between Hamamatsu PMTs and MCP PTMs (long tail in single p.e. spectrum for MCP PMTs)



*For comparison:  
Hamamatsu charge  
spectrum with higher  
light intensity  
(multi p.e.)*



All plots from *Haiqiong Zhang* and *Zhimin Wang* (see talks from weekly PMT Instrumentation Phone Meetings  
→ corresponding DocDB conferences)



The image shows three white shipping containers with yellow doors, arranged in a row. They are situated outdoors on a paved area with some grass. In the background, there is a large, dark-colored building with a flat roof. The text "Update on Next Container Systems" is overlaid in the center of the image.

# Update on Next Container Systems


## Overview

- ❖ Next three container already delivered
- ❖ All of them received magnetic shielding
- ❖ Already painted black inside and shelf system installed into next container
- ❖ HV and signal cables installed



# Magnetic shielding

- ❖ *Shielding factor of 2<sup>nd</sup> container mostly better than 10*
- ❖ Weak spots:
  - 2 drawer boxes next to ventilation openings (**expected**)
    - 15 % of EMF in two drawers, got an extra shielding with Finemet
  - Some weakness close to doors (**unexpected**)
    - Shielding factor decreased during transportation from company to DESY from below 10% to around 15%
    - Door seems to be sensitive to the placement of the container
    - Shielded drawers close to doors with additional layers of Finemet



EMF in Hamburg: ca. 48  $\mu\text{T}$

## Acquisition status / other parts of the drawer system

### ❖ Mechanical parts:

- All crucial parts for next container available
- Also most parts for light system already manufactured
- 40 new trays and light shaping tubes ready
- Light shaping tube: Glue used for 1<sup>st</sup> container to attach Tyvek is emitting a small amount of light (**darkcount rate increased by 5-10 kcts/s**) → **now using staples instead**





## Acquisition status / other parts of the drawer system

- ❖ Mechanical parts:
  - All crucial parts for next container available
  - Also most parts for light system already manufactured
  - 40 new trays and light shaping tubes ready
  - Light shaping tube: Glue used for 1<sup>st</sup> container to attach Tyvek is emitting a small amount of light (**darkcount rate increased by 5-10 kcts/s**) → **now using staples instead**
- ❖ Electronics and light sources/light system:
  - Stabilized LED already ordered, expect them end of September
  - All read out electronics already delivered to Tübingen
  - Picosecond-Laser delivered to Hamburg last week
  - Parts for laser system (filters, fibers, ...) not ordered yet
  - Cables for electronics and light system ordered, will be delivered soon
- ❖ Stronger computer for DAQ under discussion



# Summary and Outlook



## Summary and Outlook

- Commissioning of first container system: *June 1<sup>st</sup> – July 14<sup>th</sup>*
- Mechanics and electronics:
  - ✓ *Everything finished and installed, ready for shifting phase*
  - ✓ Only some cabling has to be adjusted
- DAQ:
  - ❖ *Bigger delay* due to multiple problems. DAQ software in final testing phase now, add some little things (additional LED measurements), some maintenance stuff left
  - ❖ DAQ runs in expert mode for more calibration and test measurements, but not completely finished yet
- Calibration and Data Taking:
  - ✓ *Some measurements and many calibration runs already finished*
  - ✓ Analysis guys already started to work with data
    - *on-going work and discussions to improve the system*





## Summary and Outlook II

### ➤ Remaining issues:

#### ❖ *DAQ!*

- has to be convenient for “normal” shifters at the end
- on-going work, but very time-consuming
- very difficult to give a reliable schedule (2 weeks?)

#### ❖ Finish calibration of whole system!

#### ❖ *Finalize shifter manual* ASAP

### ➤ Other container systems:

#### ✓ *most parts already delivered*

#### ✓ *installation and preparation of 2<sup>nd</sup> container is advanced*

→ *everything well in schedule* (shipment of 2<sup>nd</sup> container hopefully on end of October 2017)



## For more information....

...see also DocDB (talks from on-site workshops, documentation of container loading procedure, notes with suggestions on data naming convention and calibration...)

→ keyword **PMT test**



# Thank you.

Contact:

**Alexander Tietzsch**

Kepler Center for Astro and Particle Physics,  
Eberhard Karls Universität Tübingen  
Auf der Morgenstelle 14,  
72076 Tübingen, GERMANY

phone: +49 - 7071 - 29 - 73286  
[alexander.tietzsch@uni-tuebingen.de](mailto:alexander.tietzsch@uni-tuebingen.de)



# Backup




## Reminder: PMT Mass Testing Container System

- Set up a mass testing facility to *test and characterize all ~ 20'000 20-inch PMTs* before mounting them into the JUNO detector
- Create *stable and comparable testing conditions* and environment, using commercial shipping containers with special shielding and climate control unit
- Check *crucial parameters* like PDE, dark rate, HV/gain, TTS, rise/fall time, pre-/afterpulse rate for every single PMT
- (sampled photo cathode uniformity tests with Dubna's scanning station)
- (one test of bare PMTs and one test with potted PMTs and standard JUNO electronics)
- Set up 4 identical container systems to test *up to 140 PMTs in parallel*



## Reminder II: PMT Mass Testing Container System






## Some purposes of the system

- ❖ Full characterization of 36 PMTs in parallel (32 “new” + 4 reference PMTs) per container run
- ❖ Measurement of PMT at magnetic field reduced to 10% of EMF
- ❖ Climate controllable, and so stable environment
- ❖ Determine HV for  $10^7$  gain, dark count rate, PE spectrum, TTS, pre- and afterpulse rate
- ❖ Automated data taking, saving all the data on a server system
- ❖ PMT testing shifts done by collaboration

# Schematic overview: Electronics, DAQ and Analysis





# Mass Testing Site

- 1st container *finished and arrived* to JUNO site (commissioning and testing area in a Pan-Asia storage hall in Zhongshan, ~ 1.5h by car from JUNO surface area)

Pan-Asia Warehouse: testing site (ready now) – pictures by Wei Wang from DocDB-2167





## Dark Count Test Measurements

Cooled PMT faced to different materials, placed on container alley and covered with curtain (EA1581,  $\text{DCR}_{\text{exp}} = 8.4 \text{ kHz}$  (value by Hamamatsu)); remaining difference most likely caused by increased air temperature and lower threshold).

- **without anything:** 14.4 kHz
- **with piece of pure Tyvek:** 15.7 kHz
- **Tyvek with glue on backside:** 19.7 kHz
- **without anything again:** 13.8 kHz
- **with piece of pure Tyvek again (now illuminated before):** 16.6 kHz
- **Tyvek with glue on backside again (also illuminated before):** 21.5 kHz
- **without anything again:** 14.0 kHz
- **covered with aluminum (reflecting):** 14.7 kHz
- **Tyvek with glue on front side:** 43.4 kHz
- **last test without anything again:** 14.5 kHz

- No significant increase by pure Tyvek
- “Small” increase by Tyvek with glue on backside
- Huge increase when glue is pointed directly to PMT
- No glowing from PMT inside observed



## Dark Count Excess Measurements

Dark count excess measurements with 36 Hamamatsu-PMTs (uncharacterized before). Values in table show the excess w.r.t. the expected dark count rate (values given by vendor)

[kHz]	1	2	3	4	5	6	7	8	9
A	+1.8	+19.6	+12.7	+3.9	+11.5	+6.9	+9.2	+14.2	+15.6
B	+11.6	+13.4	+8.8	+7.7	+11.6	+10.5	+10.7	+14.9	+2.9
C	+2.0	+8.8	+8.9	+15.3	+9.9	+8.1	+9.4	+16.7	+6.1
D	+8.3	+5.5	+8.9	+6.7	+7.7	+5.2	+7.1	+5.2	+7.4

**excess in dark  
rate:  
 $+(9.3 \pm 4.2)$   
kHz**


After changing the PMT positions:

[kHz]	1	2	3	4	5	6	7	8	9
A	+4.0	+25.0	+13.2	+7.1	+14.0	+13.7	+11.6	+18.0	+17.6
B	+12.2	+4.9	+9.3	+10.9	+14.1	+10.3	+10.5	+17.0	+4.9
C	+1.6	+10.3	+9.3	+16.4	+9.2	+9.5	+11.0	+17.5	+7.9
D	+9.5	+5.5	+9.3	+5.7	+8.7	+6.7	+8.1	+7.8	+8.1

**difference to  
above:  
 $+(1.3 \pm 2.3)$   
kHz**

## About the container DAQ: Main idea


- ✓ Automated data taking by DAQ (shifter should just press the „**START**“ button)
- ✓ Every electronics unit should be controllable by PC
- ✓ Set up a LabView program with easy user interface for shifters



*remote control on  
electronics via PC*

*commercial  
electronics*

## Setup of DAQ






# Setup of DAQ


```
input-file_for_Daq - Editor
Datei Bearbeiten Format Ansicht ?
Example for a DAQ input file for 1 container load:

## -----
## PMTid      HAM(0)/MCP(1)  V_prod      Box
013577        1              1620         B1 / 09
013578        1              1630         B2 / 10
013579        1              1650         B3 / 11
013580        1              1620         B4 / 12
013581        1              1710         B5 / 13
316262        0              1920         C8 / 25
316263        0              1870         C9 / 26
...
```

Has to be generated  
automatically or by  
hand from shifter




## Setup of DAQ








## Setup of DAQ





## Design goal of the „black box“

### ❖ **DATA TAKING**


- Easy to handle input and output files
- Only a few infos needed as input

### ❖ **SOFTWARE**

- DAQ should be as easy as possible to control (start/stop)
- Should be capable to handle with some errors (by its own, as far as possible)

### ❖ **SHIFTERS**

- Shifters need clear instructions how to handle DAQ (especially when errors occur – some kind of „emergency procedure“ at least for shift-experts)
- Shifters should be capable to check whether measurement cycle has run completely (simple completion checks, check log summary file, check data for consistency...)





# DAQ Measurement Sequence

## Step 1. Connection tests.

- ✓ Base plugged on? (apply 100 V, look for current)
- ✓ HV working? (try to apply input voltage)
- ✓ Data cable plugged? (look for some counts)

→ If one test fails: **BREAK!** (last time!!)

## Step 2. Cool down phase.

- ✓ Wait for several hours
- ✓ Dark noise tests: PMT cool now? (“dark count threshold”)

→ Continue, when all PMTs cool or **after 12 h** (max. cooling time)

## Step 3. HV/gain determination

- ✓ Take data @  $[V_0, V_0 \pm \Delta V, V_0 \pm 2\Delta V, V_0 \pm 3\Delta V]$
- ✓ Do some simple fits of spectrum to determine gain @ HV
- ✓ Fit gains to find correct HV

→ Apply correct voltage

## Step 4. Final **dark count** measurement @ correct HV (gain = $10^7$ )



## DAQ Measurement Sequence II

### Step 5. LED measurement

- ✓ Switch LEDs on
- ✓ Record waveform (520 ns) – **most parameters**
- ✓ Different light intensities? ( $\sim 0.1$  p.e. /  $\sim 1$  p.e.)

### Step 6. Laser measurements

- ✓ Switch ps-Laser on
- ✓ Record waveform:
  - (520 ns) – **TTS measurement**
  - ~~(20  $\mu$ s  $\equiv$  20  $\times$  1024 ns)~~ – **afterpulse measurement**

### Step 7. Afterpulse counting

- ✓ Another Laser measurement
- ✓ Just counting pulses in 20  $\mu$ s window (VETO for initial pulse)

### Step 8. Turn off HV, **save all the data** (waveforms as binary, counters as txt-file), stop DAQ, create **LOG-SUMMARY** for shifter.





## Data format

- ❖ Two types of files with different data format:
  - *WAVEFORM DATA* (recorded by ADC, 520 ns windows, baseline and waveform, saved as **4 separate, big-endian coded binary dat-files**)
  - *COUNTING DATA* (recorded by Scaler, just int numbers, saved as **ASCII coded txt-files**)
  - Additional: *LOG-SUMMARIES* for each PMT, saved as **txt-files**
- ❖ All measurements connected to waveforms and pulse analysis (HV/gain, p.e. spectrum, rise-/fall-time, TTS) recorded as waveform data; also some raw baseline test data and trigger pulse data files will be recorded in that way
- ❖ All measurements connected to rate determinations (afterpulses, dark noise) recorded as counting data



## Expected number and size of all data files

- ❖ HV/Gain-determination: **36** ch. x **7** HV settings x **4** files (*binary*)
- ❖ Dark noise measurement: **36** ch. x **1** file (*ASCII txt-file*)
- ❖ LED-measurement: **36** ch. x **2** light intensities x **4** files (*binary*)
- ❖ Laser-measurement (TTS): **36** ch. x **2** light intensities x **4** files (*binary*)
- ❖ Afterpulse measurement: **36** ch. x **2** file (*w/ and w/o light; ASCII txt-file*)
- ❖ Additional: **4** x **2** ADCs x **2** light intensities x **4** trigger files to subtract ADC jitter for TTS determination (*binary*)
- ❖ **36** ch. x **4** file with just noise, to monitor ADC against overvoltage (OV) protection (*binary*)
- ❖ **37** additional files: 1 log-summary per PMT for container run, and 1 input-parameter-file ASCII txt-files

---

Saving of all waveform data into **4 separate files** („part1.dat“, ..., „part4.dat“) is for performance reasons. Each file contains a quarter of the total number of acquired waveforms.

OV protection saves ADC from voltage spikes, but cannot be recognized by running DAQ → noise files will be used by shifters as „data quality check files“ (work in progress...).



## Expected number and size of all data files II

In total: **1937** files per full container run

-----  
1792 raw data binary files (.dat)

145 ASCII-coded txt-files

- ❖ Total amount of data per container run: between **100** and **250 GB**  
(depends on number of data points, number of recorded waveforms and number of measurements – not yet finally decided)
- ❖ All files can be compressed into a zip-file before transferred to server  
(“Run\_0050.zip”)
- ❖ Waveform files can also be converted into a ROOT tree before transferred to server

***Data compression/conversion and transfer to server is duty of the shifter! Scripts for this should be provided (work in progress...)***



## Suggested naming convention for data files

- ❖ Every single file (except the input file, the log-summary and the trigger monitor files) should at least include the PMT ID, the drawer box number (from inside the container: 101...136) and the container run number
- ❖ Suggested naming convention:

Example File Name	Explanation
EA0001_101_0050_HV_1800_part1.dat	PMT-ID_BOX_RUN-No_HV-Measurement_appliedVoltage_part
EA0001_101_0050_DNR_1830.txt	PMT-ID_BOX_RUN-No_DarkNoiseRate-Measurement_appliedVoltage
EA0001_101_0050_LED_LOW_part1.dat	PMT-ID_BOX_RUN-No_LED-Measurement_LOW/HIGH-Intensity_part
EA0001_101_0050_LASER-TTS_950_part1.dat	PMT-ID_BOX_RUN-No_Laser/TTS-Measurement_Laser-Tuning_part
EA0001_101_0050_AFP.txt	PMT-ID_BOX_RUN-No_Afterpuls-Measurement
EA0001_101_0050_AFPdark.txt	PMT-ID_BOX_RUN-No_Afterpuls-Measurement-without-light
0050_TTS_Triggerfile_11-18_part1.dat	RUN-No_Recorded-Trigger-for-TTS-ADC1-CH1-8_part
EA0001_101_0050_OVcheckData_part1.dat	PMT-ID_BOX_RUN-No_OvervoltageCheck-Data_part
log-summary_EA0001_101_0050.txt / DAQ-input_0050.txt	LogSummary_PMT-ID_BOX_RUN-No / DAQ-Input_RUN-No

## Suggested structure on the server farm

Location of the container testing data on the server farm (currently only calibration and test data saved there):

***farm1.pmt.ihep.ac.cn:/pmtfs/disk01/container\_data/***

One folder for each container run (for example run #50).

### ***(1) Uncompressed/unconverted:***

*container\_data/mass\_test\_data/run0050/EA0001\_101\_0050\_HV\_1800\_part1.dat*  
*container\_data/mass\_test\_data/run0050/EA0001\_101\_0050\_HV\_1800\_part2.dat*  
*container\_data/mass\_test\_data/run0050/EA0001\_101\_0050\_HV\_1800\_part3.dat*  
*container\_data/mass\_test\_data/run0050/EA0001\_101\_0050\_HV\_1800\_part4.dat*  
*container\_data/mass\_test\_data/run0050/EA0002\_102\_0050\_HV\_1740\_part1.dat*

...

### ***or (2) Compressed into 1 zip-file:***

*container\_data/mass\_test\_data/run0050/run\_0050.zip*

### ***or (3) Waveforms converted into ROOT-trees:***

*container\_data/mass\_test\_data/run0050/EA0001\_101\_0050\_HV\_1800.root*  
*container\_data/mass\_test\_data/run0050/EA0002\_102\_0050\_HV\_1740.root*  
*container\_data/mass\_test\_data/run0050/EA0004\_103\_0050\_HV\_1920.root*

...



## Cable of Potted PMTs (maybe obsolete?)

- 100 m cable from Xiaoshan
- Fits inside packaging
- Weight 7 kg

→ *Total weight of tray with PMT: 15 kg*

- Two ways to keep it on tray:
  - (1) Curled around the neck, then close to head → quite ugly, but it fits (see picture)
  - (2) Near the base → Special holder necessary
- Maybe obsolete now with new electronics design?



(1)



(2)

