



Where does PXD live?






Where does PXD live?





PXD Hardware in the E-Hut






Top of Belle: PXD Rack




6



PXD Rack








- Rack
 - Non-compliant standard
 - Impromptu borrow from ancient Belle storage
- Many systems not in final configuration
 - External bench PS needed for DHI
 - + PS interlock


PXD Status and Integration






B3 Control Room





Final Test at DESY – August 2017





Final Test at DESY – August 2017




- Final Test of "all" BEAST components and Shipping preparation
- Many components were still missing e.g.:

- One patch panel
 - → one module went untested
- ATCA DHH
- Main PS + PS backplanes
 - + controller
- DHI (CLC Bbs)
- Cables

PXD Status upon Arrival at KEK





B4 VXD clean room





BEAST PXD Modules Testing at B4



- Switched on DHPs only
 - High speed link stability tests
 - → "First big temperature scare"
- Overall cooling time with open CO2 system
 - ~10 hours
 - → extremely limited testing, basically one set of pedestals per module
 - → high temperatures, unstable DHP behavior (current, links)
 - 2 days before insertion
 - → only then patch panel short became apparent (first full test of PP)
- In the meantime many grounding/shielding problems
 - Patch panel / dock box / DHI "eco system" is not in order

https://elog.belle2.org/elog/Beast-II-Commissioning/



Test in Final Detector Position



- Highspeed link tests
- Attempted Delay scans
- Pedestals tests
 - Local data taking very difficult with DHC + FTSW system
- Final hardware component DHI arrived beginning of December
 - Reason for stability problems became apparent
 - → Grounding/Shielding issues
 - → Sensing issues
- Since January DAQ tests with DHP test pattern

https://elog.belle2.org/elog/Beast-II-Commissioning/

PXD Module Summary




- So far Modules 100 % functional (surprisingly)
 - Links sufficiently stable
 - Matrices appear to be working
- Modules not optimized at all
 - No ADC optimization
 - No matrix working point data for two modules
 - Not final grounding scheme
- PXD local data + pedestals
 - Online Monitor has to be commissioned/developed
 - Scripts have to be developed for all optimization (with DHC + FTSW system)

PXD Slow Control Summary



- PXD Servers installed and running in "final system like" configuration
- Slow Control GUI still only for experts (even too much for them)



Outlook



- Lots of work until phase 2 necessary
 - Module optimization → scripts
 - Slow Control GUIs → shifter operation

- Last hardware missing
 - BNC cables to connect to VXD local hardwired interlock (VLHI)
 - Dockbox temperature monitoring readout system (installation in 2 weeks)
 - Maybe DHI modification still?

Intense "workshop" at KEK in February to tackle these problems