

# DHI, DHH for Phase 3 and DHH Upgrade


**Igor Konorov**

Institute for Hadronic Structure and Fundamental Symmetries (E18)

TUM Department of Physics


Technical University of Munich

DEPFET Workshop 22.01.2018, DESY




*Uhrenturm der TUM*

# DHI Prototype @ Phase 2




# DHI Phase 2 – Phase 3

## PHASE 2



## PHASE 3



DHI – control and synchronization  
 DHE – data processing


# DHI

## Status

- 12 modules are in production
- Production was scheduled for beginning of January but delayed due to missing DC/DC LTM4622
- DIGIKEY run out of stock, delivery 26 weeks
- ARROW USA has in stock but ordering requires custom clearance
- Stock at RS ? Ordering in progress
- Backup solution : piggy back PCB with another type of DC/DC converter

## Firmware changes

- Small change of DHE firmware
  - Remove JTAG, SPI interface, Manchester encoder
- Assemble DHI firmware
  - UCF  $\Leftrightarrow$  5 x (IPBUS + JTAG + SPI)
- **If no bugs delivery time to DESY end of February**
- DHI dummy will be delivered to DESY beginning of February for cable arrangements



# Delivery to DESY for Final Detector Test

In end of January we ship DHH system for half shell to DESY, except DHI :

- ATCA shelf
- 4 DHCC
- 4 DHRTM
- 20 DHE
- 4 DHC
- 0 DHI

# To be Done for Phase 3

## Missing Hardware

8 x DHI modules

Short of DHE/DHC modules because quite few were damaged

- Production of 20 more modules scheduled for middle of February

## DHE/DHC firmware changes

DHE

- Remapping
- Row wise hits sorting for clustering algorithm
- Clustering algorithm

DHC


- Round Robin event distribution to 4 ONSEN modules

# DHH Upgrade : DHU

**Module being developed for Belle2 DAQ upgrade and DHH upgrade**

**Technical parameters :**

- Double width AMC card
- XCKU095-1FFVB2104
  - 1.2 M logic cells
  - 60 Mbit Block RAM
  - 64 x 16Gb/s
- 2 x 16 GB DDR4 SODIMM,
- AMC connector Interfaces
  - B2TT
  - Ethernet(IPBUS)
  - 15 x 16Gb/s
- Front panel interfaces  
48(60) x 16Gb/s



Module will substitute 5 DHE and 1 DHC => 8 DHQ

First two prototypes will be ready by May 2018

# Summary

## Phase 3

- Production of DHI modules is on hold because of missing DC/DC converter
- If there are no bugs DHIs will be delivered to DESY in end of February
- New firmware to be developed for DHI
  
- DHH system for half shell will be delivered to DESY next week
- Integration of remapping and clustering algorithm in DHE firmware

## DHH Upgrade

- DHU module is in development, first prototype will be ready in May 2018

THANK YOU