

## LMU München - Excellence Cluster Universe

# PS, Services, Grounding

**Stefan Rummel 2018/01/23** 





# **Overview**



- PS Production, OVP, Firmware
- Grounding
- Dockboxes Production, Testing
- Second set cables



## PS - Production



- Commissioning of units completed
  - 50 units dedicated for PXD
  - OVP build in, not enabled
- Software to test OVP is has been finished in 12/17
  - Each OVP condition is tested, shutdown levels are determined
  - → First systematic tests revealed issue with one important channel
- Condition: for Vref-Vsub only single limit applied
  - → Rework towards window: -0.4V<(Vref-Vsub)<2.2V ongoing
- First 10 units have been adapted
  - Rate of rework ~10/WD
- → 10 units can be shipped to DESY within January



#### **PS** – Firmware



- Observation: Parallel operation of 4 units showed issue while simultaneous power up
- Investigations showed that commands are distributed to all nodes instead of a point to point connection
  - Probably a horrible way to implement our specification to have broadcast commands to all units available...
- Commands transmission is organized by XME middleware
  - Black box for most developers


### Possible options:

- (1) Restart firmware project with TUM/Fortiss. However most people worked on the project have left (project running 2011 to early 2013)
- (2) Remove XME from firmware
- → Michael will report on option 2



# **Grounding – Baseline**





- Based on the recommendations from ITA/Fernando
- Details like referencing the transmitter / DHI not covered




## Grounding



- ITA / Fernando worked out grounding scheme
- → Baseline for PXD

Phase 2 commission revealed a set of issues in the grounding scheme:

- Transmitter housing internally connected to gnd
  - Dockbox connected transmitter housing to chassis gnd
  - → Short of chassis gnd to transmitter gnd
  - → Fixed using tape, pads towards screws opened
- Accidental connection of inner shield of Infiniband cable and PP housing
  - → Should be fixed by detailed production documentation by ACK
- Intentional connection on DHI between inner shield of CLC and chassis gnd
  - → Loss of ground sense wire(!) as ground sense is used as transmitter ground
- Link stability was only achieved by shorting transmitter ground to chassis
  - → Sense wire has high resistance
- DCD\_MON cable pair carries DGND\_SENSE, too
  - → Need to be adapted while PP production



- Use Inf.B. cable drain wires /inner shield to define potential of transmitter and DHI, remove connection between CLC shields on DHI
- → Restore DGND sensing




## **Dockbox**



#### Dockboxes:

- First batch of 12 production boxes has been produced
- EMS via MPI electronics workshop
- Setting jumper, testing of power at LMU
- Ongoing mounting and testing of transmitters at TUM
- Flexibility to adapt grounding by exchanging R/C
- → Aiming for final batch once green light from collaboration





# Dockbox Changes 3.0 to 3.1



- Topoverlay (Names of components, strings for documentation) is switched on
- All capacitors are marked, the power connectors with names, similar to the PS -"analog" and "digital"
- Jumpers (where required) are named with the possibilities they offer (eg. sw\_sub / sw\_dvdd ....)
- SW\_SUB jumper has been replaced with a net tie, therefore no manual soldering is required anymore
- Version of box now mentioned
- Connections to the mounting holes of the transmitter are disconnected from the chassis-ground as the transmitter housing is internally connected to TGND
- Pads of the transmitters have been changed from chassis-ground to TGND
- Passives around the keepout areas have been moved from the keepout
- → Jig for safe mounting developed by ACK





#### Services cables



- Camera link cables available at DESY
- Power cables available, one batch of 11 is still at LMU
- Fibers/transmitter available at LMU

#### Second Set:

- Application for funding has been granted in December
- Most pressing item the power cables have been ordered lead time ~5 month
- Dockboxes dummies will be prepared by DESY
- Orders for Fibers, Connectors, Cameralink-cables will be ordered soon



## **Summary**



- PS commissioning done, OVP testing ongoing
- 10 units for DESY within January
- Major improvement in firmware stability, scalability expected
- First set of cables available
- Procurement of the second set started in December
- Final batch of Dockboxes can be started after decision of collaboration.





# **Backup**



## **Patch panel**




- Components for PP availiable
  - Infinibandcables
  - Glenair 165cm, 185cm and some 200cm
  - 30 housings for PP production available
- Issue: Final length of cables not decided
- Issue: Availability of slots for manufacturing at HighQ EMS
  - Glenair assembly by E-Workshop @ LMU
  - First PP assemblies (10) done by E-Workshop @ MPI



## **Services - PP**



• PP production has been documented in detail by ACK, incorporating all our experience





## **Services - PP**



