


# WG 4, Input & HOM Coupler Summary

TTC @ FNAL April 2007

# RF CONDITIONING AND TESTS ON TTF-III POWER COUPLEURS AT LAL (Interlock thresholds)

W-D Moeller on behalf  
of H. Jenhani

## Last conditioning time performances



		First values	Last values
Vacuum	1 <sup>st</sup> threshold	$2 \times 10^{-7}$ mbar	$6 \times 10^{-7}$ mbar
	2 <sup>nd</sup> threshold	$4 \times 10^{-7}$ mbar	$1 \times 10^{-6}$ mbar
	Vacuum interlock limit	$1 \times 10^{-6}$ mbar	$5 \times 10^{-6}$ mbar
e- current	Current interlock limit	5 mA	
Light	PM interlock limit	1 Lux	
Temperature	I. R. detector limit	85 °C	
Arcs	If any		
Repetition rate	2 Hz		4 Hz
Control loop	30 s		15 s

Need more  
tests

## Conclusion


- ❑ New conditioning time performances : ~20 h
- ❑ 4.5 kV DC bias of the inner conductor seems to be efficient to stop e- activity on TTF-III coupler
- ❑ More tests are needed to find the best way to use the coupler inner conductor for e- current measurements



# High power tests of the prototype input couplers for the Cornell ERL injector & RF system update

*S. Belomestnykh*  
*Cornell University*







- ❑ We have ordered ten more couplers of an updated design.
- ❑ We are closely following fabrication at CPI to ensure good quality.
- ❑ Recent RRR measurements of a copper sample produced good result:
- ❑ The first production pair of input couplers is expected to be delivered in June with the rest shortly after.
- ❑ As our installation schedule is very tight, we plan to do full testing of only the first two couplers.
- ❑ As we now have an operating high power klystron, it will be used for the coupler testing.
- ❑ As we have observed very little vacuum action in the cold parts of couplers (vacuum baked) and a lot of vacuum activity in the warm parts, we think that it is very important to implement *in situ* vacuum bake especially if we are to skip high power testing of input couplers.
- ❑ All input couplers will be *in situ* vacuum baked upon installation in the cryomodule and kept under vacuum after that. While it is already implemented for HTC, there are still some problems with the five-cavity cryomodule.
- ❑ Five more klystrons will be delivered between mid-May and mid-September and then tested at Cornell.
- ❑ While all cavities will be tested in a vertical dewar, only one will be tested in a specially design single-cavity HTC in late June/July. The prototype input couplers and HOM loads will be used in this test.
- ❑ Assembly of the five-cavity injector cryomodule is expected to be finished by the end of the year with installation starting early in 2008.

# HOM Damping and Coupler Mutipacting Simulations

Z. Li, L. Xiao, L. Ge

A. Candel, *A.Kabel*, C. Ng, K. Ko

V. Akcelik, S. Chen, L. Lee, E. Prudencio, G. Schussman, R. Uplenchwar


SLAC-Advanced Computational Department

Work supported by U.S. DOE ASCR & HEP Divisions under contract DE-AC02-76SF00515




# SLAC 3D Parallel FEM EM Codes

- Tetrahedral Mesh with Finite-Element
  - Up to 6th order basis for field accuracy
  - Unstructured grid for modeling geometry with large variation in dimensions
- Parallel implementation ( $10^2$ - $10^3$  processors,  $10^2$ GB memory)
  - Modeling details with great realism



- Simulating large systems such like multi-cavity cryomodule





- A suite of solvers including frequency domain and time domain
  - Omega3P - Frequency Domain Mode Calculation
  - S3P - S-parameter Computation
  - T3P - Time Domain With Beam Excitation
  - Track3P - Particle Tracking, MP and dark current
  - V3D - Visualization

...



# Coupler Test Setup

Will simulate all the components to compare with and to help understand the HP test results



B. Rusnak, C. Adolphsen, R. Swent,  
C. Nantista, G. Bowden, J. Lewis  
TTC meeting KEK




## First Results on a New 1.3 GHz Coupler Component Test Stand\*

*B. Rusnak (LLNL) (presenting), C. Adolphsen, F. Wang,  
G. Bowden, E. Doyle, L. Ge, K. Jobe, L. Laurent, B.D.McKee,  
C. Nantista, R. Swent, J. Tice, N. Yu (SLAC)*


*2007 TTC Meeting at Fermilab  
April 23-26, 2007*

*\*This work was performed under the auspices of the U. S. Department of Energy by the University of California,  
Lawrence Livermore National Laboratory under Contract No. W-7405-Eng-48.*

To do these measurements, a novel L-band test stand was developed and installed at SLAC




Concept and hardware of test set up for measuring components – first test component is a 40 mm straight tube







Delta as a function of RF input power and z axis locations



Delta as a function of RF input power and MP order.



No Multipacting activities between coax pipe

# 3.9 GHz Input Couplers at Fermilab


E. Harms

TTC Meeting

23-23 April 2007




# Coupler Design & Specs




## Conditioning Results to Date

- Maximum Power delivered - 71kW
  - 1.4 kW peak reflected
- Maximum Pulse Length - 1300 us/64kW
- Repetition Rate - 1/3 Hz, can now be adjusted to as fast as 2 Hz
- Temperature Rise - minimal
- Vacuum Activity - none
- Trips due to Arcing, etc. - none (expected)



## Industrialization process for XFEL Power couplers and Volume manufacturing

TTC meeting at Fermi lab, April 2007  
Serge Prat / LAL - Orsay





## Scope of delivery



Manufacturing parts and sub-assemblies

### In ISO 6 and ISO 4 clean room:

- Cleaning
- pre-assembly
- Vacuum oven outgassing
- Final assembly on test stand



Final assembly


1 000 couplers are needed for XFEL

- Vacuum pumping
- In situ baking
- Connect to RF power




Deliver 2 by 2



- Dismount
- Pack
- Transport





RF conditioning




# Some work results



Warm window sample






Sliding support



# Measurements on the New HOM Feedthrough and Heat Station for the HOM Coupler at CW Operation

Ed Daly


for the SRF Institute





# Heat Station and HOM Feedthroughs


Two HOM  
feedthroughs  
installed on  
C100 HTB  
test cavities.



Heat station  
bolted onto  
Return Header.

Cu mounting  
block is brazed  
onto the SST  
pipe.

# High Conductivity RF Feedthru



- Heat from Nb probe (item 6) is conducted through sapphire (item 2) to the copper sleeve (item 3).
- Heat is removed from copper sleeve via thermal strap to copper block on 2 K return header.



Prototype parts for Tesla-style cavity




# Conclusions / Future Work

- Conclusions
  - Stripline heat station isolates cable inner conductor heating from HOM feedthrough
  - Feedthrough performs well; maintains SC Nb probe tip
  - Very conservative thermal anchoring scheme
- Future Work
  - Test REN with improved heat stationing
    - Fields not reduced...
  - Quantify component performance limits – what simplifications can be made (impact on 12 GeV)
  - Understand dynamic losses in RF cables – better specifications

# CW Operation of TESLA HOM Loop Couplers

J. Knobloch, **BESSY**








## Disconnected the HOM Pickup cables

- Zero-field temperatures drop significantly (nearly 4 K)
- Temperature rise on tuner side very small & time constant short
- Larger time constant and temperature rise on coupler side.







# SRF Operations at SNS

Isidoro Campisi and Sang-Ho Kim

For the SNS SRF Task Force



# FPC interaction with cavity field



# Conclusion

- **HOM filters are not needed for SNS and will be phased out (blanked off for now and later removed)**
- **CCG's cannot provide interlock protection for FPC windows and will be replaced by electron current monitors**
- **Piezo tuners may be needed for only a handful of cavities and will be eliminated in the cryomodules being repaired**
- **Field emission (not necessarily from contamination) needs to be understood and brought under control**
- **Many failure modes are lurking to make the operation of even a modest number of cavities difficult**
- **Some failure modes are peculiar to pulse operation (e.g. one can afford to operate more deeply into field emission and be vulnerable to HOM problems, cryogenics overload etc.)**




TESLA Technology Collaboration Meeting  
Fermilab April 23-26, 2007

**OAK RIDGE NATIONAL LABORATORY**  
**U. S. DEPARTMENT OF ENERGY**




# Designs of the HOM coupler, T. Khabiboulline, FNAL


Initial design No.1




1-post design #3




Trimmed Initial design -1a




1-post design #4



Modified 2-post design #2




1-post Long design #5



## 3<sup>rd</sup> harmonic cavities for FLASH


### HOM Comparison

	Hp/H#1	Ep/E#1
HOM #1	1	1
<b>HOM #1a</b>	<b>0.4</b>	<b>0.4</b>
HOM #2	0.76	0.45
HOM #3	0.77	0.48
<b>HOM #4</b>	<b>0.67</b>	<b>0.31</b>
HOM #5	0.57	0.098
<b>cavity</b>	<b>7.4</b>	<b>3.5</b>







# Nb 9 cell cavity N4. 2<sup>nd</sup> cold test after HPR. 2007.04.21.




QvsT. Surface resistance  $R_s$  36 nOhms.



QvsE.  $E_{acc}=23$  MV/m. Limitation quench in the cavity. It was high x-rays at 15 MV/m. Then something happened and x-ray dropped ~1000 times.



Temperature sensor installed in the bottom end cell shows some heating during RF pulse.



~ 20 MV/m CW. T-sensor installed in the HOMs.

## **Conclusions:**

- The source of the heating of the HOM found.**
- Multipactor calculations and measurement results are in a good agreement.**
- Several new designs of the HOM developed for dumping of the multipactoring.**
- Modified (trimmed) old design HOM coupler allows reduce fields in coupler by factor of  $\sim 2.5$ . It shifts MP threshold to  $\sim 27$  MV/m. Test results ( $\sim 23$  MV/m, no MP) are in a good agreement with expectations. Cavities #3-6 will have trimmed design.**
- Prototype of a new one leg design is tested and approved for next Nb cavities. End groups with this design under production.**

# New HOM Dampers for KEK 45 MV/m 9-Cell Structures




- Part of Revision of End Structures –

Morozumi Yuichi

High Gradient SRF Development  
KEK



# Suppression of Multipacting in HOM Damper



# Summary

HOM Damper – Newly Designed for Improved  
Cavity Characteristics and  
Performance

Multipacting – Highly Reduced

HOM Damping – Improved or Acceptable  
(under Evaluation for Higher  
Frequency HOMs)

Accelerating Mode Decoupling – Checked

# High lights WP4

- very powerful simulation tools are available for new developments and investigation of problems
- together with this simulations there is a test stand available
- CW solution for the HOM coupler is available now