

Vertical Test Results of Tesla-type 9-cell Cavities for STF

E. Kako, H. Hayano, S. Noguchi, T. Shishido, K. Umemori,
K. Watanabe, Y. Yamamoto (KEK)
H. Sakai, K. Shinoe (ISSP, Univ. of Tokyo)
Moon Sung Ik (POSTEC) and Xu Qinjin (IHEP)


Outline

- **Overview of the Baseline Cavity System**
 - . System design feature
 - . Cavity fabrication and surface preparation
- **Results of Vertical Tests**
 - . Summary of 14 tests for 4 cavities
- **Particular Observation**
 - . Excitation of another passband mode
 - . Heating at HOM pickup antenna
 - . Multipacting at HOM couplers
- **Summary**

Overview of STF Baseline Cavity System


Cryomodule for
STF Phase 1.0

Tesla-type
STF Baseline Cavities
(Four 9-cell cavities)




Valve Box

Cryomodule Cross-section




Low loss type
High Gradient Cavities




Construction of a real accelerator with a beam operation.
Checking of the reliability as a total SC cavity system.

Tesla-type STF Baseline Cavity Package

Two Disk Window Input Coupler



Warm Window Cold Window




3 Cavities
(Vertical test)




Warm Coupler & Cold Coupler



HOM Coupler




Titanium
Jacket



Slide Jack Tuner


TTC Meeting at FN
AL 200

STF Baseline Cavity ; Improved Stiffness



TTC Meeting at FN
AL 200

Fabrication of STF Baseline Cavities



Fabrication at KEK-M.C.




HOM coupler



End-groups

Center-cells
(Tokyo Denkai ; RRR~300 Nb)



Four cavities were fabricated by MHI
(Mitsubishi Heavy Industries)

Surface Preparation of STF Baseline Cavities




Barrel Polishing
~100 μm




Initial EP
100 μm



Anneal
750°C, 3h



Pre-tuning
fo, flatness, HOM filter



Final EP
50 μm
(20, 30 μm)




Hot Rinse with
ultra-sonic bath
50°C, 1h



HPR 8MPa, 6~16h



Assembly



Baking 120°C, 40h

(HF or H₂O₂ Rinse, 1h)

TTC Meeting at FN
AL 200


Vertical Tests

Making clear the performance level of four 9-cell cavities fabricated by a Japanese company (MHI) and prepared by existent infrastructures at KEK.
→ Starting point in the first step for us

- Check and adjust of frequency, field flatness, HOM filter characteristics → consideration for a beam operation.
- Qo-Eacc curve, Eacc,max and x-ray radiation are standard data → Both Eacc (cell) by passband modes and heat spot (cell) by thermometry are also important.
- Cold leak test of vacuum seals in the same time
→ confirmation of reliability.

No hardware trouble and vacuum leak in the V.T !!

Vertical Test Results, $E_{acc,max}$, Q_0 , x-rays




Vertical Test Results, Eacc,max

One Result ;
a final performance
after processing in one surface treatment


Ave. Eacc,max = 20.3 MV/m
Limitation → Quench

14 tests for 4 cavities



TTC Meeting at FN
AL 200

Final Performance in Vertical Tests



Eacc,max


#1	20.8 MV/m
#2	29.4 MV/m
#3	20.5 MV/m
#4	20.2 MV/m

high $Q_o > 10^{10}$


TTC Meeting at FNAL
200

Vertical Test Results, Passbands meas.


Summary / #1 Cavity - 4th Tests (Passbands)



Fixed temp. sensors
(every 90°, total~40)



Mode cell	π	8 π /9	7 π /9	6 π /9	5 π /9	4 π /9	3 π /9	Eacc, max
#1, #9	20.8	26.3	29.3	21.9	18.3	22.6	14.9	29.3
#2, #8	20.8	23.4	15.5	0	12.5	29.6	29.6	29.6
#3, #7	20.8	17.3	5.9	21.9	21.6	12.9	14.9	21.9
#4, #8	20.8	9.7	22.8	21.9	3.7	32.7	14.9	32.7
#5	20.8	0	31.3	0	23.3	0	29.6	31.3
Heating at	#3	#9	#9	#3	#3	?	?	MV/m





Vertical Test Results, #1 Cavity


#1 Cav. 3rd

Comparison before/after 2nd B.P.
(additional surface removal of ~250 μm)

#1 Cavity ; 3rd and 4th Test




#1 Cav. 4th aft. 2nd Barrel Polishing



Vertical Test Results, #3 Cavity

#3 Cavity ; 1st and 2nd Test

Comparison before/after 2nd B.P.
(additional surface removal of ~250 μm)




#3 Cav. 1st

#3 Cavity ; 20.3 MV/m

Sorry, no data !!

Every cell \rightarrow 20.3 MV/m


#3 Cav. 2nd aft. 2nd Barrel Polishing




Vertical Test Results, #2 Cavity

#2 Cavity ; 4th and 5th Test


+ EP 20 μ m, H₂O₂ Rinse 1h,
Hot Rinse 1h, HPR 16h



#2 Cav. 4th aft. 2nd Barrel Polishing




#2 Cav. 5th



Vertical Test Results, Eacc of cells

Before (total~250 μm), after 2nd BP (total~500 μm)




Passband Excitation (1)

Strange Phenomenon ;

?? The Q_0 value goes up with the E_{acc} ??


#1 Cavity – 4th Test

Summary #1 Cavity - 4th Tests (π mode)





#3 Cavity – 2nd Test

Summary #3 Cavity - 2nd / Match, Detune, Overcouple





Heating at HOM pick-up antenna

$$H_{\text{antenna-tip}} \sim H_{\text{sp}} / 20.$$



At $E_{\text{acc}} = 10$ MV/m,
 $\Delta P_o = 8$ W
 $P_{\text{-loss (cal.)}} = 2$ W x 2

Slow Quench ~ 10 sec. Fast Quench ~ 1 msec.




Transition from SC state to normal state occurred at the location isolated thermally.




1st test (long antenna) 2nd test (short antenna)

Multipacting at HOM couplers


HOM - 1




HOM - 2



Heating at HOM couplers was observed at $E_{acc} = 2 \sim 16$ MV/m.





#1 2nd, $E_{acc} = 2.4$ MV/m, 1 s/div.



Cavity Assembly (#3 Cavity) ; Installation of Cold coupler and Tuner system

November, 2006'



TTC Meeting at FN
AL 200

Three cavities (#1, #2, #4 Cavity) covered with He Jacket

March, 2007'



Schedule of High Power RF Test in STF

- 2007'
- May First cool-down test (Phase 0.5)
Low power rf test (fo, Qext, HOM, Tuner, ...)
- June Installation of Warm coupler
Coupler conditioning at room temp.
- July Second cool-down test
High power rf test (Eacc,max, Lorenz detuning,
Voltage control, Compensation by Piezo-tuner,...)
- Aug. Disassembly of cryomodule
- Sept. String assembly of four cavities
- Dec. First cool-down test (Phase 1.0)
Start operation with beam
- 2008' Replace with improved four cavities (Phase 1.5)

Towards the next step

(Summary of the vertical tests at KEK)

Achieved $E_{acc,max}$ in vertical tests :

→ max. 29 MV/m, but 20 MV/m for three cavities
lower than our expectation (> 25 MV/m)

- Need further strict quality control in both cavity fabrication process and surface preparation for the next 4 cavities (in Phase 1.5)
 - improve welding procedure and clean environment at MHI
 - construction of new infrastructures at STF, (now ongoing)
- Cryomodule test after string assembly of four cavities:
 1. Pulsed operation at 29 and 20 MV/m without any degradation
 2. Suppression of Lorenz force detuning by improved cavity stiffness
 3. Compensation of Lorenz force detuning by a piezo-tuner

END

Thank You for Attention !