# ALPSII: Overview and Status Report

The search for Axion-like particles with long baseline cavities

Aaron Spector 14th Patras Workshop Hamburg, Germany June 19, 2018




HELMHOLTZ RESEARCH FOR GRAND CHALLENGES

# Light Shining through a Wall Concept


Measuring the conversion-reconversion of Axion-like particles

### LSW concept

- High power source directs light through a magnetic field creating a flux
  Axion-like particles through a wall
- Magnetic field converts Axion-like particles back to photons
- ALPS II: Optical cavities amplify the conversion-reconversion probability
  - Coupling sensitivity: 2×10<sup>-11</sup> GeV<sup>-1</sup> Mass: < 0.1 meV



### **ALPS II Sensitivity**



### **Experimental Infrastructure at DESY**

Providing the foundation for ALPS II

### **Optics Lab**

- Optical subsystems tested in ALPS IIa lab
- ALPS IIc (100 m cavities) in HERA tunnel

### **HERA Infrastructure**

- 5 T superconducting dipole magnets
- Use existing HERA cryogenic infrastructure
  - 10 have been unbent (need 20)
  - See poster by Dieter Trines



DESY. | ALPS II: Overview and Status Report | Aaron Spector, June 19, 2018

### **ALPS II Optical System**


#### A unique set of challenges

#### Two 100m optical resonators

- 30W amplified NPRO input laser
- PC: 150 kW circulating power
- RC: 120,000 finesse

#### Challenges

- Maintenance of dual resonance
- Maintenance of spatial overlap
- Light tightness 1 photon / 2 weeks



### **ALPS II Optical System**


#### A unique set of challenges

#### Two 100m optical resonators

- 30W amplified NPRO input laser
- PC: 150 kW circulating power
- RC: 120,000 finesse

#### Challenges

- Maintenance of dual resonance
- Maintenance of spatial overlap
- Light tightness 1 photon / 2 weeks



# **ALPS II Optical System**


### A unique set of challenges

### Two 100m optical resonators

- 30W amplified NPRO input laser
- PC: 150 kW circulating power
- RC: 120,000 finesse

#### Challenges

- Maintenance of dual resonance
- Maintenance of spatial overlap
- Light tightness 1 photon / 2 weeks




### **ALPS IIa Status**

Addressing challenges in the lab

### **Cavity Power Buildup**

- 50 kW circulating in 10 m Production Cavity
- Finesse of ~ 93,000 in 10 m Regeneration Cavity



DESY. | ALPS II: Overview and Status Report | Aaron Spector, June 19, 2018

### **ALPS IIa Status**


### Addressing challenges in the lab

#### **Dual Resonance**

- Length stabilization system meets relative stability requirements without additional seismic isolation
  - 5kHz actuation on a 2" mirror
  - Stability ~ 0.5 pm (532 nm)
  - Meas. of EPR changes see poster by Dennis Schmelzer

### **Spatial Overlap**

- Alignment drift of CBB mirrors measured for 2 different mounts
- Both meet requirements




### **ALPS II Detectors**

#### Two independent measurement systems


#### **Transition Edge Sensor**

- Microcalorimeter measures temp. change induced by absorbed photon
- Squid readout
- New cryostat being installed



#### Heterodyne detection system

- AC measurement of interference of regenerated field with local oscillator
- Stable path length between cavities
- No fundamental background
- Demonstrated in testbed at UF
- See poster by Giuseppe Messineo



### **ALPS II Detectors**

#### Two independent measurement systems



- Microcalorimeter measures temp. change induced by absorbed photon
- Squid readout

chip

New cryostat being instal


 $T_{bath}$ 



asurement systematic. ce of lator

ated in testbed at UF





ver.

 $T_{bath} = 80 \text{ mK}$ 

 $T_C = 140 \text{ mK}$ 

avities

### **ALPS II Timeline**

- HERA tunnels and hall currently being cleared
- Magnet installation will begin before the end of the year
- Optics installation will begin in the middle of 2019
- ALPS II data run scheduled 2020

### Conclusions

- ALPS II is making progress in the three key areas of the experiment
  - Infrastructure:
    - Clearing of the tunnels
    - Magnet unbending
  - Optics:
    - Development of the cavity systems in ALPS IIa
  - Detection technologies:
    - Demonstration of Heterodyne
    - New cryostat for TES
- ALPS II data run scheduled 2020

### **Thank you!**


• This work would not be possible without the support of the DESY infrastructure groups.

### **Questions?**

### **ALPS II cavities in context**

#### Approaching the state of the art


#### Plot from LIGO T-1400226-v6



DESY. | ALPS II: Overview and Status Report | Aaron Spector, June 19, 2018

### **Length Stabilization Results**

Actuating on a 2" mirror with a 5 kHz bandwidth




DESY. | ALPS II: Overview and Status Report | Aaron Spector, June 19, 2018


# **Transition Edge Sensor**

#### Two independent measurement systems

### **Transition Edge Sensor**


- Microcalorimeter measures temp. change induced by absorbed photon
- Squid readout
- 7% energy resolution





### **Heterodyne Detector**

- Backgrnd. signals:
- < 1 photon/10<sup>6</sup> s
- Meas. signals:
- ~ 3 photons/100 s




### **ALPS IIa Status**

### Addressing challenges in the lab

### **Dual Resonance**

- Length stabilization system meets relative stability requirements without additional seismic isolation
  - 5 kHz actuation on a 2" mirror
  - Stability ~ 0.5 pm (532 nm)
  - Measurements of EPR See poster by Dennis Schmelzer on effective point of reflection changes



Demonstration of the length stability requirements for ALPS II with a high finesse 10 m cavity

#### Jan H. Põld,<sup>1,\*</sup> and Aaron D. Spector<sup>1</sup>

<sup>1</sup>Deutsches Elektronen-Synchrotron (DESY), Notkestraße 85, D-22607 Hamburg, Germany \*jan.pold@desy.de

arXiv:1710.06634v1 [physics.ins-det] 18 Oct 2017