

# Heavy Ion Beam Test with the cw-CH-Cavity

C. Burandt<sup>1,2</sup>

K. Aulenbacher<sup>1,2,4</sup>, W. Barth<sup>1,2,5</sup>, M. Basten<sup>3</sup>, M. Busch<sup>3</sup>,  
F. Dziuba<sup>1,2</sup>, V. Gettmann<sup>1,2</sup>, M. Heilmann<sup>2</sup>, S. Lauber<sup>1,2,4</sup>,  
J. List<sup>1,2,4</sup>, H. Podlech<sup>3</sup>, A. Schnase<sup>2</sup>,  
M. Schwarz<sup>3</sup>, S. Yaramyshev<sup>2,5</sup>


<sup>1</sup>HIM, Helmholtz Institute Mainz, Mainz, Germany

<sup>2</sup>GSI Helmholtzzentrum, Darmstadt, Germany

<sup>3</sup>IAP, Goethe Univ. Frankfurt, Frankfurt, Germany

<sup>4</sup>KPH, Johannes Gutenberg Univ., Mainz, Germany

<sup>5</sup>National Research Nuclear Univ., Moscow, Russia



## SHE and “Material Science” requirements:


- high average beam currents
- high repetition rate (50 Hz)
- high duty factor up to 100 %


## FAIR requirements (implies synchrotron injection):

- high peak beam currents
- low repetition rate (max. 3 Hz)
- low duty factor 0.1 %


## Helmholtz Linear Accelerator HELIAC:

- Independent source + injector
- Continuous beam energy variation
- **cw operation @ high gradients → superconducting rf acceleration**







$H_{211}$  mode of "pillbox" cavity



Cross-bar-H-mode cavity



Current  
H Field










Table 1: Main Parameters of the Cavity


$\beta$ ( $v/c$ )		0.059
Frequency	MHz	216.816
Accelerating cells		15
Effective length ( $\beta\lambda$ )	mm	612
Diameter	mm	409
Tube aperture	mm	18 / 20
$G$	$\Omega$	52
$R_a/Q_0$		3240
$R_a R_S$	$k\Omega^2$	168
$E_a$ (design)	MV/m	5.5
$E_p/E_a$		6.3
$B_p/E_a$	mT/(MV/m)	5.7




- Capacitive coupling of RF power
- Coaxial antenna setup (inner conductor made from copper)
- Divided into cold & warm part by 2 ceramic windows ( $\text{Al}_2\text{O}_3$ ), TiN coated
- 5 kW cw operation, cold window connected to  $\text{LN}_2$  supply
- 216.816 MHz operation frequency with 33 MHz bandwidth



- 2017: Successful commissioning (presented 2018 at M&T-meeting)
- Additional beam times in 2018
  - Confirmation of 2017 results
  - Additional investigations








- 2017: Successful commissioning (presented 2018 at M&T-meeting)
- Additional beam times in 2018
  - Confirmation of 2017 results
  - Additional investigations






## Validating Calculations of Energy Gain





How to understand and optimize the longitudinal matching?

Phase Space  
unknown




Poster  
presentation by  
Simon Lauber


variation of rebuncher  
settings

W.I.P.


phase space  
(symbolic plot)



reconstruction



many bunch shapes  
(symbolic plot)






## Properties of the tuning system:

- Capacitive bellow tuner
- Electrical drives:
  - Slow stepper motor:  $\pm 1 \text{ mm}$  ( $\approx \pm 60 \text{ kHz}$ )
  - Fast piezo actuator:  $\pm 4 \mu\text{m}$  ( $\approx \pm 240 \text{ Hz}$ )



## Practical experience:

- Microphonics caused by stepper motor
- Pronounced hysteresis for piezo drive
- Bellow tuner actuated by He pressure changes?







- Verified beam dynamics simulations
- Beam acceleration above design gradient
- Evaluated BPM as part of cold string
- UNILAC-LLRF proven to be adequate for SRF operation
- Beam-based alignment
- He-Pressure sensitivity higher than expected
- Piezoresistive tuners show distinctive hysteresis
- Power coupler
  - ceramics suffered significantly
  - high dynamic heat load
  - high static heat load
 ⇒ major rework in progress




Poster  
presentation  
by Julian List






## 15-gap demonstrator cavity




## „short“ cavity






## Transformation of Test Site


- Transfer line to cryoplant
- Modification of cave
- Change matching line
- New site for RF amplifiers
- New control room



**2017/2018 Setup**




**2020 Setup**






- 155 m<sup>2</sup> Clean room
  - ISO6/ISO4
  - HPR
- RF infrastructure:
  - Radiation shielded test site
  - 5kW RF amplifier + LLRF
- He infrastructure:
  - 3 m<sup>3</sup> LHe reservoir
  - Transfer lines
  - He-recovery compressor





02/2015	Funding of the <i>Advanced Demonstrator</i> within POF3
09/2016	Ordering of two short CH-cavities
11/2018	Tendering of cryostat
05/2019	Modification of radiation protection shelter @GSI
06/2019	Delivery of short cavities
12/2019	Link of testing area to STF cryoplant
04/2020	Delivery of cryostat
09/2020	Commissioning of beamline (w/o cryostat) @ GSI
04/2021	Assembly of cryomodule @ HIM
06/2021	Beamtest @ GSI

**Thank you for your attention!**



---

**Collaboration partners**

**GSI / HIM**

**KPH - Johannes Gutenberg University Mainz**

**IAP - Goethe University Frankfurt**