

PXD Commissioning at DESY

Results, issues and experiences

Hua Ye

(hua.ye@desy.de)




On behalf of the DESY PXD team: V. Babu, A. Brundtland, C. Camien, K. Gadow, L. Macharski, F. J. Mueller, C. Niebuhr, U. Packheiser, F. Poblitzki, R. Stever, M. Takahashi

2018.10.09, PXD2020 Workshop, DESY, Hamburg

PXD Commissioning at DESY



PXD Commissioning at DESY






Motivation:

To verify the transport and mounting procedure, study the systematic performance. Pre-commissioning for the final campaign at KEK

- ❖ Mar - Apr prepare the clean room
- ❖ Apr.30 DHH arrives DESY
- ❖ May.10 HS2p3 is mounted onto dummy beam pipe
- ❖ July.10 HS2p3 is dismounted and sent back to MPI
- ❖ July.11 HS1p3 is mounted
- ❖ Aug. 30 HS1p3 is dismounted, delivered to KEK



DESY setup



IOCs


- Running on belle-iocpxd:
 - DHC 1x4
 - DHE 5x4
 - DHI master 1x4
 - DHI slave 5x4
 - genesys-ps-phase2-L0
 - iocPowerUpSeq
 - iocpsApp
 - dhh-sequence
 - configApp
- Running on belle-control:
 - Ps-control
 - Archiever
- Running on Raspi:
 - iocCrateController
- Running on Bonndaq:
 - utility_IOC, one for each PXD module

Grounding



Half-shell mounting

It has become a routine.




PXD Half-shell mounting procedures

PXD half shell mounting		1	PXD half shell mounting		2
Action	Comment				
Bring transport box into CR grey area			Lower crane until 10 mm above BP, guide fwd kapton steel finger into its groove (p13)		
Print this checklist for additional notes			Lower Grabber carefully onto BP: watch pins (p14)		
Print Photos of L1 M1.2 screw orientation			Screw brass SCB holder loosely to BP with 8x M2.5x12, check carbon tubes		
Have boxes for loose parts ready			Fix 8x M2.5x12 (@edge last) 1by1, watch carbon tubes		
Check BP diameter: 25±0.01 mm, (gap to L1 screw washer nominal 0.39mm)			Release straps from kaptons		
Mirror			Remove Raendei screws (Grabber-SCB holder)		
Fix box on 15° rest bwd side (p3)			Note crane counter		
Adjust BP with master jig parallel to crane flange (p4)			Lift crane up (p18)		
Adjust crane to 1.5 mm pins with alignment bar 10 mm spanner			P2: Remove M6 screws		
Lift up crane, exchange pins to thinned ones (p5)			P1: Hold and remove grabber (19)		
Remove rest from table to floor			Attach PP to endflange on one side! Slide PP through slots, watch PP connectors!		
Move box to preparation table			Mount PP on other endring		
Open box lid and remove it			Remove crane (p20)		
Check Raendei screws			Mount lower profiles (p21)		
Check kapton strap holder screws: fix loose ones			Mount PXD cover plate		
Lift support plate on holes out of box			Remove fwd steel ladder, secure screws with Kapton		Remove steel ladders?
Place it next to box on the preparation table			Check bwd peek screws 40 mNm (SCB to brass support)		
Remove empty box to grey area			Remove fwd peek screws (SCB to brass support)		
Check carbon fibre pipes and sensor for bends			Close slots in end flange with armaflex pads		
Place temporary storage onto preparation table			Mount Cu pipe connectors and connector holder, use fresh washer: 90° 5+5mm spanner		
Loosen brass 8 M2.5x12, edge ones first, check carbon tubes			Check grounding of SCB to BP		
P1: Hold grabber			Check CO2 pipes		
P2: Unscrew 6x brass screws M2.5x12			Add FOS fibers		
P1: lift up grabber and place 90° turned into temp. storage					
Bring support plate into storage box					
(? Check M1.2 screws torque: 13/15 mNm ?)					
Check M1.2 screw orientation, take photos					
Check steel ladder screws (50 mNm)					
P1: Lift grabber and slide onto crane flange. (p12)					
P2: attach 2x M6x20 1by1					
Release M6 screws crane to grabber to equalize gap above/below flange					
Date:	Name:		Date:	Name:	

Thermal tests


Mylar foils between modules and SCB

- Dozens fo thermal cycles between -25 to 18°C
- Thermal performance: CO2 at -25°C, L2_022, DCD&DHP on




- For reference, in thermal mockup, CO2@-25°C, T(EOS) ~25°C, no Parylene, no Mylar

Pedestals: FWD




Module performance

Pedestals: BWD




Module performance

Noise: FWD



Module performance

Noise: BWD



Module performance


HS1p3

- L1_019:
 - W43_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9884>
 - W03_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9990>
- L1_020:
 - W45_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9998>
 - W42_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9989>
- L1_014:
 - W01_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/10000>
 - W45_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9992>
- L1_036:
 - W13_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9999>
 - W13_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9997>
- L2_029:
 - W09_OB2, <https://elog.belle2.org/elog/PXD-Mass-Testing/9883>
 - W32_OF1, <https://elog.belle2.org/elog/PXD-Mass-Testing/9988>
- L2_034:
 - W12_OB2, <https://elog.belle2.org/elog/PXD-Mass-Testing/9901>
 - W41_OF1, <https://elog.belle2.org/elog/PXD-Mass-Testing/9996>


HS2p3

- L1_017:
 - W44_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9469>
 - W32_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9472>
- L1_018:
 - W41_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9470>
 - W41_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9471>
- L1_015:
 - W02_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9476>
 - W47_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9474>
- L1_028:
 - W03_IB, <https://elog.belle2.org/elog/PXD-Mass-Testing/9475>
 - W02_IF, <https://elog.belle2.org/elog/PXD-Mass-Testing/9473>

Gated Mode tests



Normal charge collection



Gated mode

Clear on/off currents:

Normal: $\sim 27/-23\text{mA}$

1xGM per frame: $\sim 45/-30\text{mA}$

2xGM per frame: $\sim 65/-50\text{mA}$

Present by Felix J. Mueller in this session


Issues and Experiences

What we suffered

- Mysterious Noise in the power phase in Hera-west hall (source: a broken monitor?)
 - Different link stability between prototype and final DHI (within VME and ATCA crates)
 - Adjust the optical transmitter voltage: 3V -> 3.3V
 - UPS is necessary?

What we have learned

- Systematic tests of multiple modules working with the final DHH.
- crosstalk exists between modules, high noise was observed in neighbour modules when they are in different DHH.
 - need to synchronized the DHH with FTSW



- Many experiences gained during transport, mounting, etc.
- The system is still much simpler than the final system at KEK.

Acknowledgement

To all of you.

Vielen Dank!

Thanks a lot!

ありがとうございます!

谢谢!