Preparation for ZZ and recovery after access

Thomas Wamsat

February 5, 2019









Topics

- Magnet current during ZZ
- ZZ Injector
- Restart Injector after ZZ
- ZZ XTL
- Restart XTL after ZZ
- ◆ ZZ XTD-1-3-4-7-
- Restart XTD-1-3-5-7 after ZZ
- ZZ XTD-2-4-10-
- Restart XTD-2-4-10- after ZZ
- ZZ and Restart XTD6 and XTD9
- Useful hint




Magnet current during ZZ

- Before ZZ with magnets under current, MXL or RCs make a safety audit to ensure that there is no work near the beam pipe
- Point out to the colleagues who enter the tunnel that the magnet current is on
- Also the shift leaders should point that out while the ZZ team enters the ZZ door
- Under this conditions ZZ with magnets under current and without attendance of MKK colleagues is permitted
- Injector and XTL all magnet connections are covered
- XTD1-3-5-7 and XTD2-4-10 not every magnet connection is covered sufficiently
 - ◆ In XTD1-3-5-7 and XTD2-4-10 using a bike with magnets under current is prohibited



ZZ areas

- Injector
- XTL
- XTD1-3-5-7 (SASE2 branch)
- XTD2-4-10 (SASE1 branch)
- XTD6 (SASE2 Photon tunnel)
- XTD9 (SASE1 photon tunnel)
- XTD8 (empty tunnel)





ZZ Injector


- Save a file (sequencer)
- Use sequence "Separate Injector from XTL" (required to close BS TD1)
- Switch of RF
 - GUN
 - A1 and AH1 (with energy manager)
 - Injector TDS (uncheck RF on/off)
- In case of work near beam pipe, switch off and ground magnets
 - Use 'Magnet overview' panel to switch off magnets and ask MKK for grounding (also Dump dipole will be switched off, no effect on XTL beam permission





Restart Injector after ZZ

- Ask MKK to unground magnets
- Switch on magnets and load file values
- Switch on BB.62.I1D (use "Dump Switch" panel
- Switch on RF
 - GUN (see training "GUN operation")
 - A1 and AH1 with energy manager
 - Injector TDS
- Use sequence "Join Injector with XTL"





ZZ XTL


- Save a file
- Set golden orbit in orbit FBs
- Use sequence "Separate Injector from XTL" to keep Injector running
- Shut down RF by using "Linac Energy Manager"
- Shut down TDS B2 (press STBY)
- In case of work near beam pipe, switch off and ground magnets
 - Use 'Magnet overview' panel to switch off magnets by clicking on each section and press Switch off
 - Ask MKK for grounding





Restart XTL after ZZ


- Unground magnets
- Switch on magnets and load file
- Cycle all main magnets
- Ask Shift leader for beam permission
- Restart RF using the 'Linac Energy Manager'
 - See training "LLRF"
- Use sequence "Join Injector with XTL"
- Use corrector CBB.62.I1D to correct orbit and re-establish transmission
- Switch on orbit FBs to re-establish transmission





ZZ XTD1-3-5-7 (South branch SASE2)


- Save a file
- Set golden orbit in orbit FBs
- Use sequence "Separate SASE2 from XTL"
- In case of work near beam pipe, switch off and ground magnets
 - Use 'Magnet overview' panel to switch off magnets by clicking on each section and press Switch off
 - Ask MKK for grounding





Restart XTD1-3-5-7 after ZZ

- Use sequence "Join SASE2 with XTL"
- Cycle special grounded magnets
- In case magnets were grounded, unground, switch on and reload file and cycle main magnets
- Switch on orbit FB to re-establish transmission






Thomas Wamsat, February 5, 2019

ZZ XTD2-4-10 (North branch SASE1/3)


- Save a file
- Set golden orbit in orbit FBs
- Use sequence "Separate SASE1/3 from XTL"
- In case of work near beam pipe, switch off and ground magnets
 - Use 'Magnet overview' panel to switch off magnets by clicking on each section and press Switch off
 - Ask MKK for grounding






Restart XTD2-4-10 after ZZ

- Use sequence "Join SASE1/3 with XTL"
- Cycle special grounded magnets
- In case magnets were grounded, unground, switch on and reload file and cycle main magnets
- Switch on orbit FB to re-establish transmission



ZZ XTD6 and XTD9

- No magnets in this areas
- For ZZ in XTD6 close BS TD6
- For ZZ in XTD9 close BS TD9





Useful hint

 Beam warning, as requirement for beam permission, for any interlock section can only be given, when all interlock keys are locked

Thank you!

Questions?

