

SNS PPU Cavity Fabrication and Test Results

Pashupati Dhakal

On the behalf of PPU
Cavity Team

January 27, 2022



Outline

- Background
- Preparation of cavity qualification and Helium vessel welding prior to production run
- Cavity qualification steps
- RF performance
- Lessons learned and challenges
- Summary



SNS PPU Upgrade

- Upgrade will double the proton beam power from 1.4 to 2.8 MW by adding 7 additional cryomodules each contains four six cell high beta ($\beta=0.81$) SRF cavities.
- This will be accomplished by ~50% increase in beam current, from 25 to 38 mA and an increase in the final beam energy from 1.0 to 1.3 GeV

| Parameters | Original SNS high-beta cryomodule | PPU high-beta cryomodule |
|--|--|--|
| E_{acc} ($=E_0 T_g$, T_g : Transit time factor at $\beta=0.81$) (MV/m) | 15.8 $Q_0 > 5 \times 10^9$ | 16.0 $Q_0 > 8 \times 10^9$ |
| Fundamental power coupler (FPC) rating, peak and average (kW) | 550, 50 | 700, 65 |
| External Q of FPC, Q_{ex} | 7×10^5 ($\pm 20\%$), fixed type | 8×10^5 ($\pm 20\%$), fixed type |
| Material of cavity | High RRR niobium (RRR > 250) for cells, reactor-grade niobium for end groups | High RRR niobium (RRR > 250) for both cells and end groups |
| Higher-order mode couplers per cavity | Two (one at each end group) | None |

PPU Upgrade (Original Vs Upgrade)




Figure 3.3. End group modification. (Top: cavity with modified end group for the PPU. Bottom: Original SNS high-beta cavity).




Figure 3.15. Original (left) versus new (right) vacuum vessel.




Figure 3.16. Original (left) versus new (right) vacuum jacket design.




Figure 3.17. JT valve positions for the PPU cryomodule (left) and the original (right) cryomodule.




Figure 3.18. Original (left) versus new (right) supply end can.



Figure 3.5. Original (left) versus new (right) helium vessel designs.




Figure 3.19. Original (left) versus new (right) return end can.

SNS HB cavities (Original)

$$\beta = 0.81,$$

$$f = 805 \text{ MHz}$$


$$E_{pk}/E_{acc} = 2.19,$$

$$B_{pk}/E_{acc} = 4.72 \text{ mT}/(\text{MV}/\text{m})$$

$$R/Q = 483 \text{ ohms}$$





Maximum Gradient Distribution
SNS Cryomodules



- The performance of the original SNS cavities in the linac is mainly limited by field emission and multipacting, resulting in lower operating gradients at 13.5 MV/m on average.
- A high-beta spare cryomodule was developed in-house at SNS and has been installed in the tunnel for operation since summer 2012 with average gradient greater than 16 MV/m
- A major change on spare module was the cavity being treated by electropolishing over BCP used in original HB cavities.

Helium Vessel Welding Development Work


- Production cavities were delivered to JLab, under vacuum, ready to be tested. After the VTRF qualifications, HVs are added before qualifying for the string assembly.
- Prior to production cavities Jefferson Lab received 3 (old design) cavities to develop the HV welding process (horizontal under vacuum) as original HV was done in vertical.
- HV welding processes was developed. The frequencies and field flatness were measured before and after the welding. The field flatness was within $\pm 2\%$ and in an average ~ -100 KHz frequency shift was observed.



PPU Upgrade Cavities




- SNS was responsible to contract production cavities. The cavities contract was awarded to RI, initially for 30 cavities
 - 7 cryomodules plus 2 spares
- Additional two cavities were ordered with an additional 8th cryomodule to be built.
- The vendor was responsible for procurement of material, material inspection, fabrication and processing.
- Cavities send to JLab under vacuum ready to be tested.

Cavity Production plan



EP Process Development (Original)


- During 2018, JLab received 3 cavities to investigate the EP process on cavities
 - The cavities were EP'd at JLab and RF tests were performed.
- RF tests were not so encouraging due to issues with EP, Q-disease, MP and FE.
- Re-processing wasn't done due to schedule constraints.



- EP process was developed with the vendor. Both JLab and SNS scientists visited the vendor several times during the start up of EP process.
- Two cavities that were EP'd at vendor site and RF tested at SNS met RF performance
 - EP parameters were fixed for production cavities.


For more see: J. Mammosser et al., SRF 2021

Vertical Test Qualification of PPU Cavities at JLab



VTA Qualification of PPU Cavities (01/01/2022)

- Jefferson Lab received all **32** cavities from vendor under vacuum, ready for testing. First cavity received on 09/04/2021
- **29** cavities were VTA RF tested to date as received from vendor. Total **80 RF** test were done including bare and tanked cavities.
- **24** cavities completed HV welding.
- **4** string assembly was completed.
- About **75%** of cavity related work is completed.




Acceptance Criteria for Vertical RF Testing

| Final Run Vertical Test Acceptance Criteria | Test to be Conducted | Nominal Value for Acceptance for PPU String Assembly |
|---|--|---|
| 1. Field Emission at 16 MV/m | Measure Eacc vs Rad with admin limit at no greater than 22 MV/m | Integrated dose of $\leq 20\text{mR/hr}$ At 16MV/m |
| 2. Gradient Limit | Measure the Eacc vs Qo with admin limit at no greater than 22 MV/m | $\geq 18\text{ MV/m}$ |
| 3. Unloaded Q | As part of the Eacc vs Qo measurement | $Qo \geq 8e9$ up to 16MV/m |
| 4. Field Probe Coupling | Calculated from decay measurement and power balance | Range: $7e11$ to $2e12$ |
| 5. Pi Mode Frequency | Measured with calibrated frequency counter in closed loop at 2.1K | $805.6 \pm 0.250\text{ MHz}$ |
| 6. Residual Magnetic field | Measured in dewar during cold test | $\leq 20\text{mG}$ |


Cavity RF Performance (Bare Cavities – VTA test)

- First few cavities received from vendor were limited by early field emission.
- The FE on cavities were eliminated after JLab reprocessing with high pressure rinse and clean assembly.
- In some occasion multipacting was observed ~ 10-15 MV/m, but it was processed with high power processing.
- After the cavity qualifies from VTA test, the cavity sent to helium vessel welding work station and HV welding was conducted under vacuum in horizontal position.
- After the completion of HV welding, with appropriate external cleaning (most cavities received additional HPR), the cavity retested in VTA.




Cavity RF Performance (Bare vs Tanked cavities – VTA test)


- The re-test of the tanked cavities reproduced the performance of bare cavity.
- We suspected the burst disk was collecting rinse water and re-contaminating the cavity during processing steps. So, the burst disk was removed from assembly at vendor site after the first 4 cavities.
- We started to see the performance improve on PPU05 which had no field emission as delivered from vendor.
- Additional change was made to replace the ethanol rinsing after EP to detergent degreasing and DI water rinsing before HPR, following JLab's successful procedure. **All second HPR rinsed cavities at JLab showed little or no field emission up to 22 MV/m**



Cavity RF Performance (Bare cavities – VTA test)




- 42% (12/29) of cavities were qualified as received from vendor.
- 100% (10/10) cavities met PPU spec after reprocessing with HPR at JLab.
- 7 cavities still need reprocessing with HPR to meet specification. Based on 10 cavities work at JLab, project is going forward with HV welding and re-test (requalify) after tanking.



Challenge : Minimizing FE on Tanked Cavities

- The main challenge we encountered was the cross-contamination of the tanked cavities during the disassembly process.
- Periodically the exterior cleaning process needed to be changed to mitigate the early FE of tanked cavities, which resulted in multiple RF tests of tanked cavities.
- Current process includes the exterior pressure wash of tanked cavity, DI water rinse, long high pressure rinse and final clean assembly.
- Process change minimized the number of cycle the cavities needed for reprocessing.



Cryomodule Production


- CM1 nearly completed
 - Will go into CMTF next week
 - Expect to ship to SNS in time for high-power testing in March
- CM2 is currently in early stage of Final Assembly
- CM3 & CM 4 are in Cold Mass Assembly work station



Summary & Highlight

- All 32 cavities were delivered to JLab required for 8 cryomodules (No spares).
- 42% of cavities passed initial RF test as received from vendor.
- 100% of bare cavities met specification after reprocessing with HPR at Jlab with all cavities reaching 22 MV/m limited by admin limit.
- 4 cryomodule string assemblies are complete.
- First cryomodule is scheduled to be delivered to SNS in March.

Production – Well-Defined Process Flow: On Track



Acknowledgements

To all Jefferson Lab Cavity Production
Staff
&
PPU Cavity Team at SNS