Status of ILC Global Activities / KEK



KEK / IDT-WG2 Shin MICHIZONO (KEK)

- ✓ ILC accelerator
- ✓ ILC international collaboration
- ✓ Technology level
 - ✓ SRF
 - ✓ Positron source
 - ✓ Damping ring
 - ✓ Final focus
 - ✓ Beam dump
- ✓ Technical preparation at Pre-lab
 - ✓ WP-1/2
- ✓ Civil/Safety/Environment
- ✓ Summary

250GeV ILC





ILC machine parameters



ILC	electron/positron	ILC250	
Beam Energy	GeV	125 (e-) and 125 (e+)	
Peak Luminosity (10^34)	cm-2 s-1	1.35	
Int. Luminosity	ab-1/yr	0.24* * 5,000-hour operation at peak lumin	osity
Beam dE/E at IP		0.188% (e-), 0.150% (e+)	
Transv. Beam sizes at IP x/y	nm	515/7.66	
Rms bunch length /	cm	0.03 (σ _z)	
beta*	mm	bx*=13mm, by*=0.41mm	
Crossing angle	mrad	14	
Rep./Rev. frequency	Hz	5	
Bunch spacing	ns	554	
# of bunches		1,312	\backslash
Length/Circumference	km	20.5	
Facility site power	MW	111	
Cost (value) range	\$B US	~5 (tunnel and accelerator)	
Timescale till operations	years	(~1) + 4(prep.) + 9(construction)	





Potential for upgrades



The ILC can be upgraded to higher energy and luminosity.

			Z-Pole [4]			Higgs [2,5]		500Ge	eV [1*]	TeV [1*]	
			Baseline	Lum, Up	Baseline	Lum. Up	L Up.10Hz	Baseline	Lum. Up	case B	
Center-of-Mass Energy	Ecm	GeV	91.2	91.2	250	250	250	500	500	1000	Energy
Beam Energy	E _{beam}	GeV	45.6	45.6	125	125	125	250	250	500	
Collision rate	f _{col}	Hz	3.7	3.7	5	5	10	5	5	4	
Pluse interval in electron main linac		ms	135	135	200	200	100	200	200	200	
Number of bunches	n _b		1312	2625	1312	2625	2625	1312	2625	2450	
Bunch population	Ν	10 ¹⁰	2	2	2	2	2	2	2	1.737	
Bunch separation	$\Delta t_{ m b}$	ns	554	554	554	366	366	554	366	366	
Beam current		mA	5.79	5.79	5.79	8.75	8.75	5.79	8.75	7.60	
Average beam power at IP (2 beams)	PB	MW	1.42	2.84	5.26	10.5	21.0	10.5	21.0	27.3	
RMS bunch length at ML & IP	σz	mm	0.41	0.41	0.30	0.30	0.30	0.30	0.30	0.225	
Emittance at IP (x)	γe* _×	μm	6.2	6.2	5.0	5.0	5.0	10.0	10.0	10.0	
Emittance at IP (y)	γe* _{>}	nm	48.5	48.5	35.0	35.0	35.0	35.0	35.0	30.0	
Beam size at IP (x)	σ^*_{\times}	μm	1.118	1.118	0.515	0.515	0.515	0.474	0.474	0.335	
Beam size at IP (y)	σ^*	nm	14.56	14.56	7.66	7.66	7.66	5.86	5.86	2.66	
_uminosity	L	10 ³⁴ /cm ² /s	0.205	0.410	1.35	2.70	5.40	1.79	3.60	5.11	Lumi.
Luminosity enhancement factor	H_{D}		2.16	2.16	2.55	2.55	2.55	2.38	2.39	1.93	
Luminosity at top 1%	$L_{0.01}/L$	%	99.0	99.0	74	74	74	58	58	45	
Number of beamstrahlung photons	n _g		0.841	0.841	1.91	1.91	1.91	1.82	1.82	2.05	
Beamstrahlung energy loss	δ_{BS}	%	0.157	0.157	2.62	2.62	2.62	4.5	4.5	10.5	
AC power [6]	Psite	MW			111	138	198	173	215	300	
Site length	Lsite	km	20.5	20.5	20.5	20.5	20.5	31	31	40	

ILC construction/operation cost



ILC accelerator (including tunnel) construction cost is ~5 B\$.

	TDR: ILC500	ILC250	Conversion to:
	[B ILCU]	[B ILCU]*	[B JPY]
	(Estimated by GDE)	(Estimated by LCC)	(Reported to MEXT/SCJ)
Accelerator Construction: sum	n/a	n/a	635.0 ~ 702.8
Value: sub-sum	7.98	4.78 ~ 5.26	515.2 ~ 583.0
Tunnel & building	1.46	1.01	111.0 ~ 129.0
Accelerator & utility	6.52	3.77 ~ 4.24	404.2 ~ 454.0
Labor: Human Resource	22.9 M person-hours	17.2 M person-hours	119.8
	(13.5 K person-years)	(10.1 K person-years)	
Detector Construction: sum	n/a	n/a	100.5
Value: Detectors (SiD+ILD)	0.315+0.392	0.315+0.392	76.6
Labor: Human Resource (SiD + ILD)	748+1,400 person-years	748+1,400 person-years	23.9
Operation/year (Acc.) : sum	n/a	n/a	36.6 ~ 39.2
Value: Utilities/Maintenance	0.390	0.290 ~ 0.316	29.0 ~ 31.6
Labor: Human Resource	850 FTE	638 FTE	7.6
Others (Acc. Preparation)	n/a	n/a	23.3
Uncertainty	25%	25%	25%
Contingency	10%	10%	10%
Decommission	n/a	n/a	Equiv. to 2-year op. cost

*1 ILCU= 1 US\$ in 2012 prices

Main advantages



- A linear accelerator is more advantageous for accelerating electron and/or positron beams to higher energies.
- The spin of the electron and/or positron beam can be maintained during the acceleration and collision. This can help significantly improve measurement precision.
- The small surface resistance of the SRF accelerating structure (cavity) made of Nb enables the efficient power transfer from the AC power source to the beam.
- Further energy efficiency improvements are considered as part of the of Green ILC concept, which aims to establish a sustainable laboratory.



Circulating beam loses energy by synchrotron radiation. Linear collider can extend its collision energy by longer tunnel/ higher gradient.



Status of ILC Global Activities / KEK



KEK / IDT-WG2 Shin MICHIZONO (KEK)

- ✓ ILC accelerator
- ILC international collaboration
 - ✓ Technology level
 - ✓ SRF
 - ✓ Positron source
 - ✓ Damping ring
 - ✓ Final focus
 - ✓ Beam dump
 - ✓ Technical preparation at Pre-lab
 - ✓ WP-1/2
 - ✓ Civil/Safety/Environment
 - ✓ Summary

Brief History of ILC Collaboration





IDT organization





ILC International Development Team

Executive Board

Americas LiaisonAndrew Lankford (UC Irvine)Working Group 2 ChairShinichiro Michizono (KEK)Working Group 3 ChairHitoshi Murayama (UC Berkeley/U. Tokyo)Executive Board Chair and Working Group 1 ChairTatsuya Nakada (EPFL)KEK LiaisonYasuhiro Okada (KEK)Europe LiaisonSteinar Stapnes (CERN)Asia-Pacific LiaisonGeoffrey Taylor (U. Melbourne)



From IDT to Pre-Lab, ILC construction

IDT is formed under ICFA. KEK serves as its host.

Stage 1 International Development Team (~1.5 years)

ILC Pre-Lab. is established by MOU's among the laboratories.

Stage 2 ILC Pre-Laboratory (4 years)

ILC Lab. is established by governmental agreement.

Stage 3 ILC Laboratory (10 years for construction)

Stage 4 Experiment at ILC!

Pre-lab proposal

ILC newsline June 1,2021

https://newsline.linearcollider.org/2021/06/01/ilc-preparatory-laboratory-proposal-released/

The ILC International Development Team (IDT) was established by the International Committee for Future Accelerator (ICFA) in August 2020, to prepare the ILC Preparatory Laboratory (Pre-lab) that would complete the technical development and engineering preparation for the International Linear Collider project to be ready for construction. During the same period, governmental authorities of interested nations are expected to forge an agreement on the sharing of the cost and responsibilities for the construction and operation of the ILC facility and on the organisational structure and governance of the ILC Laboratory.

After ten months of work, the IDT has achieved the first major milestone of completing the ILC Pre-lab proposal, which outlines the organisational framework, an implementation model and work plan of the Pre-lab. Three working groups were the key players and an impressive number of people

have been contributing to this effort. Working Group 1 worked on the

Proposal for the ILC Preparatory Laboratory (Pre-lab)

International Linear Collider International Development Team

During the preparatory phase of the international Linear Collider (ILC) project, all technical development and engineering design needed for the start of ILC construction must be completed in parallel with intergovernmental discussion of governance and sharing of responsibilities and cost. The ILC Preparatory Laboratory (Pre-lab) is conceived to execute the technical and engineering work and to assist the intergovernmental discussion by providing relevant information upon request. It will be based on a workwide partnership among aboratories with a headquarter hosted in Japan. This proposal, prepared by the ILC International Development Team and endorsed by the international Committee for Future Accelerators, develope and on the pre-lab. Elaboration, and work pain of the Pre-lab. Elaboration, modification and adjustment should be introduced for its implementation, in order to incorporate requirements arising from the physics community, laborationes, and governmental automation in the ILC.



Artist's impression of the ILC. In

Full text of Pre-lab proposal: https://zenodo.org/record/4884744

mandate, governance model, organisational structure and Pre-lab start-up procedure. Working Group 2 identified necessary technical development and engineering preparation work for the ILC accelerator and site construction. Working Group 3 discussed a strategy for developing the compelling ILC physics programme. Then the Executive Board took the responsibility of compiling the document. It was very encouraging to see the growing number of participants in those activities.

The IDT activity now enters the next phase of implementing the steps for establishing the Pre-lab along the lines described in the proposal. The plan for the accelerator technical development and engineering preparation work needs to be further elaborated and people and laboratories with interest and expertise in the work must be identified. The physics community needs encouragement and support for further exploring the physics potential of the ILC and converging towards concrete designs of experiments. Discussion on the Pre-lab start-up process must be initiated among the world key laboratories.

An equally crucial factor now is to understand what kind of process is needed to achieve the establishment of the Pre-lab. Unlike the ILC itself, the Pre-lab activities will be driven at the level of laboratories rather than having a direct involvement of governmental authorities. For the managements of interested laboratories to engage seriously in the discussion of responsibility sharing for the Pre-lab activities, however, a signal from the Japanese government indicating its interest in hosting the ILC and supporting the Prelab would be required. In parallel, we will make further effort to gain more support for the ILC worldwide.

We will continue to do our best for the swift realisation of the Pre-lab. Exciting times are head of us all.

Timeline



Now we are at pre-preparation phase (waiting for the preparation phase). Four years preparation (@ILC Pre-Lab) and ~10 years construction (@ ILC Lab.).

	IDT		ILC Pi	re-Lab)	ILC Lab.										
	PP	P1	P2	P3	P4	1	2	3	4	5	6	7	8	9	10	Phys. Exp.
Preparation CE/Utility, Survey, Design Acc. Industrialization prep.																
Construction																
Civil Eng.																
Building, Utilities																
Acc. Systems																
Installation																
Commissioning																
Physics Exp.																

Technical preparation



IDT-WG2 summarized the technical preparation as work packages (WPs) in the technical preparation document.



1MILCU=1M\$(2012)

Status of ILC Global Activities / KEK



KEK / IDT-WG2 Shin MICHIZONO (KEK)

- ✓ ILC accelerator
 ✓ ILC international collaboration
 ✓ Technology level
 ✓ SRF
 ✓ Positron source
 ✓ Damping ring
 ✓ Final focus
 ✓ Beam dump
 ✓ Technical preparation at Pre-lab
 ✓ WP-1/2
 - ✓ Civil/Safety/Environment
 - ✓ Summary

Area systems of the ILC



Sources

- •Creating particles **So** •polarized elections/positrons
- •High quality beams

- Damping ring
- Low emittance beams
 - •Small beam size (small beam spread)
 - •Parallel beam (small momentum spread)
- Acceleration

Main linac

- superconducting radio frequency (SRF)
- •Getting them collided *Final focus* •nano-meter beams
- •Go to *Beam dumps*



ILC Technology level



Since the publication of the conceptual design report (RDR) in 2007 and the Technical Design Report (TDR) in 2013, the technical development has been progressing steadily toward the start of construction.

Status	(RDR)	(TDR)		2021 (EDF	٤)*
SRF cavity, CM	~ 2017 Technology development ->Mo	odel work-> Prototype	2018 ~ 2021 High performance an reduction of cavit	International mas	s production, nonstration
SRF Linac	Model work: small-scale models, partial models.	l/component	European XFE	L user operation	
e- source	Tech. Design->Tec	~ 2017 h. Development->Tec	h. Demonstration	Tech. confirmation	
e+ SOUICE Undulator scheme	~ 2017 Tech. Design->Tech. Develop	oment	2018 ~ 2021 Tech. Demonstration	arget and magnetic focusi	nstruc
e+ SOUICE e-driven scheme	~ 2017 Tech. Design->Tech. Develo	pmen	2018 ~ 2021 Tech. Demonstration	Target and capture ca	vity O
DR	Design->Tech. Developm	~ 2017 nent-> Tech. demonstr	ration achieved at KEK ATF	Kicker	=
Final focus	Design->Tech. Developm	~ 2017 ent->Tech. demonstra	ation achieved at KEK ATF	Stable op.	
Dump	~ 2017 Tech. Design->Tech. D	evelopment	2018~2021 Facility design	Remote handling	
	: ~2017 : 2018 ~ 2021 : Pre-lab TT	C 2022 (Shin MICF	IIZONO)	*EDR:Detailed I Design Report r start constructio	Engineering equired to on. 16

Progress in SRF





TTC 2022 (Shin MICHIZONO)

Americas

International Cooperation in SRF



<u>2018-2021:</u>

- Achieve stable electric field E > 35 MV/m through US-Japan cooperation
 - Improvement of Nb material manufacturing process and properties (FG, MG, LG)
 - Improvement of surface treatment technology
 - Low temperature (10-20C) EP Two-step baking (75C and 120C) Optimization of cooling speed (flux expulsion)
- Cavity manufacturing efficiency improvement and dust ٠ prevention work automation Europe-Japan cooperation
- KEK-STFdemonstrated the beam acceleration at 33 MV/m ٠
- High Gradient Cryomodule (HGC, FNAL) (in progress)
 - Aim to demonstrate 38 MV/m



5 10 15 20



TTC 2022 (Shin MICHIZONO)

Improving efficiency in cavity manufacturing

Automation of Dust Prevention Work





inglation of the process in Virtual R



30

25 Eace [MV/m] 45



Progress in DR



TTC 2022 (Shin MICHIZONO)

Progress in final focus





Progress in beam dump



Status of ILC Global Activities / KEK



KEK / IDT-WG2 Shin MICHIZONO (KEK)

- ✓ ILC accelerator
- ✓ ILC international collaboration
- ✓ Technology level
 - ✓ SRF
 - ✓ Positron source
 - ✓ Damping ring
 - ✓ Final focus
 - ✓ Beam dump
- Technical preparation at Pre-lab
 - ✓ WP-1/2
 - ✓ Civil/Safety/Environment
 - ✓ Summary

Technical preparation



IDT-WG2 summarized the technical preparation as work packages (WPs) in the technical preparation document.



1MILCU=1M\$(2012)

WP-1: Cavity industrial-production readiness



In recent years, U.S.-Japan/Europe-Japan cooperation is working on cavity performance improvemen and cost reduction. The yield will be evaluated.



To be confirmed the best method for mass-production 2022 (Shin MICHIZONO)

WP-2: CM Assembly, Global transfer and Performance assurance





Status of ILC Global Activities / KEK



KEK / IDT-WG2 Shin MICHIZONO (KEK)

- ✓ ILC accelerator
- ✓ ILC international collaboration
- ✓ Technology level
 - ✓ SRF
 - ✓ Positron source
 - ✓ Damping ring
 - ✓ Final focus
 - ✓ Beam dump
- ✓ Technical preparation at Pre-lab
 - ✓ WP-1/2
- ➡ ✓ Civil/Safety/Environment
 - ✓ Summary

ILC Site Candidate Location in Japan: Kitakami





Topography and geology assumed in civil engineering design of ILC



- Rock mass is generally uniform over a long distance of 50 km
- Solid rock zone is less susceptible to ground vibration
- No "known faults" crosses the site, which is expected to be active faults



We evaluated candidate sites by selecting the most suitable geology for construction.

Reduces civil and cost risks due to massive water inflow, etc.

Construction of road tunnels and other projects may pass through areas with poor geology, depending on the conditions of the starting and ending points. ILC selects candidate sites with priority given to geology, avoiding soft ground in advance.

- Seismic survey (total 30 km), electromagnetic survey (13 km), and borehole survey (7 boreholes) were carried out.
- In the area of the accelerator tunnel, hard and uncracked granite is considered to be widely distributed.

Radiation safety and community understanding



Facility design for radiation safety (radiation protection and long-term maintenance of radioactive materials)

 KEK and other large accelerators around the world have enough experiences

Such as proton accelerators with more severe activation (Selection of materials for beam dump windows and positron targets)



- The final design for safety, including the structure of radiation shielding, maintenance methods for activated components, measures against leakage of beam dump water, and long-term maintenance of activated materials, is being carried out with international cooperation.
- Specific design of facilities and equipment through industry-academia collaboration
- Studying measures for drainage, earthquake, and radiation (AAA WG)



Briefing sessions to promote understanding among local Universitie Universitie Universitie Universitie

- Explanation of safety management and environmental impact measures
- Briefing sessions were held at 13 venues, including the Community Exchange Center, in order to broaden the participation of local residents.
- Questions asked at the briefing sessions and answers to questions and concerns raised by local residents were compiled and made available on the website.

https://tipdc.org/inquiries#qa (in Japanese)



Environmental Initiatives



Environmental impact assessment policy

"ILC Environmental Assessment Advisory Board" was established with external experts (2019)

Chair: Kenichiro Yanagi (Professor Emeritus, Meiji University), Chairman of Tokyo Olympic and Paralympic Environmental Assessment Committee

Based on the project characteristics of ILC,

- Basic guidelines for assessment, and
- Implementation structure, process, and
- Methodology and assessment targets

 (environmental impact, social and economic impact)

Summary of the Discussion

https://www2.kek.jp/ilc/ja/contents/docs/Strateg ic_Environmental_Assessment_of_the_ILC_Pr oject_Summary_of_the_Discussion_r.pdf



Flow of environmental assessment for the ILC project (assumed)

"Green ILC" for the environmen

(Green ILC WG, AAA)

https://tipdc.org/assets/uploads/2020/12/guideline03.pdf (in Japanese) https://tipdc.org/assets/uploads/2020/12/guideline04.pdf (in Japanese)

- Energy measures: Biomass, Power-GRID, waste heat utilization
- Utilization of resources: Use of local wood for ILC-related facilities, use of high-quality granite produced during tunnel excavation

Status of ILC Global Activities / KEK



KEK / IDT-WG2 Shin MICHIZONO (KEK)

- ✓ ILC accelerator
- ✓ ILC international collaboration
- ✓ Technology level
 - ✓ SRF
 - ✓ Positron source
 - ✓ Damping ring
 - ✓ Final focus
 - ✓ Beam dump
- ✓ Technical preparation at Pre-lab
 - ✓ WP-1/2
- ✓ Civil/Safety/Environment
- ✓ Summary

Summary



- ILC R&D activities have been carried out by international collaboration.
- Now IDT (International Development Team) leads the ILC collaboration.
- Efforts to improve the performance and reduce the cost of SRF cavities are being made through US-Japan and Europe-Japan cooperation.
- IDT-WG2 summarized technical concerns pointed out by the ILC advisory panel and the SCJ in the "Technical preparation document" as work packages (WPs) (by the global in-kind contribution).
- Since the cavity production in the ILC construction will be shared among the world's three regions, and mass production demonstration of SRF is an important next step.
- The design of the facility has been carried out based on the topographical, geological and hydrological surveys of the envisioned area.



Thank you for your attention