# LUXE: A NEW EXPERIMENT TO STUDY **NON-PERTURBATIVE QED**

### LOUIS HELARY

HELMHOLTZ RESEARCH FOR GRAND CHALLENGES


LUXE - T20 KICKOFF MEETING, NOVEMBER 12TH 2021





#### INTRODUCTION: QED, VACUUM AND STRONG FIELD QED

- If one apply a strong electromagnetic field on a vacuum:
  - $W_{\text{field}} < 2 m_{\text{e}}$
  - Quantum ElectroDynamics becomes non perturbative  $\rightarrow$  Strong field QED (SFQED)!
- Experimental consequences:
  - Field-induced ("Breit-Wheeler") Pair Creation
  - Modified Compton Spectrum.
- Non-perturbative and strong field QED have never been reached in laboratory, accessible by LUXE!
  - Experimentally reached by colliding highly boosted electrons with high-intensity laser!
- Main Luxe scientific goals:
  - Pioneer new regime of quantum physics.
    - Measure positron rate as a function of laser intensity.
    - Measure Compton edges.
  - Study BSM physics.
- LUXE results will have effect over future accelerators, astro- and particle physics and atomic physics!







• Experiment will be located in annex of XS1 shaft building in Osdorfer Born.


#### • Beam parameters for LUXE:

Parameter	Мах	Typical
Beam Energy [GeV]	17.5	14
Bunch Charge [nC]	1	0.25
Bunch length (RMS) [fs]	80	20
Beam Size [mm]	variable	10
Repetition Rate [Hz]	1-10	13500 (in 10 Hz bursts)

#### Experiment designed to have no impact on photon science!











#### LUXE FOOTPRINT IN XS1 BUILDING






### LASER


- Use Ti-Sa laser, with CPA technique
  - Peak wavelength at 800nm
- Staged installation
  - Start from a 40 TW laser (that can be the JETI40 or a new
  - Then move to commercial 350 TW system.
- Installation planned in UG02 laser to interaction point (IP) wi long vacuum pipe.
- Dedicated IP vacuum chamber.
- Could share space and more with ChirpTaper project.
  - Potentiality to share up to laser front end (being discussed)
- Summary, main characteristics of clean room
  - Volume clean-room 300m<sup>3</sup>
  - Temperature in the clean-room: 21±0.5 °C
  - Humidity in the clean-room:  $40 \pm 5\%$




	Parameter	Pha	Pha		
	Laser Power [TW]	4	35		
	Laser energy after compression [J]	1	1		
w system)	Percentage of Laser in focus [%]				
	Laser focal spot size w <sub>0</sub> [µm]	> 8	> 3	>	
vith 40m	Peak intensity in focus [×10 <sup>19</sup> Wcm <sup>-2</sup> ]	1.9	13.3	12	
	Peak intensity parameter $\xi$	3.0	7.9	23	
	Peak quantum parameter $\chi$ for $E_e = 16.5$ GeV	0.56	1.50	4.4	
ed). Laser cl	ean Laser pipe Mir	ror 1 Mirr	ror 2	Mir	









#### **EXPERIMENT**












#### ONE WORD ON THE PLANING


- CDR recently released.
  - Now working toward TDR for 2022.
- Experiment now decoupled from beam-line planing.
  - With the caveat that to start data-taking experiment need beam-line.
  - Would be nice if most of experiment can be installed in 2024.
    - Long shutdown of the XFEL.
  - Baseline:
    - Data taking to start in 2024.
      - Start with e-laser.
      - γ-laser to start in 2025.
      - Laser upgrade (350 TW) in 2026.
    - Run until XFEL want to construct new fan (2029 for now).
  - Working on alternative scenario where missing pieces of the experiment could be installed in regular shutdown of the XFEL.

• In parallel of review continue detector R&D, and experiment planification.

Plan to perform multiple test-beam campaign in the future.

				021
		Q1	Q2	Q2
Beamline	Finalize design			
	Prepare installation			
	Infrastructure installation			
	Beamline installation			
	Commission beamline			
Laser	Clean room installation			
	Finalize design			
	install diagnostics			
	40TW laser installation			
	40TW laser commission			
	350 TW laser installation			
	350 TW laser commission			
Detectors	Finalize design & prototyping			
	Construction & indiv. testing			
	Combined testing			
	Install & commission			
	upgrades installation (tbc)			
Commission				
Data taking	phase-0 e-laser/y-laser			
	phase-I e-laser/y-laser			








7

- The LUXE experiment will allow to measure QED in uncharted regime! • Might expect some surprises there!
- Experiment working toward being integrated in DESY-Roadmap.
- Installation planing of different elements is currently being investigated.
  - Laser as soon as possible, to allow early commissioning.
  - As much as possible of the TD20 line and experiment in 2024.
    - Rest in shorter shutdown.
- Experiment installation is highly stageable and adaptable with external constraints.
  - The sooner the data-taking can start the better for the physics.





## Back up



#### **Beam Extraction**

- Oct. 2021: Hire of additional technician/engineer at MEA and MVS
- review by MAC already in 2020)
- Nov. 2021: Full inventory for long lead items (magnets, power supplies, beam instrumentation) exists, start to prepare purchase
- also requirements for SASE1/SASE2 chirp-taper projects, eventually hire additional personnel for MKK and MPC
- Nov. 2021: Start mechanical engineering for beamline integration and support (Note: engineering for beamline components does exist to a large extend); start vacuum engineering
- Jan. 2022: Purchase of long lead items (magnets, power supplies, auxiliaries)
- Sep. 2022: Finalise mechanical, vacuum and XS1 infrastructure engineering, internal review
- Jul. 2023: Last delivery of long lead items, quality check and pre-integration
- Oct. 2023: Finalise installation plan and resource requirements (integrated into XFEL2024 schedule), internal review

#### **Experiment**

- Dec. 2021: Start of ISO6 Laser clean-room technical specifications to prepare call for tender
- Feb. 2022: Start design supporting structure in experimental area, to prepare call for tender.
- Mar. -May 2022: Start Laser clean-room and support structures call for tender(3-6 months).
- Aug. 2022: Start design of experiment counting room refurbishment.
- Oct. 2022: Finalise early installation plan and resource requirements. **Dec. 2022:** Early phase install: XS1-UG02: counting room and laser clean-room; XS1-UG03: Supporting structure.
- Jan. 2023: Install and commissioning JETI40 in XS1
- Jul. Oct. 2023: Last delivery of long lead items (Magnets and Detectors), quality check and pre-integration
- Oct 2023: Finalise installation plan and resource requirements (integrated into XFEL2024 schedule), internal review

• Oct. 2021: Freeze of lattice for XFEL 2024 upgrade, including beam extraction to TD20 up to LUXE final focus triplet, internal review (Note: external

• Nov. 2021: Start of XS1 technical integration meetings to allocate and distribute space for technical and laser infrastructure in XS1/XHE1, including

• Dec. 2021: Draft installation plan ready => Goal install "as much as possible" during 2024 shutdown and the rest in shorter 2-4 week shutdowns.


• Jul. -Aug. 2022: End call for tender Laser clean-room and support structures, company chosen start technical design and installation planing







#### **IP CHAMBER**

- IP Chamber main characteristics:
  - Vacuum: 10^-6 mbar
  - Dimensions: 2m\*1.m\*0.4m





## THANK YOU FOR YOUR ATTENTION!



#### **Conceptual Design Report for the LUXE Experiment**

H. Abramowicz<sup>1</sup>, U. Acosta<sup>2,3</sup>, M. Altarelli<sup>4</sup>, R. Aßmann<sup>5</sup>, Z. Bai<sup>6,7</sup>, T. Behnke<sup>5</sup>, Y. Benhammou<sup>1</sup>, T. Blackburn<sup>8</sup>, S. Boogert<sup>9</sup>, O. Borysov<sup>5</sup>, M. Borysova<sup>5,10</sup>, R. Brinkmann<sup>5</sup>, M. Bruschi<sup>11</sup>, F. Burkart<sup>5</sup>, K. Büßer<sup>5</sup>, N. Cavanagh<sup>12</sup>, O. Davidi<sup>6</sup>, W. Decking<sup>5</sup>, U. Dosselli<sup>13</sup>, N. Elkina<sup>3</sup>, A. Fedotov<sup>14</sup>, M. Firlej<sup>15</sup>, T. Fiutowski<sup>15</sup>, K. Fleck<sup>12</sup>, M. Gostkin<sup>16</sup>, C. Grojean<sup>\*5</sup>, J. Hallford<sup>5,17</sup>, H. Harsh<sup>18,19</sup>, A. Hartin<sup>17</sup>, B. Heinemann<sup>†5,20</sup>, T. Heinzl<sup>21</sup>, L. Helary<sup>5</sup>, M. Hoffmann<sup>5,20</sup>, S. Huang<sup>1</sup>, X. Huang<sup>5,15,20</sup>, M. Idzik<sup>15</sup>, A. Ilderton<sup>21</sup>, R. Jacobs<sup>5</sup>, B. Kämpfer<sup>2,3</sup>, B. King<sup>21</sup>, H. Lahno<sup>10</sup>, A. Levanon<sup>1</sup>, A. Levy<sup>1</sup>, I. Levy<sup>22</sup>, J. List<sup>5</sup>, W. Lohmann<sup>‡5</sup>, T. Ma<sup>23</sup>, A.J. Macleod<sup>21</sup>, V. Malka<sup>6</sup>, F. Meloni<sup>5</sup>, A. Mironov<sup>14</sup>, M. Morandin<sup>13</sup>, J. Moron<sup>15</sup>, E. Negodin<sup>5</sup>, G. Perez<sup>6</sup>, I. Pomerantz<sup>1</sup>, R.Pöschl<sup>24</sup>, R. Prasad<sup>5</sup>, F. Quéré<sup>25</sup>, A. Ringwald<sup>5</sup>, C. Rödel<sup>26</sup>, S. Rykovanov<sup>27</sup>, F. Salgado<sup>18,19</sup>, A. Santra<sup>6</sup>, G. Sarri<sup>12</sup>, A. Sävert<sup>18</sup>, A. Sbrizzi<sup>§28</sup>, S. Schmitt<sup>5</sup>, U. Schramm<sup>2,3</sup>, S. Schuwalow<sup>5</sup>, D. Seipt<sup>18</sup>, L. Shaimerdenova<sup>29</sup>, M. Shchedrolosiev<sup>5</sup>, M. Skakunov<sup>29</sup>, Y. Soreq<sup>23</sup>, M. Streeter<sup>12</sup>, K. Swientek<sup>15</sup>, N. Tal Hod<sup>6</sup>, S. Tang<sup>21</sup>, T. Teter<sup>18,19</sup>, A. Zarubin<sup>29</sup>, K. Zeil<sup>3</sup>, M. Zepf<sup>18,19</sup>, and A. Zhemchukov<sup>16</sup>

#### CDR, accepted by European Physics Journal ST: https://arxiv.org/abs/2102.02032





12



SITY OF SCIENCE



			2021				20	22			20	2023			20	024			2025				2026				20	2027			20	28			2029		
		Q1	Q2	Q2	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1 (	22	Q3	Q4
	Finalize design																																				
	Prepare installation																																				
	Infrastructure installation																																				
	Beamline installation																																				
	Commission beamline																																				
Laser	Clean room installation																																				
	Finalize design																																				
	install diagnostics																																				
	40TW laser installation																																				
	40TW laser commission																																				
	350 TW laser installation																																				
	350 TW laser commission																																				
Detectors	Finalize design & prototyping																																				
	Construction & indiv. testing																																				
	Combined testing																																				
	Install & commission																																				
	upgrades installation (tbc)																																				
Commission																																					
Data taking	phase-0 e-laser/y-laser																																				
	phase-I e-laser/y-laser																																				

