

# Undulator Hall Ventilation at LCLS

J. Welch, SLAC NAL, [welch@slac.stanford.edu](mailto:welch@slac.stanford.edu)

XFEL Tunnel Ventilation and Air Conditioning workshop, Oct 25-26, 2010,  
DESY, Hamburg, Germany

# Contents

- ✱ Requirements
- ✱ Scheme
- ✱ Performance






# Requirements

- ✱ The Undulator Hall houses a 130 m long undulator which is the heart of the FEL
- ✱ It is made of temperature sensitive permanent magnets precisely aligned to microns.
- ✱ It has a separate air condition system from the rest of the laboratory.
- ✱ The temperature of the circulating air surrounding the undulator must be held within 0.5 C of 20 C at all times.
- ✱ In the event of any HVAC failure, including power failure, the temperature excursions must never be more than 5 C.

# Tunnel

- \* 170 m long
- \* Above the water table







# Parameters

- \* 34,000 m<sup>3</sup>/hr total from two air-handler units (AHU)
- \* Regulate on supply air temperature, with set-point adjusted to make average undulator 20C
- \* Average tunnel air flow velocity ~0.4 m/s
- \* recirculated, with 10% fresh air.


# Radiation

- \* Undulator Hall air is separate from Beam Dump air
  - \* 5 W maximum continuous loss of beam used for radiation calculations for short-lived radionuclide calculations.
- \* Air exchange rate at (10% fresh air), about one air-change per hour, was deemed acceptable by radiation physics department.

# Air Handlers



“Tempered” water is made from chilled and hot water and used to control the air temperature.





# Heating and Cooling Loads

- \* Sources of heat

- \* lighting (5 or 30 fc), wiring losses, hot water lines, etc.


- \* undulator equipment - design limit 50 W/m

- \* Sources of cooling

- \* tunnel walls and floor

- \* chilled water lines passes through tunnel

# Equipment Heat Loads






# Loads and Temperature Profile


<b>Total Heat Load</b>		<b>All</b>	<b>8205 [W]</b>		
<b>Undulator System</b>			<b>7780 [W]</b>	45.8	
<b>Conventional Facilities</b>			<b>303 [W]</b>	1.8	
<b>Distributed Load Parameters</b>					
magnet water convective load	0 W/m	If two 2 in lines with no insulation at 19 C, should be -2.4 W/m.			
chilled water convective load	-5.2 W/m	the -5.2 value is based on 60% specification			
LCW for Beam Dump	7.2 W/m	Two 3 inch pipes 90 F, with 1 inch insulation			
Wall heating load	-24 W/m	varies slowly with time, -22 W is Kleyn est. 6 month after HVAC starts			
AC & DC Power line load	5.0 W /m	5 kW ave. transmitted AC power @ 3% loss, and 4.1 W/m for DC magnet wires			
Lighting load	19 W /m	19 W/m is 5 fc, lights out for normal operation			
Quad & corrector wires	0.09 W /m	per wire pair. 3.1 W/m for 18 units at full power, from A deLuca. I put in factor of 0.5 for opeational			
<b>HVAC Parameters</b>					
air flow (cfm)	20,000 cfm	design			
Max Temp Required	20.56 deg C	design			
Min Temp Required	19.44 deg C	design			
Discharge Temperature	19.50 deg C	design			
<b>Temperature and Net Load Distributions</b>				<b>Undulator System Estimate</b>	
Location Name	Location	Air Temperature	Delta Q	Integrated Q	Magnet Water Lines Convective load
					Quad Power Lines (defunct)



# Ground temperature



# Ground temperature fluctuations (estimated)







QuickTime™ and a  
Microsoft Video 1 decompressor  
are needed to see this picture.



# Cooling rate by walls and floor




# Net estimated temperature profile



# Spatial uniformity measured

33X12 PRECISION  
RTD THERMISTORS




AIR FLOW →




# Temperature Stability

- ✱ 1 week during normal operation, include 1 day of beam-off for accelerator maintenance.



# Transient response



# Humidity

- \* There is no direct humidity control
- \* Benign climate, no mold, comfortably dry year round.
- \* Recent (light rain outside) 57%



# Summary

- \* Very satisfied with the performance
  - \* excellent stability, especially temporal
  - \* fault tolerant
  - \* low maintenance, no down-time
- \* Limited heat load budget affects accelerator upgrades.