



This project has received funding from the European Union's Horizon 2020 Research and Innovation programme under GA No 101004730.

Vertical cavity testing at DESY

AMICI ETIAM Workshop on Vertical SRF Cavity testing
14-15.09.2022 DESY Hamburg

Mateusz Wiencek (DESY MSL)




Outline

- AMTF Hall overview
- Cavities preparation area overview
- Test stands overview
- VT procedure
- Current projects
- Future plans and possibilities
- Cavities testing in serial mode
- Summary




AMTF Hall Overview




Cavities preparation area overview

- 6 inserts
 - 1 x Up to 4 x 1.3GHz 9-cells cavities
 - 1 x Up to 3 x 1.3GHz and 1 x QPR housing
 - 2 x Up to 2 x 704MHz 6 cells cavities
 - 2 x R & D 1.3GHz with additional instrumentation




Vertical cryostats

2 x



Vertical test stands hardware

- XATC1
 - 2 amplifiers (1.3 GHz & 704 MHz) and auxiliaries
- XATC2
 - Currently only 1.3 GHz



Frequency counter

Power meters

Spectrum Analyzer

Oscilloscope

RF Generator


Phase Shifter

PLL


ADCs

BuBo (relay system)

RF Reference



- Most signals available in DOOCS and EPICS
- Measurements performed with semi – automatic Labview software
- Some additional scripts and software for VNA




DESY Test stand XATC1 summary

XATC1				
No	Property name	Value	Unit	Comment
1	LHe volume	2000	L	
2	Operating temperature	4.2 – 1.4	K	
3	Diameter / size	1.150	m	
4	Number of inserts	6		For 2 cryostats
5	RF Frequency	1300, 704	MHz	
6	Maximum Incident power	200	W	
7	Additional instrumentation	Second Sound, Additional T-sensors, Magnetometers		R&D inserts
8	Typical testing rate (VTs / year)	127 (2021)		For 2 cryostats
9	Possibility to test naked cavities	YES	YES / NO	
10	Infrastructure for small intervention	YES	YES / NO	

DESY Test stand XATC2 summary


XATC2				
No	Property name	Value	Unit	Comment
1	LHe volume	2000	L	
2	Operating temperature	4.2 – 1.4	K	
3	Diameter / size	1.150	m	
4	Number of inserts	6		For 2 cryostats
5	RF Frequency	1300	MHz	
6	Maximum Incident power	200	W	
7	Additional instrumentation	Second Sound, Additional T-sensors, Magnetometers		R&D inserts
8	Typical testing rate (VTs / year)	127 (2021)		For 2 cryostats
9	Possibility to test naked cavities	YES	YES / NO	
10	Infrastructure for small intervention	YES	YES / NO	

VT procedure




- Whole procedure usually takes around 2 weeks
- Cryogenic operations and 2K measurements around 3 - 5 working days
- Requires good cooperation within several experts from different fields
 - Vacuum
 - Mechanics
 - Cryogenics
 - RF

VT procedure – Incoming inspection






- RF Incoming
 - FM Spectra
 - Antennas shortcuts check
- Mechanical incoming
 - Shock loggers disassembly
 - Torques on screws
 - Positions of auxiliaries
 - AV closed properly?
 - etc...





LONG SIDE		Example photo
2.5.10	Check the presence of the Beamtube flange (red arrow) and check if there are 6 threaded screw holes M8 or M6 on the flange (yellow arrow). OK <input checked="" type="checkbox"/> NOK <input type="checkbox"/> Comment:	
2.5.11	Make note number from the beamtube flange (long side): Beam tube flange – DESY 1.4429 ESU Ch 920396 Trinos 02/14	
2.5.12	Check the presence and orientation of the He inlet ports at the long side Cavity Beamtube Flange (should be 4). Correct orientation – one of the He inlets lies on the straight line connecting Pick-Up antenna and brackets. OK <input checked="" type="checkbox"/> NOK <input type="checkbox"/> Comment:	
2.5.13	Check number of bolts and check if they are tightened (30 Nm) – should be 12 bolts, 24 nuts and 12 washers. OK <input checked="" type="checkbox"/> NOK <input type="checkbox"/> Comment:	


VT procedure – insert assembly and checks




VT procedure – move insert to cryostat




VT procedure - cool down






- Standard cool down performed with FSM by cryo shift
- Different cool down speeds possible




VT procedure - measurements at 2K – FM Spectra, HOM Spectra




- Fundamental mode spectra
- HOM Spectra




VT procedure - measurements below T_c - Q vs E



- Q vs E
 - 2K \rightarrow Cavity performance
 - 1.8K \rightarrow Second sound
 - 1.5K \rightarrow Obtain R_{BCS} at 2K




VT procedure - measurements below T_c - $Q_{vs}T$






• $Q_{vs}T$


- Obtain R_{res}
- E_{acc} between 3 and 5 MV/m
- 3.5 K \rightarrow 1.4 K
- Movable antenna




VT procedure - measurements below T_c – Second Sound




VT procedure - measurements around T_c - FvsT



- FvsT
 - Constant pressure inside cryostat
 - Frequency change around T_c




VT procedure – after cold test



- Shielding opening, radiation measurement
- Warm – up to room temperature
- Vacuum disconnection at cryostat
- Transport of the insert to preparation area
- Vacuum connection, LC & RGA after cold test
- Vacuum disconnection
- Cavity dismounting

VT procedure – outgoing inspection



- Mechanical outgoing
 - Torques on screws
 - Positions of auxiliaries
 - AV closed properly?
 - Shock loggers assembly
 - etc...
- Additional procedures (if requested)
- RF Outgoing
 - FM Spectra
 - Antennas shortcuts checks



Current R&D projects

Single cells R&D


- Mid-T backing
- Low-T backing



SRF GUNs





QPR




Current and recently finished external projects

- ESS MB
- ESS HB
- POLFeL
- Another 1.3GHz cavities on request from industry



Future plans

- Test stands
 - Switch test stand hardware to digital system (MTCA4)
 - B-mapping
 - Additional Xrays detectors (Gamma Spectrometer)
- Projects
 - PIP II
 - XFEL upgrade




Additional possibilities

- Change to other frequencies
 - Mechanical adaptation of the insert
 - Switch measurement hardware
 - Amplifier
 - Frequency shifter
 - Some passive elements (directional couplers, additional cabling etc...)
 - Personal interlock adaptation
- Cryogenic test of components in cryostat

Cavities testing in serial mode


- XFEL

- 1276 VTs for serial XFEL cavities performed over 3,5 years
- In 2014 (testing peak) – 525 Vertical tests performed
 - 10 VTs / week (including holidays, maintenance etc...)
- Special testing team working on 2 shifts




Last year (2021) VT summary

- 127 VT
 - R&D single cells – 50
 - DESY 1.3GHz 9 cells – 19
 - SRF GUN – 12
 - ESS MB – 12
 - ESS HB – 21
 - Other 9-cells 1.3GHz – 4
 - POLFel - 9



■ R&D ■ Accelerator cavities



■ DESY ■ External

Summary

- In AMTF hall at DESY performing of cavity vertical test is a daily routine
 - Long time experience
 - Trained personnel
- Big cryostats give a lot of possibilities
- Test stands serve for both: R&D and accelerator cavities
- Currently 2 cavities types (1300 MHz, 704 MHz) can be measured
 - There is a possibility to switch to other frequency



THANK YOU VERY MUCH!!



This project has received funding from the European Union's Horizon 2020 Research and Innovation programme under GA No 101004730.