

Quality control for SiPM-on-tile section of the CMS HGICAL at DESY

Wrapped tile size and light yield test stands

Daria SELIVANOVA *on behalf of DESY HGICAL team*

DPG SMuK 2023, Dresden, 22/03/23

T 97: Calorimeter / Detector Systems IV

Contact:

daria.selivanova@desy.de



HELMHOLTZ



Introduction

High Granularity for the High Luminosity LHC

High Granularity Calorimeter (**HGCAL**) to replace existing CMS endcap calorimeter for upcoming HL-LHC
Scintillator part of CE-H (hadronic calorimeter) based on SiPM-on-tile technology being developed



Introduction

TAC and QC

Tile Assembly Center (**TAC**) at DESY is one of two centers performing tile module production and quality control (**QC**) at every stage


Objective is to assure top performance based on a small fraction (a spot sample) of all tiles

Developing test stands:

- Wrapped tile size
- Light yield (LY)

To achieve:


- High accuracy of measurements at fast pace
- Tile-to-tile wrapping and light yield uniformity
- Speed of tile module assembly ~150/month (for 1800 in total)




Introduction

Assembly and QC

Wrapping machine
4 tiles wrapped per minute



Pick-and-place machine
Small tolerance for tile acceptance



Efficiency of tile module assembly motivates improvements to speed and precision of QC stands

Ask for demonstration of these machines at work (backup). Warning: very cool!

Wrapped tile size test stand

Tile size test stand

Motivation and setup

Mechanical measurement (calliper) impossible:

- Wrapping is not rigid: could be bent to incorrect size (or even damaged)
- Trapezoidal shape is challenging, good precision is critical

Tile size test stand

Motivation and setup

Mechanical measurement (calliper) impossible:

- Wrapping is not rigid: could be bent to incorrect size (or even damaged)
- Trapezoidal shape is challenging, good precision is critical



Solution: perform optical measurements!

Bonus: better compatibility with pick-and-place machine for automatized assembly

Tile size test stand

Motivation and setup

Mechanical measurement (calliper) impossible:

- Wrapping is not rigid: could be bent to incorrect size (or even damaged)
- Trapezoidal shape is challenging, good precision is critical



Solution: perform optical measurements!
Bonus: better compatibility with pick-and-place machine for automatized assembly

Canon CanoScan 5600F scanner with:

- SANE backend drivers for Linux
- Scanimage command interface

External lighting is provided, scanner lamp is turned off to eliminate tile shadow


3D-printed frame to help position the tile in the middle of the scanner (12 cm x 12 cm)

SW written in Python using OpenCV library



Tile size test stand

Algorithm utilizing OpenCV functions



Tile size test stand

Goals and achievements

- Tile size determination with high precision

Better than $30\text{ }\mu\text{m}$

- Measurement reproducibility

Calculated corrections for angle
of placement variation

- Tile-to-tile uniformity checks

Within $200\text{ }\mu\text{m}$

- Outlier detection


Can be detected with clearly defined
margins to the wrapped tile sizes

- Fast measurement times



Below 1 min/tile

Plans to go faster by measuring
multiple tiles at once

$$33.305 < w < 33.905$$



$$33.68 < h < 34.28$$






Light yield test stand

LY test stand

Motivation and setup

- Want to maintain high LY during production (critical for signal-to-noise ratio after irradiation)
- Ensuring uniformity will ease production




LY test stand


Goals and achievements

- Compatibility with all tile types
 - Various frames for different sizes
- Speed of measurement
 - Around 6 mins/tile for better than 2% precision with current source
 - Plan for ~2min/tile with a stronger source
- Reproducibility
 - Different measurements of a single tile show low variation (~0.5%)
- Push-button operation for tests and (re)calibration
 - Dedicated scripts for voltage setting, spectra fitting, LY and Breakdown voltage calculation



Single pixel spectrum (SPS)



MIP spectrum



$$LY = \frac{MIP \ MPV - ped}{gain}$$





Conclusions

QC at DESY TAC for HGCal

Tile Quality control program at DESY Tile Assembly Center achievements so far:

- Test stands established
 - Tile size after wrapping
 - Light yield
- Results with high precision
- Minimum lag between production changes and evaluation of the quality of their outcome due to fast paced procedure
- Continuous upgrades based on communication with all steps of production to assure top performance



Backup

Backup

Tile wrapping machine

Backup

Pick-and-place machine