

# The detector Upgrades for HL-LHC at DESY

Sergio Díez Cornell (DESY)

MU days DESY, 12-13 December 2024

HELMHOLTZ



## Introduction

#### Leading the effort in instrumentation

# DESY keeping his commitment driving collider physics

- Contributing to the major international collaborations as one of the main players
  - Full exploitation of ATLAS and CMS experiments
  - Crucial in the most ambitious upgrade projects within the detectors: Trackers and HGCAL (endcap calorimeter)
- Maintaining the leading role of DESY in particle physics instrumentation
  - In-house experience and competence in construction of detector systems
  - Strong, multidisciplinary engineering teams
  - State-of-the-art facilities
  - German "hub" for universities and institutions





## The HL- LHC Upgrade

Exploring the limits of the World's biggest collider

- Main measurement: measurement at 4sigma (or better) of the Higgs self-coupling mechanism, by combining ATLAS and CMS
- Main challenges: 5-7x higher instantaneous luminosity (7.5x10<sup>34</sup> cm<sup>-2</sup>s<sup>-1</sup>) and 10x more pile-up events ( $\mu$  = 200) in the detectors
- Main design goal: Maintain or improve resolution and particle identification performance of current detectors





## The HL- LHC Upgrade

Exploring the limits of the World's biggest collider

- Main measurement: measurement at 4sigma (or better) of the Higgs self-coupling mechanism, by combining ATLAS and CMS
- Main challenges: 5-7x higher instantaneous luminosity (7.5x10<sup>34</sup> cm<sup>-2</sup>s<sup>-1</sup>) and 10x more pile-up events ( $\mu$  = 200) in the detectors
- Main design goal: Maintain or improve resolution and particle identification performance of current detectors



High granularity

High speed

Radiation tolerant





## The HL- LHC Upgrade

Exploring the limits of the World's biggest collider

- Main measurement: measurement at 4sigma (or better) of the Higgs self-coupling mechanism, by combining ATLAS and CMS
- Main challenges: 5-7x higher instantaneous luminosity (7.5x10<sup>34</sup> cm<sup>-2</sup>s<sup>-1</sup>) and 10x more pile-up events ( $\mu$  = 200) in the detectors
- Main design goal: Maintain or improve resolution and particle identification performance of current detectors







## **Replacing the old trackers**

After more than a decade of excellent performance

ATLAS Inner Detector End-cap





CMS strips tracker End-cap





## The new CMS and ATLAS trackers

#### A whole new scale for silicon detectors



## The new CMS and ATLAS trackers

#### The role of DESY



## The new CMS and ATLAS trackers

#### The role of DESY



HELMHOLTZ | HL-LHC@DESY | Sergio Díez Cornell, 13.12.2024

## **Covering the full spectrum**

#### From the smallest sensing units to the biggest structures

# Covering the whole range of the detectors design, assembly, and test from the start

- Silicon sensors and modules
- (Instrumented) support structures and its electronics
- Global structures
- Integration of sub-detectors
- System testing
- Know-how expertise present at DESY for integration, installation and commissioning of detector systems instrumental for their success







**Tooling for assembly, QC and integration** 

# Exploiting the strong and multidisciplinary engineering expertise at DESY

- Leaders in production of custom-built tooling and setups for components assembly, quality control (QC), and detector integration
  - Module and instrumented supports assembly
  - Thermal QC
  - Electrical QC
  - Integration tooling and tests
  - **Dual-phase CO<sub>2</sub> cooling** machines

Tooling for assembly, QC and integration

# Exploiting the strong and multidisciplinary engineering expertise at DESY

- Leaders in production of custom-built tooling and setups for components assembly, quality control (QC), and detector integration
  - Module and instrumented supports
    assembly
  - Thermal QC
  - Electrical QC
  - Integration tooling and tests
  - **Dual-phase CO<sub>2</sub> cooling** machines



**Tooling for assembly, QC and integration** 

#### Exploiting the strong and multidisciplinary engineering expertise at DESY

- Leaders in production of custom-built tooling and setups for components assembly, quality control (QC), and detector integration
  - Module and instrumented supports ٠ assembly
  - **Thermal QC** ٠
  - **Electrical QC** ٠
  - **Integration tooling** and tests ٠
  - **Dual-phase CO<sub>2</sub> cooling** machines ٠





Tooling for assembly, QC and integration

# Exploiting the strong and multidisciplinary engineering expertise at DESY

- Leaders in production of custom-built tooling and setups for components assembly, quality control (QC), and detector integration
  - Module and instrumented supports assembly
  - Thermal QC
  - Electrical QC
  - Integration tooling and tests
  - Dual-phase CO<sub>2</sub> cooling machines
- Produced and delivered most of these tools to the ATLAS and CMS Collaborations



## **Detector Assembly Facility (DAF)**

New clean rooms for new detectors

#### **DESY** laboratories for integration

- Detector Assembly Facility, constructed for the assembly and integration of the new CMAS and end-cap trackers
- ISO-6 and ISO-7 clean rooms
- More than 600sqm of laboratory space







## **Approaching production phase**

ATLAS

#### First steps into final assembly of components

#### **Recent milestones: ATLAS**

- Qualified as module and instrumented support sites
  - More than 55 pre-production modules and three fully instrumented petals built and QCed during pre-production
- First cosmic tests performed on system test setup
- Multiple DESY components in production
  - Local supports ("petal cores")
    - ~ 20% of cores received and tested
  - Back-end electronics boards ("EoS")
    - >50% of production assembled and tested
  - Rapidly approaching production on modules (est. March 2025)
- Recent **arrival of endcap global structure**, ready for integration
  - End-cap integration already exercised on system test setup



ATLAS system test setup







## **Approaching production phase**

#### First steps into final assembly of components

#### **Recent milestones: CMS**

- Pre-production gaining traction
  - First 5 pre-production modules in fabrication, expected O(25) by Feb 2025
  - First two pre-production supports ("DEEs") in-hand, a total of four by Feb 2025
  - DEE integration exercise took place at DESY in June 2024
    - 13 prototype modules mounted on prototype Dee and operated in parallel with final services routing
- Moving towards production
  - DEE production recently started (Dec 2024), first objects expected by Q2 2025
  - Module production aiming for Q3 2025









## A new Endcap Calorimeter for CMS

#### **Replacing pre-shower, ECAL and HCAL**

*Current CMS endcap Calorimeter* 

## **A new Endcap Calorimeter for CMS**

#### High Granularity Calorimeter (HGCAL)

#### High Granularity Calorimeter (HGCAL)

- Silicon and SiPM-on-Tile readout
- SiPM-on-Tile: Developed at DESY
  - Originally developed for future e+e- colliders
  - Scintillator part: 3700 m<sup>2</sup>, 280k SiPMs

#### **DESY contributions**

- Development and production of 2000 Tilemodules
- Automated production techniques
- Mapping and calibration software









HGCAL SiPM scintillator tiles

## **CMS HGCAL Status**

#### **Approaching production**

#### **Production techniques proven**

- Scintillator tile wrapping: DESY development
  - Reproduced at 2nd site (FNAL)
- Tilemodule assembly: adaptation of industrial pick & place technology

#### Quality control procedures in place

- Tile dimensions, light output, tilemodule response to particles (beam, cosmics)
  - Throughput matches production requirements
  - Results according to specs

#### **Pre-series module production complete**

- Close-to-final components
- Final production techniques



Populated HGCAL scintillator sector



## **CMS HGCAL Outlook**

#### System testing and production start

#### 2025-26: Tilemodule production and test

- Tile wrapping, electrical assembly, placement of tiles
- Tests of tiles, electronics and full modules

#### System tests and software development

- In cooperation with KIT
- Build up expertise for integration, commissioning
- Testbed for software: machine learning for calibration, simulation,...

#### **Future developments**

- Prepare for scalability and integration challenges
- High-granularity calorimeter for future Higgs factory



First 10-degree sector test



Beam test in 3T field

### In summary

DESY background and workforce provides a strong systems and commissioning competence

State-of-the-art facilities

Well regarded as a "German instrumentation hub" for universities and institutes

Multiple successful projects completed or in production

Ambitious goals for instrumentation in future experiments in HEP





# Thank you

#### Contact

Deutsches Elektronen-Synchrotron DESY Sergio Díez Cornell FH - ATLAS Group sergio.diez.cornell@desy.de

www.desy.de