11. ANNUAL MT MEETING GSI Darmstadt 03.11.25







I. Asparuhov for Magnet Group @ Helmholtz Zentrum Berlin

BESSYII → BESSYII+ → BESSYIII

BESSYII+ bridge upgrade for BESSYII prior to 2.5-GeV 4^{th} -gen. low-emittance BESSYIII \rightarrow 2 permanent-magnet (PM) projects:

- PM storage ring dipoles to replace 2/32 BMs as metrology SR sources.
- Compact bending magnet triplet for transfer line (B2PT) to replace present 30-kW 1.6-kA electro-dipole (1st PM-based magnet at BESSYII).






Magnetic field by PM blocks in steel structure (yoke + pole pieces).
6 PM rows/dipole @ max. 6 magnet blocks/row => max 36 PMs/dipole.

Hybrid permanent-magnet triplet B2PT @ 3 dipole units, 2 identical outer and 1 stronger inner one. Assembly start April 2025.




Goal → **Provide new bend angle for e**⁻ **beam** towards septum required by modified injection setup.

Power reduction (0.2 GWh/year) & enhanced magnet operation @ elimination of field ripple & vibration sources (power supplies & cooling channels).



NdFeB N42 PM material of $B_r = 1.3$ T easy-axis.





PM char. : $\lim \mu_r = 1.05, B_r = 1.37$

 $=53.653 \,\text{mm}$, $\theta_{x \, fol} = 4.038^{\circ} (3.278 \,\% \text{ off } \theta_{trat})$

 $\theta_{tun} \pm \theta_{tun} = 3.91^{\circ} \pm 5.6 \% = [3.691^{\circ}, 4.129^{\circ}]$

 $\int d_{entr}ds = -1906.823 \,\mathrm{mm.mm}, \int d_{ext}ds = -1820.071 \,\mathrm{mm.mm} \,(\int_{\Pi} \mathrm{GFR}ds \, @ \, 3000.0)$





Acknowledgements

Daniel Böhlick Volker Dürr Marc Dirsat Andreas Jankowiak Nina Ohm Fabian Pflocksch Oliver Schappeit Jens Völker Nora Wunderer


PM blocks tested in Helmholtz Coil-Setup and Hall-Array. Material, equipment & assembly tool cost amortized in 1.5 op. Years.

Field variation with **low-current convection-cooled coils** on outer dipoles. **Down-tuning via steel trim plates**, 12 /dipole in 2 groups X 6.

Total field tuning $\approx 5.6\%$. PM block positioning with dedicated press-in tool.



Optimization of triplet PM block fill & geometry configuration for required beam trajectory taking constrained by





PM-based triplet ready for full assembly with yokes & PM blocks delivered & unit dipole assembly tested – installation foreseen 2026. Corrector coil production and tests started in house.

