

PSI


Lessons Learnt in the Commissioning of Swiss Light Source 2.0

M. Aiba on behalf of SLS 2.0 team

08.10.2025


Low Emittance Ring Workshop

DESY, Hamburg, Germany



Overview of SLS 2.0

- New 4GLS storage ring
- Primary goals
 - Emittance, 40 times lower
 - Hard X-ray, 100 times brighter
- Key parameters
 - C: 288 m, reusing building and injector
 - Natural emittance: 158 pm w/o ID
 - Beam energy: 2.4 GeV $\rightarrow$ 2.7 GeV
came with negative $\alpha \rightarrow$ positive α
- Key technologies
 - NEG coating
 - Permanent magnet (PM)
 - HOM damped cavity
- Challenges
 - Compact lattice, 7BA with PM
 $\rightarrow$ Mechanical integration
 $\rightarrow$ Feasible?
 - Short dark time, tight schedule
 $\rightarrow$ All systems ready on Day-1




More details

- Talk on SLS2.0 upgrade project by H. Braun, this session
- Talk on SLS2.0 magnets by G. Montenero, Thursday afternoon

Parameters	SLS today	SLS upgrade
Lattice type	TBA	7-BA
Number of arcs	12	12
Circumference (m)	288	288
Gross straight length (m)	79.9	83.6
Total bending angle (deg)	374.69	430.08
Working point Q_x/Q_y	20.43/8.74	39.37/15.22
Momentum compaction factor, first/second order (10^{-4})	6.04/36.3	1.05/7.94
Natural chromaticity ξ_x/ξ_y	-67.3/-21.0	-99.0/-33.4
Vertical emittance (pm)	≈ 10	10
Chromaticity in operation	5	1.0-1.5
Energy (GeV)	2.411	2.700
Natural emittance (pm)	5630	158 (135)
Energy spread (10^{-3})	0.88	1.16 (1.04)
Radiation loss per turn (keV)	549	688 (915)
Damping partition $J_x/J_y/J_s$	1.0/1.0/2.0	1.83/1.0/1.17
Damping time $\tau_x/\tau_y/\tau_s$ (ms)	8.65/8.67/4.34	4.14/7.58/6.47
Beam current (mA)	400	400
Maximum rf voltage (MV)	2.6	2.2
Harmonic number	480	480
Number of bunches	390-420	450
Beam lifetime (h)	≈ 10	≈ 9

7BA lattice




- Permanent magnets
 - Longitudinal Gradient Bend 
 - Reverse bend 
- Electromagnets
 - Matching quad 
 - Sextupole 
 - Oct. + Normal & Skew Qs (0.32 T) 
 - Orbit correctors (800/600 urad) 

- Orbit and linear optics along the achromat are entirely based on permanent magnets!
- Pseudo-symmetry: same phase advance for S, M and L straights
- Limited corrector strength
- Significant magnetic crosstalk compensated by magnet optimization/tuning (backup slide)

Machine commissioning plan: 7 Phases

- Phase 1: Injector / 2024 Dec
 - Phase 2: First turn / 1+3 days
 - Phase 3: Multi-turn / 1+0 days
 - Phase 4: Accumulation, Basic feedback, Linear optics / 8+3 days
 - Phase 5: Nominal current, Advanced setting, Feedback / 15+5 days
 - Phase 6: Insertion devices and Collimator / 9+0 days
 - Phase 7: Finalization, Elaboration / Open end
- Shift plan was one (long) shift per weekday, and vacuum conditioning over night and weekend as long as we were on schedule
 - No weekend shift was needed in reality

Actual progress



- Machine commissioning is completed almost as planned
 - First electron into storage ring on 14th January
 - First stored beam on 23rd January
 - Design beam current, 400 mA, on 3rd April
 - First light to dipole beamlines on 10th/11th April
- We made it within 50 beam days!




Figure by courtesy of B. Rösner
Thanks to PX beamline colleagues

Getting first stored beam

- 14th Jan: Injector restart. Beam going through the thin septum
- 15th Jan: Beam going through first three sectors. Sector-4 BPMs were not triggered...
- 16th Jan: LGB realignment (correcting “known misalignments”), almost one turn
- 17th Jan: One turn and shortly after 8 turns achieved, but not more...
- 20th Jan: 5 turns but not more...
- 21st Jan: Taper into 3HC was blocking the injected beam, and realigned, ~40 turns
- 22nd Jan: Sextupole/Octupole ramped up, orbit correction, ~125 turns
- 23rd Jan: RF capture and stored beam! Individual cavity phasing was needed

* BPM commissioning was undergoing in parallel during these first days

Machine commissioning plan: 7 Phases


- Phase 1: Injector / 2024 Dec
- Phase 2: First turn / 1+3 days
- Phase 3: Multi-turn / 1+0 days
- Phase 4: Accumulation, Basic feedback, Linear optics / 8+3 days
- Phase 5: Nominal current, Advanced setting, Feedback / 15+5 days
- Phase 6: Insertion devices and Collimator / 9+0 days
- Phase 7: Finalization, Elaboration / Open end

Orbit threading

- Procedure
 - Beam launch into the storage ring
 - Injected beam was centered at the first two BPMs (pseudo-on-axis injection) using K3 and K4 in H plane and transport-line vertical correctors in V plane
 - Threading based on model matrix
 - 1st turn correction without cutting many eigenvalues was possible, $X_{\max}/Y_{\max} \sim 1$ mm
 - BPM electronic offsets were corrected before commissioning
 - 300 μm (assumed in simulation) vs 228/116 μm (BBA in Phase 4)
 - “Stitching”
 - Correctors upstream of the septum were manually adjusted with all four bump kickers ON
→ Multi turns achieved, and switching to the orbit mode
- Sextupoles/Octupoles were OFF
 - Despite strong focusing MBA lattice, transporting the beam through *linear lattice* is rather “easy”
- It goes without saying that BPM in turn-by-turn mode was essential and most important diagnostic at this stage.

Orbit threading

- Process
 - Beam position at two BPMs
 - Trajectory (pseudo-on-axis injection) using K3 and K4 V plane
 - “1st turn trajectory corrected”
 - “possible, Xmax/Ymax ~1 mm
- Sextupoles/C
 - Despite str rather “easy,
- It goes without saying that BPM is most important diagnostic at the




Machine commissioning plan: 7 Phases

- Phase 1: Injector / 2024 Dec
- Phase 2: First turn / 1+3 days
- Phase 3: Multi-turn / 1+0 days
- **Phase 4: Accumulation, Basic feedback, Linear optics / 8+3 days**
- Phase 5: Nominal current, Advanced setting, Feedback / 15+5 days
- Phase 6: Insertion devices and Collimator / 9+0 days
- Phase 7: Finalization, Elaboration / Open end

First stored beam



- Sextupoles/Octupoles ON
- RF capture
 - Phase scan, cavity by cavity
 - On-crest phase $\leftrightarrow$ Maximum turn
 - Phases were set to the synchronous phase
 - $\rightarrow$ Beam captured!



Injection


- Kicker bump injection (SLS1 kickers reused)
 - Easy to start with
 - Overdriven until the first stored beam (no accumulation possible)
 - Accumulation right after the first stored beam by switching to nominal setting
- Injection efficiency
 - Vacuum chamber downstream of the thin septum was largely misaligned, very poor efficiency
 - After realignment, ~80% efficiency achieved (Transfer line ICT vs Ring PCT)
 - New 3HC taper with bellows installed, ~100% efficiency achieved (Transfer line ICT vs Ring PCT)
- In Phase 7
 - Booster extraction and Transfer line tuning mitigated the residual beam loss, ~100% efficiency achieved (Booster PCT and Ring PCT)
 - Keeping ~100% efficiency is next challenge; sometimes it drops to <90% though >90% most of time.
- Plan for Aperture sharing/Quasi-on-axis injection
 - Stripline kicker, 20ns/2 ns pulse, is under development; PSI contribution to iFAST WP7
 - Prototype tested at ESRF-EBS
 - Prototype final test in this month → Kicker design to be finalized

Turn-by-turn signal from BLM (Libera) in the injection straight




Orbit correction


- BPM (quick) beam-based alignment
 - 115 BPMs aligned within about 10 μm . Can be done in about 3 hours.
- No problem in V plane: Correctors within ± 4 A while the limit is at ± 5 A
- In H plane, **not enough corrector strength**
 - BBA constant (BPM offset) was manipulated in Sector 4, 5 and 6 by 200 μm or so, to prevent the corresponding correctors from reaching to their limit
 - Fixed in Phase 7



Linear optics correction




Beta beat from reconstructed machine



- Correction with only matching quadrupoles, and then the quad correctors were included
- Dispersion correction (backup slide)

Vertical emittance control

- Coupling and V dispersion were corrected first using skew quads
- Vertical dispersion bumps was introduced to control V emittance
 - This static approach is convenient for the early stage of commissioning
 - Emittance dilution utilizing bunch-by-bunch Feedback is considered
- Nominal V emittance = 10 pm




Machine commissioning plan: 7 Phases

- Phase 1: Injector / 2024 Dec
- Phase 2: First turn / 1+3 days
- Phase 3: Multi-turn / 1+0 days
- Phase 4: Accumulation, Basic feedback, Linear optics / 8+3 days
- **Phase 5: Nominal current, Advanced setting, Feedback / 15+5 days**
- Phase 6: Insertion devices and Collimator / 9+0 days
- Phase 7: Finalization, Elaboration / Open end

Reaching 400 mA and vacuum conditioning/scrubbing

- <25 mA until the beam dump kicker was installed
- Two scenarios were considered in the planning:
 - Scenario A: No need to close the bunch-by-bunch feedback (BBBF) loop
 - Scenario B: Coupled bunch mode instability requires BBBF, increasing chromaticity or 500 MHz cavity tuning...
- Thanks to the new HOM damped cavities, Scenario A was the case. This made our life much easier!
 - Ion instabilities observed as expected with >100 mA. Otherwise, no instabilities observed up to 400 mA
- Some hot spots observed with temperature sensors at 400 mA...
 - Additional water cooling where necessary
- About 160 A.hours provided by April 15th
 - No aggressive scrubbing applied; Vertical pinger at 3 Hz
 - Beam lifetime of 8 hours was achieved → ~12 h in July





Average pressure and **Beam current**

January 25th to April 15th 2025

Figure from R. Ganter

Vacuum system


SLS Vacuum vessel design



- Aggressive design “no bellows over 17 m”
- Beam dose of 100 A.hour → Minimal conditioning
- Pressure better in the arc chamber with NEG ($< 1e-9$ mbar) than some other parts not coated ($> 1e-9$ mbar)


Beam dump and Machine protection

- Machine protection system
 - Protect thin vacuum chambers, IDs, ring permanent magnets, etc.
 - Designed to react within $\sim 100 \mu\text{s}$
 - Beam is safely dumped even for the worst event, i.e., power cut
- Dump kicker and internal beam dump
 - Integrated into the injection straight
 - Slope of the sinusoidal kicker pulse spread the bunch train on the beam dump surface





500 MHz RF system

- New HOM damped cavities
 - Large beta functions at the RF location
 - New digital LLRF system
 - Pre-conditioning at test stand
 - Sophisticated tool was available since commissioning Day-1: beam recovery after beam dump as quick as possible
- Harmonic number = 480
 - Nominal filling = 450 bunches uniform
 - Two gaps or 50-bucket long gap to avoid ion instability when it was necessary
- No coupled bunch mode instability up to 400 mA





Third harmonic cavity, passive SC



- SLS1 3HC cavities reused
 - Tuning system and cryo-plant upgraded
- Approximately tuned during the beam current increasing
- In Phase 7, further tuning with streak camera
 - Operating point: ~ 501 kV
 - Bunch length: ~ 10 ps w/o HC vs ~ 25 ps average with HC



Beam size measurement with visible light




Images from π -polarization beam-size monitor



- Significant V beam size increase was observed when the vacuum pressure was high
 - Small-angle/multiple scattering with residual gas (?)
- Later, with good vacuum, the monitor was used to confirm the vertical emittance control


Machine commissioning plan: 7 Phases

- Phase 1: Injector / 2024 Dec
- Phase 2: First turn / 1+3 days
- Phase 3: Multi-turn / 1+0 days
- Phase 4: Accumulation, Basic feedback, Linear optics / 8+3 days
- Phase 5: Nominal current, Advanced setting, Feedback / 15+5 days
- **Phase 6: Insertion devices and Collimator / 9+0 days**
- Phase 7: Finalization, Elaboration / Open end



Preparation for ID beamline commissioning

- Beamline vacuum conditioning
 - Before starting ID beamline commissioning, ID gaps have been closed to condition the vacuum up to the photon shutter
- Orbit feedforward tables have been measured and applied
 - 4 correctors are attached to undulator (H/V/upstream/downstream)
 - Gap dependence of the orbit feedback correctors is reduced
- Tune and coupling feedforward are considered





Machine commissioning plan: 7 Phases

- Phase 1: Injector / 2024 Dec
- Phase 2: First turn / 1+3 days
- Phase 3: Multi-turn / 1+0 days
- Phase 4: Accumulation, Basic feedback, Linear optics / 8+3 days
- Phase 5: Nominal current, Advanced setting, Feedback / 15+5 days
- Phase 6: Insertion devices and Collimator / 9+0 days
- **Phase 7: Finalization, Elaboration / Open end**

Realignment campaign (1)


- Vertical girder alignment
 - Girders are motorized and can be remotely aligned from the control room
 - Beam Assisted Girder Alignment (BAGA)
 - Girders were moved with stored beam and FOFB running
 - New corrector setting is obtained immediately
 - All girders were aligned to the reference ($Y=0$)
- Horizontal girder alignment
 - Manual alignment in the tunnel; not motorized in H plane
 - Girders in Sector 5 were aligned during the last shutdown in August
 - It is not necessary to align all the girders; horizontal alignment is planned for a few more locations
- Some beamline components need to be realigned
 - Difficulty to establish smoothly-connected alignment network between the machine and the beamline



Simulated and actual vertical corrector changes. Good agreement indicates well-corrected optics.

Realignment campaign (2)

- LGB in Sector 6 and Reverse bends in Sector 4, 5 and 6 were shifted, up to 500 μm , to regulate the horizontal corrector current...






Status of feedbacks

- Fast orbit feedback (postponed from Phase 5 to Phase 7)
 - Slow orbit feedback was running since Phase 4 and good enough for beamline commissioning
 - FOFB loop is currently running at 40 kHz, possibly pushed to 80 kHz if better
 - RF frequency correction is included in FOFB; Low alpha machine, $\alpha \sim 1e-4$
- Filling pattern feedback is in-progress
- Bunch-by-bunch feedback is ready
- Tune feedback is not demanded
 - Manual tune correction from time to time

Orbit stability


Reference BPM:



Zero dB point ~ 400/500 Hz (H/V)

All BPMs: 144/91 um in H/V

Beamline commissioning



Lessons learnt (and known)

- Importance of preparation
 - Planning, hardware tests, magnet polarity check, high level applications, virtual accelerator, etc.
- Importance of beam diagnostics
 - BPM was the most important diagnostics to establish stored beam, and later for orbit correction and fast orbit feedback
 - Enhanced BLM system was useful to localize beam losses
- Excellent new devices
 - Thin septum: Injection efficiency close to 100% achieved
 - HOM damped cavity; no instability observed except for ion instabilities
- Vacuum conditioning/scrubbing
 - 100 A-hour is a good measure
 - Increased beam size gave us extra time for optics refinement; Lifetime was dominated by gas scattering when the pressure was high
- Beam lifetime longer than expected, 9 hours in design vs ~12 hours
 - Gas scattering lifetime might be underestimated with $1.0\text{e-}9$ mbar CO assumed
 - Robust beam optics with pseudo-symmetry lattice design
 - Planar undulators including CPMU14 (3.8 mm gap) had no significant impact on the lifetime. Apple type undulators to be examined.
- Compact MBA based on permanent magnet is feasible
 - Orbit and linear optics correction were fine with limited correctors (proof for crosstalk compensation) ← This was the grave concern from beam dynamics point of view!
 - Excellent job done by magnet and alignment groups
 - No issues with large number of power supplies for matching quads + multipoles + Q/D correctors

*When we made
the first stored beam...*

Special thanks for the input:

F. Armbrorst, S. Bettoni, M. Böge, H. Braun, A. Citterio,
M. Dehler, R. Ganter, B. Keil, G. Montenero, C. Ozkan,
L. Stingelin, P. Willmott, M. Wurm



Thanks to all PSI colleagues who contributed to SLS2.0

Thank you for your attention!

© Photo by Takashi Tomizaki

Magnetic crosstalk

Sextupole+Reverse Bend+Correctors
FEM modeling





Reverse bend field attenuation 4.6%...

All permanent magnets were measured and tuned to compensate for crosstalk


Linear optics correction, Dispersion

- Dispersion was not well corrected with LOCO (not expected)
- “Dispersion knob” applied
 - One dispersion knob consists of 6 quad correctors
 - Almost transparent to beta function
 - 72 dispersion knobs applied





Girder and Ground vibration

Transfer function over frequency



- Most distinct Magnet amplification at 27Hz (Also seen in beam measurement)
- Girder Motion at 90 Hz is not amplified to the Magnets

Comparison to SLS 1

	PSD vertical	Integrated RMS Girder	Natural frequency	Girder Style
SLS		vertical 32nm horizontal 56nm	1 st EF ~15Hz	• Mover System • 5 DOF
SLS 2.0		vertical 7 nm horizontal 8 nm	1 st EF ~25Hz	• Wedge Design • 2 DOF