

News on Phase-2 Activities



Andreas Mussgiller

CMS Tracker Upgrade Phase-2 Meeting
26/10/2012




Outline

- > CFRP-PGS Laminates
- > news from the labs




CFRP-PGS Laminates

- > bondability of PGS (Pyrolytic Graphite Sheet) needs to be tested
- > samples were produced at INTA (Madrid)
- > samples are 20 x 120 mm²
- > 6 different types of samples
 - 2 types of PGS foil
 - S Type
 - A-RV type
 - 3 PGS foil „shapes“
 - 20 x 120 mm² (full)
 - 16 x 116 mm² (frame/centered)
 - 20 x 120 mm² (perforated)
- > 5 samples per type




CFRP-PGS Laminates cont.



- > M55J high-modulus fibre (Toray)
- > PGS foil is laminated into the CFRP
 - 125 μm per ply
 - $0^\circ / -60^\circ / +60^\circ / 0^\circ / -60^\circ / +60^\circ / \text{PGS} / +60^\circ / -60^\circ / 0^\circ / +60^\circ / -60^\circ / 0^\circ$
 - quasi-isotropic CFRP sheets
- > 20 additional quasi-isotropic sheets available for own bonding tests
 - $0^\circ / -60^\circ / +60^\circ / +60^\circ / -60^\circ / 0^\circ$

S-Type Full




0°
-60°
+60°
0°
-60°
+60°
+60°
-60°
0°
+60°
-60°
0°


1.6 mm

CFRP-PGS Laminates - Planned Tests

- > confirm thermal conductivity
 - effect of perforation



- > measure interlaminar shear stress
 - where does bond break
 - interface between CFRP and PGS
 - inside PGS



- > how does radiation effect interlaminar shear stress


News from Lab 2



- slight rearrangement of equipment
 - now complies to D5 regulations



News from Lab 2 cont.



coolant
distribution



- new vacuum pump system directly connected to vessel
- chiller currently shared between vessel and ODM
- additional chiller will be ordered for microchannel cooling activities
 - use Julabo chiller for ODM
 - new chiller for all thermal measurements


News from Lab 1



- too much ambient light when all panels are switched on
 - housing will be covered with black foil from the inside
- dry air supply is working
- first tests with dry air planned once setup closed and sealed
- linear drives for camera and light panel frames yet to come





News from Lab 1



- complete restructuring of software
- scriptable
- split measurement and analysis parts into two codes



ODM Calibration Device



- > some minor modifications wrt. 3D model were needed
- > precision thread for micrometer screw is tilted
 - should be fixed by end of next week
- > new calibration surfaces are available
- > first measurements with laser measurement system at FEC beginning of November

Summary

- > samples for PGS bonding tests are available
 - thermals tests will start once Lab 2 equipment is commissioned

- > a lot of progress over the last few months
 - many thanks to Carsten Muhl, Adam Zuber, Holger Maser, Karten Gadow, Korbinian Pöppel, Sven Junck and Sander Vanheule
- > idea to split coolant supply for thermal measurements and ODM
- > dry air supply is ready
 - first measurements planned for early November
- > calibration device for ODM almost ready
 - calibration of the calibration device planned for early November
- > ODM software needs to be finished
 - need all hardware in place for this

