


Characterization of BCM1F Lasers




Brian Pollack, Northwestern University, BRM Group



Overview

- ★ **Analog Opto-Hybrids**
- ★ **PLT Go/NoGo Tests**
- ★ **BCM1F Laser Characterization**
 - Completed Items
 - ToDo
- ★ **Timeline**

Analog Opto-Hybrids



- ★ Optical Links used for data transmission
- ★ High bandwidth, low power, low noise
- ★ We intend to use 16 AOHs (48 channels, 3 lasers per AOH)
- ★ Must characterize laser response for accurate calibration



PLT Tests

- ★ **30x3 PLT analog opto-hybrid (AOH) lasers were tested for functionality (Go/NoGo tests)**
- ★ **Results: All Go (PLT group can sleep easy tonight)**



BCM1F Laser

Characterization

★ Plan Of Attack

- All BCM1F AOH lasers will be tested to determine laser output as a function of input voltage
- Input voltage will vary from sub-mip level to ~10% below maximum design value
- Tests will be conducted at 4 gain levels for each laser
- After lasers are characterized, we choose the 16 that have the most similar response curve and activation threshold
- Further tests will be conducted at low temperature
 - ♦ It is hypothesized that the laser response will be non-linear as a function of temp


Hardware/Software



- ★ Analysis hardware (frequency generator, oscilloscopes, macbook) and software programs (matlab) are ready and working
- ★ Once tests commence, routine will be automatized and should produce results quickly and accurately




Test Box



Final Issues

Analog In (GOOD)




Digital Out (BAD)

- ★ The PLT AOH Test Box requires some modification before the full suite of tests can begin
- ★ The default setup uses an internal trigger as a digital input signal
- ★ Currently working with Alan Bell And Vladimir Ryjov to modify the box to accept input from frequency generator and transmit and analog signal to the AOH
- ★ Setup should be ready soon after the conference

Timeline

| | Fall 2012 | | | Winter 2012/13 | | | Spring 2013 | | | Summer 2013 | | | Fa |
|--|-----------|----------|----------|----------------|----------|----------|-------------|----------|----------|-------------|----------|----------|----------|
| Activity | 1-Sep-12 | 1-Oct-12 | 1-Nov-12 | 1-Dec-12 | 1-Jan-13 | 1-Feb-13 | 1-Mar-13 | 1-Apr-13 | 1-May-13 | 1-Jun-13 | 1-Jul-13 | 1-Aug-13 | 1-Sep-13 |
| Removal BCM1F | | | | | | | | | | | | | |
| Removal of BCM1F beam pipe pixels 25/03-24/05 | | | | | | | | | | | | | |
| Sensors, FE ASICS and Lasers | | | | | | | | | | | | | |
| sCVD Sensor Order to procurement | | | | | | | | | | | | | |
| pCVD Sensor Order to procurement | | | | | | | | | | | | | |
| Metallization | | | | | | | | | | | | | |
| Sensor Testing, Characterisation | | | | | | | | | | | | | |
| FE ASIC Design, submission | | | | | | | | | | | | | |
| FE ASIC + sensor Test Board pcb design & fabrication | | | | | | | | | | | | | |
| FE ASIC Delivery and tests | | | | | | | | | | | | | |
| Integration of ASIC to sensor and source tests on test pcb | | | | | | | | | | | | | |
| Laser test setup and characterization | | | | | | | | | | | | | |



Everything is on schedule!