XFEL DAQ -- Infrastructure & Environment



Thomas Hott

XFEL DAQ -- Infrastructure & Environment

DAQ computer cluster(s) shall be installed close to the experimental stations

- -> i.e. on the Schenefeld premises
- -> preferable in the Exp. Hall or its surface building

Infrastructure requirements:


- Space
- Power
- Air conditioning / water cooling
- IT-connection -> cables, glass fibres
- Connection to the front end devices -> cables, glass fibres
- Radiation protection
- Fire protection
- Permanently accessible
- Protection against unauthorised access

So far nothing particular is planned. However there are no problems providing the required infrastructure -> Financial frame to be defined!






The XFEL Machine



UN1 & UN2 are not part of the first installation stage!




SASE1 beam line instruments





Tunnel Cross Sections & Installation Times

Linac Tunnel XTL - Ø= 5.20 m




Infrastructure installation ≈ 57 weeks Machine installation ≈ 42 weeks

Accessible for Installation:

XTL ≈ Apr. 2011 XTD6-10 ≈ Feb. 2012 Exp. Hall (undergr.) ≈ May 2012 Exp. Hall (surface) ≈ Dec. 2012

Photon Beam Line Tunnel XTD6 - Ø= 4.50 m



Much less complex

- -> Infrastructure ≈ few (3-6) month
- -> Photon beam line ≈ few (~6) month


Current "Firsts" Dates:

- •1st beam in Injector -> end of 2012
- •1st beam in Linac -> end of 2013
- •1st SASE(1) at 0. 2 nm \rightarrow end of 2014





The Experimental Hall -> Underground

Accessible for installation ≈ May 2012



Floor size:
≈ 90 m x 50 m ≈ 4500 m²
≈ 14 m below surface
Ceiling supported by 8
columns





The experimental hall is basically designed in detail


- -> Not yet designed are the instruments/experiments and their proximity infrastructure
- -> No space (so far) envisaged for DAQ computer cluster(s)



The Experimental Hall -> Surface Building

Accessible for installation ≈ Dec. 2012





The surface building of the experimental hall is <u>not yet designed in detail</u> -> Requirements catalogue must be revised soon!

Glass fibres in the XTL (Linac tunnel)

Requirements

- ≈ 1000 individual fibres
- Distributed over ≈ 50 rack stations along the entire XTL (i.e. ≈ 2100 m)
- Radiation protected
- Vibration protected
- Temperature stabilised
- Exchangeable





Glass fibres installation

Air injection technology

Injection length for different capillaries:

 $\emptyset_{0/i} = 3/2$ mm -> Single Fibre - Coating -> up to 500 m


 $\emptyset_{0/i} = 5/3.2$ mm -> 12 Fibres - Coating -> up to 1.5 km

 $\emptyset_{\text{o/i}} = 10/8 \text{mm} \rightarrow 72 \text{ Fibres - sheath -> up to 3 km}$



Sheath tube with internal capillaries

Distribution fittings







Distribution box



Nomenclature: Building & Tunnels



XFEL - Beam Line Sections Naming Convention



XFEL - Beam Line Sections Naming Convention

The machine proper is a succession/assembly of sections with different functionalities (e.g. Injector, Bunch Compressor, Main Linac, SASE-x, Dump Lines, Photon Beam Lines)

Each functional section gets its own unique name, refering either to:

i) The function of the section:

I1 = Injector 1

I1D = Injector Dump

L1 = Booster Linac 1

BC1 = Bunch Compressor 1

BC1D = Bunch Compressor 1 Dump(Line)

L2 = Booster Linac 2

BC2 = Bunch Compressor 2

B2D = Bunch Compressor 2 Dump(Line)

L3 = Main Linac

CL = Collimation Section

TLD = Main Linac Dump(Line)

S1-3 = SASE Undulator Sections 1-3

U1-2 = Spontaneous Radiation Undulator Sections 1-2

T5D = Main Dump(Line) in XTD5/XSDU1

T5D = Main Dump(Line) in XTD4/XSDU2

XFEL - Beam Line Sections Naming Convention

ii) Or to the tunnel where the section ends:

TL = (straight) e-beam line starting at the end of the collimation section and ending at the T1-T20 switch

T1 = (straight) e-beam line starting at TL-T1 switch, ending in XTD1 at the beginning of SASE-2 section

T2 = (straight) e-beam line starting at T1-T20 switch, ending in XTD2 at the beginning of SASE-1 section

T3 = (bended) e-beam line starting after SASE-2 section, ending in XTD3 at beginning of UN1 section

T4 = (bended) e-beam line starting after SASE-1 section, ending in XTD4 at beginning of UN2 section

= (bended) e-beam line starting after SASE-3 section in XTD4, ending in XSDU2

T5 = (bended) e-beam line starting after UN1 section, ending in XTD5 at beginning of SASE-3 section

T5D = (bended) e-beam line starting after UN2 section in XTD5, ending in XSDU1

T6 = SASE-2 photon beam line in XTD6, starting at photon/e- separation (in T3 section)

T7 = UN2 photon beam line in XTD7, starting at photon/e- separation (in T5D section)

T8 = UN1 photon beam line in XTD8, starting at photon/e- separation (in T5 section)

T9 = SASE-1 photon beam line in XTD9, starting at photon/e- separation (in T4 section)

T9 = SASE-3 photon beam line in XTD10, starting at photon/e- separation (in T4D section)

Conclusions

Defined and basically not changeable anymore are:

- Underground buildings
- General infrastructure

Next Steps on 'DAQ side':

- Detail requirements for power (incl. emergency power, emergency stop & UPS), air conditioning, water and IT
- -> June 2008
- Detail requirements for cables and glass fibres, incl. routing
 - -> End of 2008
- Define budget requirements
 - -> Soon

Current "Firsts" Dates:

- •1st beam in Injector -> end of 2012
- •1st beam in Linac -> end of 2013
- •1st SASE(1) at 0. 2 nm \rightarrow end of 2014