

Fermilab/Argonne Cavity Test Results

Camille Ginsburg
Fermilab Technical Division
October 2008

Outline

- ❑ Intro to
 - ❑ Fermilab Vertical Cavity Test Facility (VCTF)
 - ❑ Argonne/Fermilab Cavity Processing & Assembly Facility (CPF)
- ❑ Cavity test results
 - ❑ our cavity tests are tests of infrastructure or instrumentation!
 - no cavity first tests yet
 - ❑ 9-cell cavity processing was primarily done at JLab, then shipped under vacuum to Fermilab
 - ❑ 1-cell cavity first processing was done at Cornell
- ❑ Near-future plans for cavity process/tests



Fermilab VCTF

Design

- Existing 125W@ 2K Cryogenic plant; 1.5K minimum
- RF system in collaboration with JLab
 - 250 W available at cavity
- Radiation and magnetic shielding
 - < 5 mrem in an hour immediately outside the shielding
 - <0.25 mrem/hr in normal working areas
 - <10 mG

Thermometry for quench location


- Capable of testing ~50 Cavities/year

Status

- One Vertical Test Stand (VTS1) commissioned 7/2007
- 17 cavity test cycles in FY08 (ILC 1- & 9-cell, SSR1)

VTS Cryostat


9-cell Tesla-style cavity





Argonne/Fermilab CPF

- Cavity processing and assembly facility
- Located at ANL; designed and built jointly
- ANL group Electropolishing (EP) of 1-cell and 9-cell ILC-style cavities
 - Accel-7 (9-cell) and two 1-cell cavities have been EP'd
- FNAL group high-pressure water rinse (HPR) tool
 - Cavity moves vertically, wand rotates
 - Instrumentation to be commissioned soon
 - Commission with a cavity Fall'08
- Cleanroom class 10, 100, 1000 in progress
- Ultrasonic (US) rinse tank for anteroom in progress
- Cavity vacuum system in progress



Argonne Electropolishing

- Accel-7 EP'd in May 2008
- Average EP material removal (ultrasound measurement)
 - equator ~ 0.866 mil (22 microns)
 - iris ~ 1.25 mil (31.9 microns)
 - beam tubes ~ 0.55 mil (14 microns)
- Sent to JLab for final cleaning/assembly/test
 - ultrasonic cleaning (Micro-90), HPR, ass'y, HPR
- ~30% E_{acc} reduction & field emission observed
- EP process of 1-cell tested at FNAL



Additional infrastructure

- Since Argonne/Fermilab CPF not fully ready, making use of Fermilab MP9 facility (cryomodule assembly) and A0 facility (3.9 GHz facility)




FY08 VCTF Test Cycle Summary

- “test” = cryogenic thermal cycle
- Includes 9-cell cavities, single-cell cavities, and SSR1 HINS cavity
- One 1-cell test in Sep.08 is not shown

FY08: Oct 2007-Sep 2008

FY08 major infrastructure work

- ☐ Inner magnetic shield installation
- ☐ Active cavity vacuum pumping
- ☐ Permanent “Fast Thermometry” system deployment at VTS1
- ☐ Adaptation for 325 MHz HINS SSR1 cavity test support
- ☐ Variable input power coupler




Single-cell cavity tests

- **TE1AES004**


- ❑ BCP'd and tested at Cornell in Dec.2007, reaching $E_{acc} \sim 25$ MV/m with the limitation of Q-slope
- ❑ EP'd at Argonne, HPR at A0, ass'y at MP9
- ❑ 33 MV/m limited by field emission, after processing of multipacting barrier and field emission

- Also, 1-cell version of 9-cell thermometry commissioned






Single-spoke resonator tests




- SSR1 cavity for HINS/Project X
- Requirements/Design parameters
 - ❑ 10 MV/m with $Q_0 > 5 \times 10^8$
 - ❑ Operating temperature is 4K
 - ❑ 325 MHz
 - ❑ manufactured by Zanon
- Process
 - ❑ BCP (120 μm) and HPR at Argonne (the not-new facility)
- Three test cycles (no BCP/HPR)
 - ❑ Initial trouble with cavity vacuum, multipacting, and probably insufficient drying
 - ❑ Final Eacc ~ 18 MV/m with $Q_0 \sim 2 \times 10^8$





Test instrumentation


- 9-cell thermometry

- ❑ Measure temperature rise, not absolute temperature, in a comprehensive pattern around each of the 9 cells, all 9-cells tested in a single step
- ❑ Fast installation; use for “every” 9 cell test
- ❑ First test of 1-cell version Sep.2008




- Variable RF input coupler

- ❑ Keeps cavity critically coupled; facilitates mode meas.
- ❑ Mounts to standard input coupler port; uses cryogenic motor
- ❑ Movement range $\Delta R \sim 15$ mm (equiv. 2×10^9  Q_{ext}  4×10^{10})
- ❑ Tested twice; installation procedure under development



- “Fast” thermometry

- ❑ Cernox RTD sensors flexibly placed, depending on test requirements, with G10 band/nylon thread & Apiezon grease for mounting
- ❑ Well tested, reliable system; used in all cavity tests




9-cell Cavity Tests at FNAL

- **Accel-6**
 - ❑ Three thermal cycles
 - ❑ First test cycle: $E_{acc} \sim 39$ MV/m
 - ❑ Second test cycle: $E_{acc} \sim 39$ MV/m; first test of cavity vacuum active pumping
 - ❑ Third test cycle: $E_{acc} \sim 21$ MV/m; field emission induced (variable input coupler)
- **AES1**
 - ❑ First 9-cell ILC-style cavity tested at FNAL, Sep.'07
 - ❑ Three thermal cycles: $E_{acc} \sim 15$ MV/m
 - ❑ Fast Thermometry and mode measurements were used to find isolated and repeatable quench locations
- **AES3**
 - ❑ Two thermal cycles
 - ❑ First test cycle: $E_{acc} \sim 20$ MV/m
 - ❑ Fast Thermometry and mode measurements were used to find isolated and repeatable quench locations
 - ❑ Second test cycle: $E_{acc} \sim 11$ MV/m; field emission induced (variable input coupler)

9-cell Cavity Test Summary


- 7 nine-cell cavity tests at FNAL VTS (black)
 - Processing primarily done at JLab, so previous JLab tests of these cavities are included for comparison (blue)
- [R.L. Geng et al., SRF2007, Beijing]
- Test at JLab of ANL EP'd cavity (green)



Best-Cavity Test

ACCEL06
June 12, 2008

Acce1-6




40 MV/m; quench limitation

Q vs. T Measurement

- Accel-6
 - ❑ 9-cell ILC-style cavity manufactured by Accel
 - ❑ Wah Chang niobium, measured RRR ~500
- Q_0 measured as a function of temperature from 4K down to 1.42 K, $G=270\Omega$
- Data below T_λ fit to

$$R_s = \kappa \times \frac{1}{T} \times \exp\left(-\beta \frac{1}{T}\right) + R_{mag}$$

- $R_s = 4.97 \pm 0.16 \text{ n}\Omega$




Vertical test cryostat works well as designed

VCTF upgrade plans

- ❑ Cavities to accommodate
 - ❑ ILC/SRF R&D
 - ❑ 9-cell and 1-cell elliptical ILC cavities
 - ❑ HINS/Project X
 - ❑ SSR1
 - ❑ SSR2
 - ❑ TSR
 - ❑ 9-cell elliptical cavities
- ❑ Conclusion
 - ❑ VTS1 is sufficient to support FY09, FY10 test plans
 - ❑ VTS2 with larger diameter operational by ~Dec. 2010 to support SSR2, TSR, and increased throughput
 - ❑ VTS3 needed by ~Sep. 2011
- ❑ Planned upgrades
 - ❑ 2 cavities at a time
 - ❑ Cryogenic system & infrastructure upgrades
 - ❑ Plan for two additional VTS cryostats
 - ❖ Ultimate capacity ~ 250 cavity tests/yr

Do not fit in VTS1

Plan 2 more VTS pits
& staging area



Conclusions

- 17 cavity tests at Fermilab VCTF in the last year
 - one 1-cell, three 9-cell Tesla-shape (1.3 GHz)
 - single-spoke resonator (325 MHz)
- Commissioning of ANL/FNAL cavity processing facility and infrastructure required to prepare cavity for test
 - It works – excellent achievement by many people
 - Field emission to be overcome
- Commissioning of instrumentation
 - 9-cell thermometry: 1-cell version first full system test complete
 - variable coupler: two full system tests, installation/cleaning need work (field emission)
- Vertical test cryostat works great
- Facility upgrades underway to increase throughput and accommodate future cavities



Thanks

- The presented work is a great coordinated effort by many people
- G. Apollinari, T. Arkan, D. Bice, R. Carcagno, M. Champion, N. Dhanaraj, I. Gonin, T. Khabiboulline, G. Lanfranco, A. Lunin, W.-D. Moeller[†], A. Mukherjee, W. Muranyi, R. Nehring, D. Olis, J. Ozelis, V. Poloubotko, Leo. Ristori, A. Rowe, R. Schuessler, D.A. Sergatskov, B. Smith, C. Sylvester, R. Wagner, R. Webber, G. Wu (Fermilab)
- M.P. Kelly (Argonne)
- JLab staff
- Cornell staff

[†]visitor from DESY