ALFA Status Report


K.Hiller for the DESY ALFA group

DESY-ATLAS meeting, Zeuthen 22 May 2008

- 1) short introduction
- 2) status of main components
- 3) outlook

Luminosity from ALFA(1): Principle

Elastic scattering in the Coulomb-Nuclear interference region:




 $L = \text{luminosity}, \ \sigma_{tot} = \text{total cross section}$

$$ho = {\rm Re} \; f_{el} \, / \, {\rm Im} \; f_{el} (t=0), \; b = {\rm nuclear \, slope}$$
 May 22, 2008 DESY-ATLAS meeting

- Measure unbiased elastic rate
- ☐ Fit dN/dt
- ☐ To reach Coulomb region
 |t/ < 10⁻³ GeV²
 needs tracking close to the beam
- ☐ Special request to:
 - 1) pot positions
 - 2) beam optics
 - 3) detectors ...

Luminosity from ALFA(2): Roman Pots



Luminosity from ALFA(3): Optics

Standard LHC optics impossible:

1) too large beam divergence

$$\sigma(x) = \sqrt{\varepsilon \cdot \beta^*}$$
 $\sigma(x') = \sqrt{\varepsilon / \beta^*}$

with: ε emmitance, β * beta function

β*/m	$\sigma(x)/\mu m$	$\sigma(x')/\mu rad$	$\sigma(t)/GeV^2$
11	74	6.7	0.002
2	32	16	0.012
0.5	16	32	0.050

Intrinsic beam divergence does not allow to measure beyond 0.001 GeV²

Optics solution: high β^* = 2625 m low ϵ = 1 μ m rad

$$|t_{\min}| = p^2 n_{\sigma} \varepsilon / \beta^*$$

with p beam momentum,
 n_{σ} distance to orbit in RMS

For
$$n_{\sigma}$$
=15 | t |_{min} ~ 0.0004 GeV²
May 22, 2008


2) ALFA tracks depend from Θ* AND y*

$$y = \sqrt{\frac{\beta}{\beta^*}} \left(\cos \Psi + \alpha^* \sin \Psi\right) y^* + \sqrt{\beta \beta^*} \sin \Psi \theta_y^*$$

For unique relation between track in ALFA and momentum transfer phase advance

$$Ψ = 90^{\circ}$$


($α^* \sim 0$ at high $β^*$)




ALFA used in special runs with: high β*, low ε, $\Psi = 90^{\circ}$ DESY-ATLAS \rightarrow L = 10 ^{27...28} cm⁻²s⁻¹

Luminosity from ALFA(4): Acceptance

Detectors as close as possible to the beam to reach the Coulomb region





For y_d = 1.5 mm: Integral acceptance = 67% t-resolution < 10%

dominated by beam divergence

ATLAS meeting

The ALFA production sites

CERN
Design
Mechanics
Detectors
Electronics
Coordination
Installation

Orsay Maroc 1/2/3 FGAs

Lisbon Fiber coating



Lund motherboard

DESY HH Fiber metrology MAPMTs, HV

HU Berlin Ti-substrates

DESY Z Triggers

Giessen
Fiber detectors
Assembling
software

Prague mechanics software

The ALFA TDR



CERN/LHCC/2008-00 ATLAS TDR 18 17 January 2008

ATLAS Forward
Detectors for
Measurement of Elastic
Scattering and
Luminosity

ATLAS Collaboration


Technical Design Report


... an important formal step for any detector component

- 1) 3 internal ATLAS referees
- 2) LHCC open meeting 7th May 2008
- 3) LHCC referees are now looking at the TDR. Special session for next meeting in July

ALFA Detector: Scheme

The Roman Pot Unit






Prototype -1: test of installation

Giessen, March 2008:

- ☐ installation issues in a very tight environment
- ☐ decision of tile readout: bundles or light guides

R7400, R7401





Good news from Aluminization / CERN



ATLAS Status of fibers aluminization at CERN

A fiber side coating system has been built at CERN

- Based on vacuum evaporation technology
- Implemented in our 1 meter evaporation plant, in building 108

Capability: 430 fibers / process







Summary of sides aluminizations for proto-2:


- 1650 fibers coated
- → 1600 fibers OK + 50 fibers rejected (bad adherence)
- 1300 fibers sent to Giessen for the assembly of the main detector fiber plates.
- 240 aluminized fibers bent for the overlap detector plates

ALF A detector meeting — Status of fiber aluminization at CERN - A Braem , C. David

Lisbon:

- problems with sputtering side coating
- DESY-/ but works fine for end coating of fibers

Good news: Prototype -2 (nearly) on schedule



)9 April 2008 - ALFA detector meeting – Status and planning of Proto 2 production - - A Braem

Trigger counters: bad news discharges, but ...

Pros & Cons of both mini-PMT solutions


Parameter	PMT inside	PMT outside
Volume filling	possible	possible
Light yield	~ 50 P.E.	~ 40 P.E.
Vacuum	discharges from 130 10-5 mbar	leakage rate 3 x 10-6 mbar* l/sec
Handling	PMT exchange possible	PMT exchange simple
Personnel (technician leaves in November)	Proto_2 O.K., other pots unclear	Good chance to finish all trigger plates
4/9/2008	ALFA meeting CERN	



White full

Trigger counters: ... fiber bundle R/O alive

Light yield estimation ...



In the fiducial area one can expect 35 .. 40 P.E.

Ti-plates: good news and concerns

Schedule of Ti-production (M.Jablonski, HU Berlin)

week #11 #14	activity order Ti grade 5 material delivery of material
<<< #18	3 weeks latency requested by workshop >>> start of electro-erosin
<<< #23	5 weeks production time >>> start of milling at HU Berlin and DESY Zeuthen
<<< #26	3 weeks final milling >>> optimistic date to have all ready
Continue	*** End of June *** e with fiber gluing in Giessen and metrology in Hamburg

Precision of OD Ti-milling in Zeuthen

< Zeuthen	> ;	*)	< HH	> **)
Plate A(ideal)	A(real)	differ	A(real)	differ
#1 136.333	136.298	+0.035	136.315	+0.018
			136.307	+0.026
#2 136.500	136.492	+0.008	136.495	+0.005
			136.478	+0.022
#3 136.667	136.648	+0.019	136.656	+0.011
			136.651	+0.016
Plate B(ideal)	B(real)	differ	B(real)	differ
#1 128.533	128.500	+0.033	128.468	+0.065
			128.483	+0.050
#2 128.700	128.660	+0.040	128.687	+0.013
			128.631	+0.069
#3 128.867	128.833	+0.035	128.839	+0.028
			128.832	+0.035
<differences></differences>		+0.028		+0.030
RMS		0.012		0.020

*) J.Bienae

- global offset of ~ 30 micron
- staggering not so much influenced
- waiting for green light from management

Roman Pot mechanics: good news from Prague

Prague February 2008



The four units



Compensation system



Stephane and the 4 units



all vacuum elements




The vacuum chambers




compensation system

Roman Pots: difficult components






- 4 stations arrived at CERN
- Prague people working for stainless steel slides
- measurements of position reproducibility for each station



Electronics: R/O scheme




Orsay: 5 PMFs on one kapton cable tested


→ production of 32 units is going on


Lund: mother board at CERN Mid of May


- → completion
- → debugging



Electronics: 5 PMFs in Orsay tested









Set up used to illuminate all the PM





Electronics: Cross talk ...





Fiber light level: X-talk at ~ 1%






High light level: Long distance X-talk via connectors

Central channel

1st PM neighbour

2nd diagonal PM neighbour

Electronics: S-curves



Conclusions:

- Good homogeneity of the 314 channels out of 320.
- 6 channels out of 320 are shifted.



Electronics: motherboard – most critical

Lund: production → CERN for completion → debugging has started

A few modifications were added before the board submission:


- An ADC has been reinstalled on board. It will be able to read the MAROC analogue outputs (one output selected by demultiplexer)
- The ADC data outputs are connected to the MB FPGA, however the transfer of these data through the optical link and ROD are not defined
- A "trigger" input has been added (to allow readout without the TTC trigger)
- The output data rate from the GOL can be selected between 40Mbits/s or 50Mbits/s: 50Mbits/s is the data rate of the MROD-X hardware

MB Status

Submission for fabrication has been done by Bjorn at Eastern

- Board with components expected at CERN ~ 15 May 2008
- Still a few components to mount at CERN
- Debug at CERN in building 251 (with PMF-2 units)

Metrology: overlap detectors



Resolution based on good knowledge of fiber position

→ metrology in Hamburg (D.Petschull)

 Only gaps between two fibres are measured, not gaps between fibre and solid metal.


15 fibres



14 gaps


Metrology: results


Pitch: gap-to-gap





Pitch – average





- → Resolution of OD due to large statistics of halo tracks
- → Less precision for individual tracks needed DESY-ATLAS meeting

Metrology: problems

 Excess of glue on fibre Might misslead LabView in finding the gap Datei Bearbeiten Aroeigen Brojekt Ausführen Werkoeuge Eenster Hilfe → @ • H Inege 7 8003000D were all gaps found right? 2560×1920 0.5X 9-bit image 70 (1174,966) CE (0 10:00

MAPMTs & HV: DESY contributions

	nv-power for final setup			U. Koetz/Desy 8.5.2008
pmts in q	uestion			
	base [MΩ]	U _{nom} (U _{max}) [V]	I _{nom} (I _{max}) [μΑ]	
R7600 R7400 R9880	2.2 2.8 3.5	800 (1000) 800 (1000) 1000 (1250)	285 (360)	

Present choice

- → DESY delivers HV for prototype-2
- → Patch panel for next test beam (I.Gregor, U.Koetz)

offer from CAEN

1 SY 1527LC

8 + 1 A1535N and 2 A1535SN (24 ch/mod)

total sum 59.256 €

delivery time 90 to 120 days

offer from iseg

8 +1 EDS 20 130n_504 (32 ch/mod)

2 crates (left and right of IP)

fans, PCAN-PCI cards,....

total sum 41.200 €

delivery time 8 to 10 weeks

offer from iseg

14 +1 EDS 20 130n_504 (16 ch/mod)

2 crates

fans, PCAN-PCI cards,...

total sum 79.700 €

delivery time 8 to 10 weeks

Some more good – bad news ...

Good:

- slow control well underway (S.Franz)
- all long cables in tunnel to USA15
- 8 CAEN power supplies ordered / 4 month
- DESY takes care for test beam HV
- some interest of the Krakow group to join ALFA

Bad:

- some short cables missing, many connector not yet ordered
- connection of ALFA to ATLAS interlock
- electronics for main/overlap detectors missing
- rack space in USA15 to check

...list certainly not complete.

Outlook

The ALFA project is based on a vital group of institutions: Berlin, Cracow, CERN, Lisbon, Lund, Giessen, DESY, Manchester, Prague, Stony Brook, Orsay, Valencia
Series of test beam measurements 2005, 2006, 2007 indicates that the design goal can be reached: resolution < 30 µm at 100% trigger efficiency 0(0.1%)
Prototype_1: used for assembling tests Prototype_2: full pot with all final components presently in assembling 4 potential weeks of test beam measurements in July, August 2008
Mass production of 8 pot units plus 2 spares till end of 2008
Installation of 8 Roman pots in shut down 2008/2009
Insert sensitive detector components earliest spring 2009, (→ 2009/2010)
ALFA stations are the test ground for physics upgrade projects RP220, FP420 → installed probably not before long shut down 2013-2015

DESY responsibilities

- 1) MAPMTs: purchase, optical reception test, from marks to shims
- 2) detector metrology: measure central line of each fiber by microscope
- 3) trigger counters: precise $0(10\mu m)$ scintillator tiles + fiber bundles \rightarrow Titanium

Items	Cost	Responsibilities	
Prototypes 2005, 2006, 2007	68	CERN, Giessen	
Fiber tracker	80	Giessen	
Titanium plates	30	Humboldt	TDD language to
Aluminization	40	Lisbon	TDR, known to
Trigger counters	40	DESY	DESY directorate
MAPMTs	310	DESY (125), Prague (50) + 80 PMTs reused from Giessen	
Total ALFA detector	568		
Total with contingency	600		

Total DESY costs ~ 300 EURO

→ DESY project urgently needed