

# **3.9 GHz, 3rd Harmonic 4-Cavity Module Status**

H Edwards/E Harms/T Arkan  
Fermilab

TTC meeting at LAL

16-19, 2009

---

# Outline 3.9GHz Module




- What is it and what will it do?
- Why do it & What has it done for Fermilab?
- Progress, Accomplishments, History
  - Technical progress
    - The steps: Design, Fabrication, Process, Vertical test, Dress, Horizontal test, Module assembly, Infrastructure
- Lessons Learned and Problems encountered
- Schedule - Looking Forward
- Conclusion

# The 3.9GHz cavity module -What is it -what will it do?



- The 3.9GHz module, ACC39, will be installed in the DESY FLASH injector just after the 1.3GHz ACC1 (first) cryomodule.
- It will be used in conjunction with this module in order to linearize the bunch energy vs. time over the bunch length.
- This in turn should make “bunch compression” to very short bunches with high peak currents more efficient, or a more controlled longer bunch charge distribution.
- The SASE FEL operation should become more efficient and stable seeded operation (sFlash) possible.
- This is an important proof of principle not only for FLASH and XFEL but also for accelerator-photon physics, and a learning experience.
- The control of the phase and amplitude of the 1.3-3.9 GHz module pair will be difficult and very important.



# Why Do It & What Has It Done for Fermilab?



- The 3.9GHz effort is part of a collaboration with DESY.
- In this collaboration DESY has advised Fermilab on many of the aspects of SRF development and has supplied design and assembly information.
- In 2007, DESY provided for Fermilab a 1.3GHz Type 3+ module kit. This module was assembled at FNAL by the FNAL personnel with the assistance of DESY experts. The module is being installed in the NML facility.
- The 3.9GHz module has been/will be a learning experience for FNAL in all aspects of beta=1 SRF cavity and module design through commissioning.
- Successful completion will clearly show Fermilab's growing competence and abilities in SRF technology.
- It is important that we learn and benefit for our experiences and "Lessons Learned".



# 3.9GHz Overview Photos



# Infrastructure



- Some old and some new
  - Old - A0 SRF R&D Infrastructure:
    - Modest, built up over the years
      - Soft wall clean room
      - UV water & Ultrasonic bath
      - High Pressure Rinse
      - Vertical test (short dewar)
      - RF systems (1.3 & 3.9)



- New - set up for 1.3GHz & also used for 3.9GHz
  - Horizontal Test Stand (HTS) at Meson (MDB)
  - String and Cold mass assembly at Cryomodule Assembly Facility (CAF)



# Cavity Fabrication Steps



- Documents on Cavity and Helium Vessel Fabrication and Welding by M. Foley, et al
  - 3.9GHz Cavity Fabrication Specification
    - Material
    - Blanks for half cells
    - Fabrication of Components
    - End Assemblies
    - Welding of Cavity
    - Final Test of Cavity
  - Procedures for Welding Helium Vessels to 3.9 GHz Cavities
    - Preparation for Electron Beam welding
    - Electron Beam Welding
    - Preparation for TIG Welding
    - Final TIG welding
    - E-beam Weld Parameters
    - TIG Weld Parameters


# Fabrication and Processing Steps



- Table of processing steps by A. Rowe, et al
  - About 200 steps after fabrication
- Outline
  - Preliminary Processing Sequence
    - Preliminary Preparation
    - External Surface Preparation
    - Internal Bulk Surface Preparation
    - Hydrogen Degasification
    - RF tuning
  - Vertical Test Processing Sequence
    - Internal Surface Preparation
    - 1st Vertical Test
    - 2nd Vertical Test
  - Titanium Helium Vessel Welding
  - Horizontal Test Processing Cycle



# Cavity fabrication, BCP, HPR, Vertical Test



Bare 3.9 cavity



Weld



BCP etch



Hi Press Rinse

Vertical test & dewar



Vertical test control area



# Helium vessel welding Dressed Cavity to HTS



# String and Module Assembly Steps



- Assembly Travelers by T. Arkan, M. McGee, D. Olis, et al
  - Assembly QA Traveler
  - Cavity String Assembly
  - Cold Mass Assembly Parts 1-3
  - Final Assembly Traveler
  - Shipping Document
  - Warm Coupler Assembly Document

# 3.9GHz Module Assembly



Assembled cavity string



Various group working on the cold mass assembly



Cold Mass being prepared for transport



Cold Mass transport

# 3.9GHz Module Assembly



Cold mass to Big Bertha



Completed Cold Mass



Cold Mass at Big Bertha




Cold Mass to the Vacuum Vessel assembly

# Warm/Low power RF Measurements


## T. Khabibouline





Cavity 5 frequency history




modes



3.9 GHz Cavity F3A5 Performance Surface Resistance







# 3.9GHz Cavity Vertical Tests



# Cav 3,5,7,8 Horizontal Test Results at HTS



★  
Design Gradient  
14MV/m





# Schedule Highlights - past



- 2002 TESLA Facility Phase 2 Report with 3.9 GHz module for bunch compression (TESLA-FEL 2002-01)
- 2002-3 Cavity design documents (TESLA-FEL 2002-05, 2003-01/FNAL TM 2210)
- 2005 DESY-FNAL MOU on 3.9 module
- 2006, 03-06 C1,C2 failures, Multipacting & HOM wall thickness
- 2006, 08 **F3A3 fabrication finished-** first usable cavity
- 2007, 05 **F3A3 good vertical test** after HOM formteils cut, 24MV/m
- 2007, 10 F3A5 vertical tests with HOM feed-throughs complete 19MV/m
- 2008, 02-09 F3A5 in horizontal test stand (HTS)
- 2008, 04 **F3A5 achieved 22.5MV/m in HTS**
- 2008, 12 F3A8 last cavity of four removed from HTS
- 2009, 01 String assembled in CAF-MP9 Clean Room
- 2009, 02 Cold mass to CAF-ICB
- 2009, 04 **Module finished** and shipped to DESY

2002 to 2009 - start to ship - for module tests at DESY

# Problems & Lessons Learned



- Technical issues
  - HOM design and multipacting - 1-post redesign for F3A7, F3A8
  - HOM antennae feed-throughs: followed JLab type design
  - Titanium Helium vessel weld design, welding and Titanium pipe welding
- Infrastructure issues
  - e- Beam welder availability
  - BCP etch availability, FNAL & ANL
  - HTS commissioning
  - Maintenance of effective CR, HPR, and Cryo systems at A0
- Procedural issues
  - Pressure vessel testing and Engineering note, ORC:
    - Fermilab is learning to deal with the safety aspects of SRF testing (non-ASME materials, etc.). The 3.9GHz effort, especially the HTS step, played a pioneering role in the format and content of Engineering notes and approval to cooldown and power test SRF cavities. At times a frustrating process (~6 months for HTS approval), but the need is also understood. Organizationally, Fermilab is now better poised and taking strategic steps for future operations.

# Still to Do



- Spare cavities
  - Qualify F3A4 & F3A6 as spares
  - Complete F3A9 fabrication and subsequent steps
- Summary Report of RF tests and measurements for each cavity (in progress)
  - History overview for assembly, process, measure and test
  - Warm and mechanical measurements
  - Vertical test summary
  - Horizontal test summary
  - Final tests
- Summary Report of Technical Designs (in progress)
  - Accelerator physics use of 3.9 GHz module
  - RF design of cavities, input couplers, HOM couplers,
  - Thermal analysis
  - Cavity assembly and processing steps.

# Update on Module after Arrival at DESY-1




- Transportation shock log data good, maximum 1.2 g differential.
- Vacuum was maintained during transport. String is leak-tight ( $10^{-8}$  Torr at pump).
- One heat shield interference found and corrected (80K coupler shield to 4K module shield).
- Survey comparison FNAL->DESY excellent:
  - Cavity targets as a group comparison, max difference 0.16mm
  - Relative to cold mass max difference 0.28mm
  - Measurement accuracy  $\sim 0.15$ mm
- One warm-end input coupler piece was test fitted by DESY and FNAL people.
- Instrumentation and cavity frequency checks are ok.

# Update on Module after Arrival at DESY-2



- Some cavity support bearing housings, “C channels”, were found out of position, others not accessible in the module to check. Likely occurred during alignment of the cavities.
- Cold Mass assembly was removed at DESY and moved ~4mm upstream. C-channels now all in position.
- Cold Mass is back in vacuum vessel as of 10-06-09. FNAL personnel assisted DESY colleagues during re-assembly.
- Coupler installation planned for week of 22 June with DESY and FNAL personnel.



# 3.9GHz Schedule Highlights – Future



May-June '09	Module fix and coupler installation
May - Sept '09	Preparation of Cryo Mod Test Bench (CMTB) at DESY for 3.9 test
Oct - Nov '09	Installation and check out of module at CMTB
Oct - Dec '09	Test ACC39 at CMTB
Sept 09 - Feb '10	FLASH shutdown
Dec 09 - Feb '10	ACC39 installation in FLASH
March '10	Technical commissioning of ACC39 in FLASH
Apr - June '10	Beam commissioning in FLASH
Summer '10	User operation

**We must still show that the cavities work in the module at DESY test facility and TTF/FLASH.**

# Conclusions



- The 3.9 module has been an important and fundamental learning experience for FNAL in all areas of SRF technology.
- This is the 1st 3.9 GHz module built anywhere.
- Cooperation across the Fermilab organization was vital to accomplish this. New players have been recruited and trained.
- Successful lasing results from FLASH will be an important step of R&D to the accelerator field in general and illustrates the importance of accelerator developments & applications across different end user facilities. (e.g. Hi Energy, Nuclear, Materials,...)